VISIT…

Computer Graphics for Java Programmers, Second Edition

byLeen AmmeraalandKang Zhang

John Wiley & Sons
2007 (386 pages)
ISBN:9780470031605

Covering elementary concepts in creating and manipulating 2D and 3D graphical objects, this book

presents topics from classic graphics algorithms to perspective drawings and hidden-line elimination.

Table of Contents

Computer Graphics for Java Programmers, Second Edition

Preface

Chapter 1 - Elementary Concepts

Chapter 2 - Applied Geometry

Chapter 3 - Geometrical Transformations
Chapter 4 - Some Classic Algorithms
Chapter 5 - Perspective
Chapter 6 - Hidden-Line Elimination
Chapter 7 - Hidden-Face Elimination
Chapter 8 - Fractals
Appendix A - Linear Interpolation of 1/z
Appendix B - A Note on Event Handling

Appendix C - File Obj3D.java
Appendix D - Class CvHLines.java
Appendix E - Some Applications
Appendix F - Hints and Solutions to Exercises
Bibliography
Colour Plates
Index
List of Figures
List of Code Examples

Back Cover

A great many varied and interesting visual effects can be achieved with computer graphics, for which a fundamental understanding of the underlying mathematical concepts – and a knowledge of how they can be implemented in a particular programming language – is essential.

Computer Graphics for Java Programmers, 2nd edition covers elementary concepts in creating and manipulating 2D

and 3D graphical objects, covering topics from classic graphics algorithms to perspective drawings and hidden-line elimination.

Completely revised and updated throughout, the second edition of this highly popular textbook contains a host of ready-to-run-programs and worked examples, illuminating general principles and geometric techniques. Ideal for classroom use or self-study, it provides a perfect foundation for programming

computer graphics using Java.

About the Authors

Leen Ammeraal is a retired lecturer of Hogeschool Utrecht, The Netherlands, where he was employed from 1977 to 1998. He has a degree (ir.) in mathematics at University of Technology Delft, The Netherlands. He worked as a programmer and mathematician at Akzo Research and Engineering, Arnhem, The Netherlands, from 1961 to 1972 and did

research work on compilers from 1972 to 1977 at Mathematical Centre, Amsterdam. He wrote many books for Wiley (as well as for the Dutch publisher Academic Service). Some of his Wiley books have been translated into other languages (Japanese, Russian, Italian, French, German, Greek, Danish, Portuguese, Bulgarian).

Kang Zhang is a Professor in Computer Science and Director of Visual Computing Lab at the

University of Texas at Dallas. He received his B.Eng. in Computer Engineering from the University of Electronic Science and Technology, China, in 1982; and Ph.D. from the University of Brighton, UK, in 1990. He held academic positions in the UK and Australia, prior to joining UTD. Zhang's current research interests are in the areas of visual languages, graphical visualization, and Web engineering; and has published over 130 papers in these areas. He has taught

computer graphics and related subjects at both graduate and undergraduate levels for many years. Zhang was also an editor of two books on software visualization.

Computer Graphics for Java Programmers, Second Edition

Leen Ammeraal
Hogeschool Utrecht

Kang Zhang
University of Texas at Dallas

John Wiley & Sons, Ltd

© 2007 John Wiley & Sons Ltd

The Atrium, Southern Gate,
Chichester,
West Sussex PO19 8SQ,
England

Telephone (+44) 1243 779777

First published 1998 (0-471-98142-7)

Email (for orders and customer service enquiries): cs-books@wiley.co.uk Visit our Home Page on http://www.wiley.com

All Rights Reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning or otherwise,

except under the terms of the Copyright, Designs and Patents Act 1988 or under the terms of a licence issued by the Copyright Licensing Agency Ltd, 90 Tottenham Court Road, London W1T 4LP, UK, without the permission in writing of the Publisher. Requests to the Publisher should be addressed to the Permissions Department, John Wiley & Sons Ltd, The Atrium, Southern Gate, Chichester, West Sussex PO19 8SQ, England, or emailed to permreq@wiley.co.uk, or faxed to (+44) 1243 770620.

Designations used by companies to distinguish their products are often claimed as trademarks. All brand names and product names used in this book are trade names, service marks, trademarks or registered trademarks of their respective owners. The Publisher is not associated with any product or vendor mentioned in this book.

This publication is designed to provide accurate and authoritative information in regard to the subject matter covered. It is sold on the understanding that the Publisher is not engaged in

rendering professional services. If professional advice or other expert assistance is required, the services of a competent professional should be sought.

Other Wiley Editorial Offices

John Wiley & Sons Inc., 111 River Street, Hoboken, NJ 07030, USA

Jossey-Bass, 989 Market Street, San Francisco, CA 94103-1741, USA

Wiley-VCH Verlag GmbH, Boschstr. 12, D-69469 Weinheim, Germany

John Wiley & Sons Australia Ltd, 42 McDougall Street, Milton, Queensland 4064, Australia

John Wiley & Sons (Asia) Pte Ltd, 2 Clementi Loop #02-01, Jin Xing Distripark, Singapore 129809

John Wiley & Sons Canada Ltd, 6045 Freemont Blvd, Mississauga, ONT, L5R 4J3, Canada

Wiley also publishes its books in a variety of electronic formats.

Library of Congress

Cataloging-in-Publication Data

Ammeraal, L. (Leendert)

Computer graphics for Java programmers / Leen Ammeraal.
– 2nd ed.
p. cm.
Includes bibliographical references.

ISBN-13 978-0-470-03160-5 (alk. paper)
0-470-03160-3

1. Computer graphics. 2. Java (Computer program language) I. Title.

T385.A488 2007
006.6 63 – dc22

2006029327

British Library Cataloguing in Publication Data

A catalogue record for this book is available from the British Library
13: 978-0-470-03160-5

(PB) ISBN-10: 0-470-03160-3 (PB)

Preface

During the eight years since the publication of the first edition of *Computer Graphics for Java Programmers*, the programming language Java has increasingly become the language of choice in many industrial and business domains. Hence the skills for developing computer graphics applications using Java have been highly in demand but are surprisingly lacking in the computer science curricula. Meanwhile, for the past five years the second author has

been teaching Computer Graphics at his current university using the first edition of this textbook, and felt that there was a need to update the book. We therefore decided to jointly write this second edition.

This edition continues the main theme of the first edition, that is, graphics programming in Java, with plenty of source code available to the reader. The new edition has, however, been updated as follows:

1. The contents of some chapters have been

updated, as a result of the authors' years of classroom experience and recent feedback from our students.

2. An instructor's manual has been created to include lecture slides and answers to exercise questions.

3. Chapter 8 has been replaced by a new chapter covering the topic of fractals.

4. A beta version of a

companion software package has been added, which demonstrates the working of different algorithms and concepts introduced in the book.

5. More illustrative examples have been included in several chapters and various minor errors in the first edition have been corrected.

Over the past few years, Java

has evolved into more powerful programming environments. The most notable development related to computer graphics is its support for 3D graphics. Many application examples illustrated in this book could be readily implemented using Java 3D without any understanding of the internal working of the implementation, which we consider undesirable for computer science students. We therefore believe that this textbook continues to serve as an indispensable introduction to the foundation of computer graphics,

on which many application program interfaces (APIs) and graphics libraries could be developed, and more importantly, *how* they are developed.

As in the first edition, the example programs can again be downloaded from the Internet at:

`http://home.planet.nl/~amm`

or at:

`http://www.utdallas.edu/~k`

In writing this second edition, several people need to be acknowledged for their direct or indirect contributions. We would

first like to thank the UT-Dallas graduate students Bill Fahle, Andy Restrepo, Janis Schubert, and Subramanya Suresh, who contributed to different parts of the demonstration software. In particular, we appreciate the great effort of Janis Schubert in developing and integrating different parts of the software while striving to maintain the same look and feel of the user interfaces. Finally, we thank Jonathan Shipley of John Wiley and Sons for his enthusiastic support and assistance in publishing this edition.

Leen Ammeraal, The Netherlands
l.ammeraal@hccnet.nl

Kang Zhang, USA
kzhang@utdallas.edu

Chapter 1: Elementary Concepts

This book is primarily about graphics programming and mathematics. Rather than discussing general graphics subjects for end users or how to use graphics software, we will deal with more fundamental subjects, required for graphics programming. In this chapter, we will first understand and appreciate the nature of discreteness of displayed graphics on

computer screens. We will then see that *x*- and *y*-coordinates need not necessarily be pixel numbers, also known as device coordinates. In many applications logical coordinates are more convenient, provided we can convert them to device coordinates. Especially with input from a mouse, we also need the inverse conversion, as we will see at the end of this chapter.

1.1 LINES, COORDINATES AND PIXELS

The most convenient way of specifying a line segment on a computer screen is by providing the coordinates of its two endpoints. In mathematics, coordinates are real numbers, but primitive line-drawing routines may require these to be integers. This is the case, for example, in the Java language, which we will use in this book. The Java Abstract Windows Toolkit (AWT) provides the class *Graphics*

containing the method *drawLine*, which we use as follows to draw the line segment connecting A and B:

```
g.drawLine(xA, yA, xB, yB)
```

The graphics context *g* in front of the method is normally supplied as a parameter of the *paint* method we are using, and the four arguments of *drawLine* are integers, ranging from zero to some maximum value. The above call to *drawLine* produces exactly the same line as this one:

```
g.drawLine(xB, yB, xA, yA)
```

We will now use statements such as the above one in a complete Java program. Fortunately, you need not type these programs yourself, since they are available from the Internet, as specified in the Preface. It will also be necessary to install the Java Development Kit (JDK), which you can also download, using the following Web page:

`http://java.sun.com/`

If you are not yet familiar with Java, you should consult other books, such as some mentioned in the Bibliography, besides this

one.

The following program draws the largest possible rectangle in a canvas. The color red is used to distinguish this rectangle from the frame border:

```
// RedRect.java: The large
import java.awt.*;
import java.awt.event.*;

public class RedRect exten
{  public static void main

   RedRect()
   { super("RedRect");
     addWindowListener(new
     {public void windowCl
```

```
        setSize (200, 100);
        add("Center", new CvRe
        show();

    }

}

class CvRedRect extends Ca
{ public void paint(Graphi
    { Dimension d = getSize(
        int maxX = d.width - 1
        g.drawString("d.width
        g.drawString("d.height
        g.setColor(Color.red);
        g.drawRect(0, 0, maxX,
    }
}
```

The call to *drawRect* almost at the end of this program has the same effect as these four lines:

```
g.drawLine(0, 0, maxX, 0);
g.drawLine(maxX, 0, maxX,
g.drawLine(maxX, maxY, 0,
g.drawLine(0, maxY, 0, 0);
```

The program contains two classes:

RedRect: The class for the frame, also used to close the application.

CvRedRect: The class for the canvas, in which we display graphics

output.

However, after compiling the program by entering the command

```
javac RedRect.java
```

we notice that three class files have been generated: *RedRect.class*, *CvRe-dRect.class* and *RedRect*$1*.class*. The third one is referred to as an *anonymous class* since it has no name in the program. It is produced by the two program lines

```
addWindowListener(new Winc
```

```
    {public void windowClos
```

which enable the user of the program to terminate it in the normal way. We could have written the same program code as

```
addWindowListener
( new WindowAdapter()
   {  public void windowClc
      {  System.exit(0);
      }
   }
);
```

to show more clearly the structure of this fragment. The argument of the method

addWindowListener must be an object of a class that implements the interface *WindowListener*. This implies that this class must define seven methods, one of which is *windowClosing*. The base class *WindowAdapter* defines these seven methods as do-nothing functions. In the above fragment, the argument of *addWindowListener* denotes an object of an anonymous subclass of *WindowAdapter*. In this subclass we override the method *windowClosing*. A further discussion of this compact program code for event handling

can be found in Appendix B.

The *RedRect* constructor shows that the frame size is set to 200 × 100. If we do not modify this size (by dragging a corner or an edge of the window), the canvas size is somewhat less. After compilation, we run the program by typing the command

```
java RedRect
```

which produces the output shown in Figure 1.1.



Figure 1.1: Largest possible rectangle and canvas dimensions

The blank area in a frame, which we use for graphics output, is referred to as a *client rectangle* in Microsoft Windows programming. We will consistently use a *canvas* for it, which is a subclass, such as

CvRedRect in program *RedRect.java*,of the AWT class *Canvas*. If, instead, we displayed the output directly in the frame, we would have a problem with the coordinate system: its origin would be in the top-left corner of the *frame*; in other words, the *x*-coordinates increase from left to right and *y*-coordinates from top to bottom. Although there is a method *getInsets* to obtain the widths of all four borders of a frame so that we could compute the dimensions of the client rectangle ourselves, we prefer to use a canvas.

The tiny screen elements that we can assign a color are called *pixels* (short for *picture elements*), and the integer *x*-and *y*-values used for them are referred to as *device coordinates*. Although there are 200 pixels on a horizontal line in the entire frame, only 192 of these lie on the canvas, the remaining 8 being used for the left and right borders. On a vertical line, there are 100 pixels for the whole frame, but only 73 for the canvas. Apparently, the remaining 27 pixels are used for the title bar and for the top and

bottom borders. Since these numbers may differ in different Java implementations and the user can change the window size, it is desirable that our program can determine the canvas dimensions. We do this by using the *getSize* method of the class *Component*, which is a superclass of *Canvas*. The following program lines in the paint method show how we obtain the canvas dimensions and how we interpret them:

```
Dimension d = getSize();
int maxX = d.width - 1, ma
```

The *getSize* method of *Component* (a superclass of *Canvas*) supplies us with the numbers of pixels on horizontal and vertical lines of the canvas. Since we begin counting at zero, the highest pixel numbers, *maxX* and *maxY*, on these lines are one less than these numbers of pixels. Remember that this is similar with arrays in Java and C. For example, if we write

```
int[] a = new int[8];
```

the highest possible index value is 7, not 8. Figure 1.2 illustrates this for a very small canvas,

which is only 8 pixels wide and 4 high, showing a much-enlarged screen grid structure. It also shows that the line connecting the points (0, 0) and (7, 3) is approximated by a set of eight pixels.



Figure 1.2: Pixels as

coordinates in an 8 × 4 canvas (with *maxX* = 7 and *maxY* = 3)

The big dots approximating the line denote pixels that are set to the foreground color. By default, this foreground color is black, while the background color is white. These eight pixels are made black as a result of this call:

```
g.drawLine (0, 0, 7, 3);
```

In the program *RedRect.java*, we used the following call to the *drawRect* method (instead of four

calls to *drawLine*):

```
g.drawRect(0, 0, maxX, max
```

In general, the call

```
g.drawRect(x, y, w, h);
```

draws a rectangle with (*x*, *y*) as its top-left and (*x* + *w*, *y* + *h*) as its bottom-right corners. In other words, the third and fourth arguments of the *drawRect* method specify the width and height, rather than the bottom-right corner, of the rectangle to be drawn. Note that this rectangle is *w* + 1 pixels wide and *h* + 1 pixels high. The

smallest possible square, consisting of 2 × 2 pixels, is drawn by this call

```
g.drawRect(x, y, 1, 1);
```

To put only one pixel on the screen, we cannot use *drawRect*, because nothing at all appears if we try to set the third and fourth arguments of this method to zero. Curiously enough, Java does not provide a special method for this purpose, so we have to use this call:

```
g.drawLine(x, y, x, y);
```

Note that the call

```
g.drawLine(xA, y, xB, y);
```

draws a horizontal line consisting of | *xB* − *xA* |+1 pixels.

1.2 THE BOUNDARIES OF FILLED REGIONS

In mathematics, lines are continuous and have no thickness, but they are discrete and at least one pixel thick in our graphics output. This difference in the interpretation of the notion of lines may not cause any problems if the pixels are very small in comparison with what we are drawing. However, we should be aware that there may be such problems in special cases, as Figure 1.3(a) illustrates. Suppose that we have to draw a filled

square ABCD of, say, 4×4 pixels, consisting of the bottom-right triangle ABC and the upper-left triangle ACD, which we want to paint in dark gray and light gray, respectively, without drawing any lines. Strangely enough, it is not clear how this can be done: if we make the diagonal AC light gray, triangle ABC contains fewer pixels than triangle ACD; if we make it dark gray, it is the other way round.



Figure 1.3: Small filled regions

A much easier but still non-trivial problem, illustrated by Figure 1.3(b), is filling the squares of a checker-board with, say, dark and light gray squares instead of black and white ones. Unlike squares in mathematics, those on the computer screen deserve

special attention with regard to the edges belonging or not belonging to the filled regions. We have seen that the call

```
g.drawRect(x, y, w, h);
```

draws a rectangle with corners (*x*, *y*) and (*x* + *w*, *y* + *h*). The method *fillRect*, on the other hand, fills a slightly smaller rectangle. The call

```
g.fillRect(x, y, w, h);
```

assigns the current foreground color to a rectangle consisting of *w* × *h* pixels. This rectangle has (*x*, *y*) as its top-left and (*x* + *w* –

1, $y + h - 1$) as its bottom-right corner. To obtain a generalization of Figure 1.3(b), the following method, *checker*, draws an $n \times n$ checker board, with (x, y) as its top-left corner and with dark gray and light gray squares, each consisting of $w \times w$ pixels. The bottom-left square will always be dark gray because for this square we have $i = 0$ and $j = n - 1$, so that $i + n - j = 1$:

```
void checker(Graphics g, i
{  for (int i=0; i<n; i++)
       for (int j=0; j<n; j
       {  g.setColor((i + n
              Color.lightGra
```

```
                g.fillRect(x + i
            }

}
```

If we wanted to draw only the edges of each square, also in dark gray and light gray, we would have to replace the above call to *fillRect* with

```
g.drawRect(x + i * w, y +
```

in which the last two arguments are $w - 1$ instead of w.

1.3 LOGICAL COORDINATES

1.3.1 The Direction of the Y-axis

As Figure 1.2 shows, the origin of the device-coordinate systems lies at the top-left corner of the canvas, so that the positive *y*-axis points downward. This is reasonable for text output, where we start at the top and increase *y* as we go to the next line of text. However, this direction of the *y*-axis is different from normal

mathematical practice and therefore often inconvenient in graphics applications. For example, in a discussion about a line with a positive slope, we expect to go upward when we move along this line from left to right. Fortunately, we can arrange for the positive *y* direction to be reversed by performing this simple transformation:

$$y' = maxY - y$$

1.3.2 Continuous vs. Discrete Coordinates

Instead of the discrete (integer) coordinates we are using at the lower, device-oriented level, we want to use continuous (floating-point) coordinates at the higher, problem-oriented level. Other usual terms are *device* and *logical* coordinates, respectively. Writing conversion routines to compute device coordinates from the corresponding logical ones and vice versa is a bit tricky. We must be aware that there are two solutions to this problem, even in the simple case in which increasing a logical coordinate by one results in increasing the

device coordinate also by one. We want to write the following methods:

iX(*x*), *iY*(*y*): the device coordinates of the point with logical coordinates *x* and *y*;

fx(*x*), *fy*(*y*): the logical coordinates of the point with device coordinates *x* and *y*.

With regard to *x*-coordinates, the first solution is based on *rounding*:

```
int iX(float x){return Mat
float fx(int x){return (fl
```

For example, with this solution we have

$$iX(2.8) = 3 \text{ and } fx(3) = 3.0$$

The second solution is based on *truncating*:

```
int iX(float x){return (in
float fx(int x){return (fl
```

With these conversion functions, we would have

$$iX(2.8) = 2 \text{ and } fx(2) = 2.5$$

With both solutions, the

difference between any value *x* and *fx*(*iX*(*x*)) is not greater than 0.5. We will use the first solution throughout this book, since it is the better one if logical coordinates frequently happen to be integer values. In these cases the practice of truncating floating-point numbers will often lead to worse results than we would have with rounding.

Besides the above methods *iX* and *fx* (based on the first solution) for *x*-coordinates, we need similar methods for *y*-coordinates, taking into account

the opposite directions of the two *y*-axes. At the bottom of the canvas the device *y*-coordinate is *maxY* while the logical *y*-coordinate is 0, which may explain the two expressions of the form *maxY* − … in the following methods:

```
int iX(float x){return Mat
int iY(float y){return max
float fx(int x){return (fl
float fy(int y){return (fl
```

Figure 1.4 shows a fragment of a canvas, based on *maxY* = 16.



Figure 1.4: Logical and device coordinates, based on *ymax* = 16

The pixels are denoted as black dots, each placed in the center of a square of dashed lines. In this

discussion and elsewhere in this book, let us write *x* and *y* for logical and *X* and *Y* for device coordinates. (Since it is customary in Java to use lower-case letters at the beginning of variable names, we will not write *X* and *Y* in program text.) In Figure 1.4, the device-coordinates (*X*, *Y*)are placed between parentheses near each dot. For example, the pixel with device coordinates (8, 2), at the upper-right corner of this canvas fragment, has logical coordinates (8.0, 14.0). We have

```
iX (8.0) = Math.round (8.0
```

```
iY (14.0) = 16 - Math.roun
fx (8) = (float)8 = 8.0
fy (2) = (float) (16 - 2)
```

The dashed square around this dot denotes all points (*x*, *y*) satisfying

$$7.5 \leq x < 8.5$$

$$13.5 \leq y < 14.5$$

All these points are converted to the pixel (8, 2) by our methods *iX* and *iY*.

Let us demonstrate this way of converting floating-point logical coordinates to integer device

coordinates in a program that begins by drawing an equilateral triangle ABC, with the side AB at the bottom and the point C at the top. Then, using

$$q = 0.05\ p = 1 - q = 0.95$$

we compute the new points A′ , B ′ and C′ near A, B and C and lying on the sides AB, BC and CA, respectively, writing

```
xA1 = p * xA + q * xB;
yA1 = p * yA + q * yB;
xB1 = p * xB + q * xC;
yB1 = p * yB + q * yC;
```

```
xC1 = p * xC + q * xA;
yC1 = p * yC + q * yA;
```

We then draw the triangle A′ B′ C′, which is slightly smaller than ABC and turned a little counter-clockwise. Applying the same principle to triangle A′ B′ C′ to obtain a third triangle, A″ B″ C″, and so on, until 50 triangles have been drawn, the result will be as shown in Figure 1.5.



Figure 1.5: Triangles drawn inside each other

If we change the dimensions of the window, new equilateral triangles appear, again in the

center of the canvas and with dimensions proportional to the size of this canvas. Without floating-point logical coordinates and with a *y*-axis pointing downward, this program would have been less easy to write:

```
// Triangles.java: This pr
import java.awt.*;
import java.awt.event.*;
public class Triangles ext
{  public static void main

   Triangles()
   {  super("Triangles: 50
      addWindowListener(ne
         {public void winc
      setSize (600, 400);
```

```
        add("Center", new Cv
        show();

    }
}

class CvTriangles extends
{   int maxX, maxY, minMaxX

    void initgr()
    {   Dimension d = getSiz
        maxX = d.width - 1;
        minMaxXY = Math.min(
        xCenter = maxX/2; yC
    }
    int iX(float x){return
    int iY(float y){return

    public void paint(Graph
```

```
{ initgr();
  float side = 0.95F *
     h = sideHalf * (fl
     xA, yA, xB, yB, xC
     xA1, yA1, xB1, yB1
  q = 0.05F;
  p = 1 - q;
  xA = xCenter - sideHa
  yA = yCenter - 0.5F *
  xB = xCenter + sideHa
  yB = yA;
  xC = xCenter;
  yC = yCenter + 0.5F *
  for (int i=0; i<50; i
  { g.drawLine(iX(xA),
    g.drawLine(iX(xB),
    g.drawLine(iX(xC),
    xA1 = p * xA + q *
    yA1 = p * yA + q *
```

```
            xB1 = p * xB + q *
            yB1 = p * yB + q *
            xC1 = p * xC + q *
            yC1 = p * yC + q *
            xA = xA1; xB = xB1;
            yA = yA1; yB = yB1;
        }
    }
}
```

In the canvas class *CvTriangles* there is a method *initgr*. Together with the other program lines that precede the *paint* method in this class, *initgr* may also be useful in other programs.

It is important to notice that, on each triangle edge, the computed

floating-point coordinates, not the integer device coordinates derived from them, are used for further computations. This principle, which applies to many graphics applications, can be depicted as follows:



which is in contrast to the following scheme, which we should avoid. Here *int* device coordinates containing rounding-off errors are used not only for graphics output but also for

further computations, so that such errors will accumulate:



In summary, we compare and contrast the logical and device coordinate systems in the following table, in terms of (1) the convention used in the text, but not in Java programs, of this book; (2) the data types of the programming language; (3) the coordinate value domain; and (4) the direction of the positive *y*-axis:

Open table as spreadsheet

Coordinate system	Convention	Data type
logical	lower-case letters	float
device	upper-case letters	integ

1.4 ANISOTROPIC AND ISOTROPIC MAPPING MODES

1.4.1 Mapping a Continuous Interval to a Sequence of Integers

Suppose we want to map an interval of real logical coordinates, such as

$$0 \leq x \leq 10.0$$

to the set of integer device coordinates {0, 1, 2, … ,9}.

Unfortunately, the method

```
int iX(float x){return Mat
```

used in the previous section is not suitable for this purpose because for any *x* greater than 9.5 (and not greater than 10) it returns 10, which does not belong to the allowed sequence 0, 1, …, 9. In particular, it gives

```
ix (10.0) = 10
```

while we want

```
ix (10.0) = 9
```

This suggests that in an improved method *iX* we should use a

multiplication factor of 0.9. We can also come to this conclusion by realizing that there are only nine small intervals between ten pixels labeled 0, 1, …, 9, as Figure 1.6 illustrates. If we define the pixel width (= *pixelWidth*) as the distance between two successive pixels on a horizontal line, the above interval $0 \leq x \leq 10$ of logical coordinates (being real numbers) corresponds to $9 \times$ *pixelWidth*. So in this example we have:

$$9 \times \textit{pixelWidth} = 10.0 \text{(the length of the interval of logical coordinates)}$$

$$\textit{pixelWidth} = 10/9 = 1.111\ldots$$



Figure 1.6: Pixels lying 10/9 logical units apart

In general, if a horizontal line of our window consists of *n* pixels, numbered 0, 1, …, *maxX* (where *maxX* = *n* − 1), and the corresponding (continuous) interval of logical coordinates is 0

$\leq x \leq$ *rWidth*, we can use the following method:

```
int iX(float x){return Mat
```

where *pixelWidth* is computed beforehand as follows:

```
maxX = n - 1;
pixelWidth = rWidth/maxX;
```

In the above example the integer *n* is equal to the interval length *rWidth*, but it is often desirable to use logical coordinates *x* and *y* satisfying

$$0 \leq x \leq rWidth$$

$$0 \leq y \leq rHeight$$

where *rWidth* and *rHeight* are real numbers, such as 10.0 and 7.5, respectively, which are quite different from the numbers of pixels that lie on horizontal and vertical lines. It will then be important to distinguish between *isotropic* and *anisotropic mapping modes*, as we will discuss in a moment.

As for the simpler method

```
int iX(float x){return Mat
```

of the previous section, this can be regarded as a special case of the improved method we have just seen, provided we use

pixelWidth = 1, that is *rWidth* = *maxX*,or *rWidth* = $n - 1$. For example, if the drawing rectangle is 100 pixels wide, so that n = 100 and we can use the pixels 0, 1, 2, …, 99 = *maxX* on a horizontal line, this simpler method *iX* works correctly if it is applied to logical *x*-coordinates satisfying

$$0 \leq x \leq rWidth = 99.0$$

The point to be noticed is that, due to the value *pixelWidth* = 1, the logical width is 99.0 here although the number of available pixels is 100.

1.4.2 Anisotropic Mapping Mode

The term *anisotropic mapping mode* implies that the scale factors for *x* and *y* are not necessarily equal, as the following code fragment shows:

```
Dimension d = getSize();
maxX = d.width - 1; maxY =
pixelWidth  = rWidth/maxX;
pixelHeight = rHeight/maxY
...
int iX(float x){return Mat
int iY(float y){return max
float fx(int x){return x *
float fy(int y){return (ma
```

We will use this in a demonstration program. Regardless of the window dimensions, the largest possible rectangle in this window has the logical dimensions 10.0 × 7.5. After clicking on a point of the canvas, the logical coordinates are shown, as Figure 1.7 illustrates.



Figure 1.7: Logical

coordinates with anisotropic mapping mode

Since there are no gaps between this largest possible rectangle and the window edges, we can only see this rectangle with some difficulty in Figure 1.7. In contrast, the screen will show this rectangle very clearly because we will make it red instead of black. Although the window dimensions in Figure 1.7 have been altered by the user, the logical canvas dimensions are still 10.0 × 7.5. The text displayed in the window shows

the coordinates of the point near the upper-right corner of the rectangle, as the cross-hair cursor indicates. If the user clicks exactly on that corner, the coordinate values 10.0 and 7.5 are displayed. This demonstration program is listed below.

```
// Anisotr.java: The anisc

import java.awt.*;
import java.awt.event.*;

public class Anisotr exten
{  public static void main

   Anisotr()
```

```
    { super("Anisotropic ma
      addWindowListener(new
        {public void windo
      setSize (400, 300);
      add("Center", new CvA
      setCursor(Cursor.getP
      show();
    }

}

class CvAnisotr extends Ca
{ int maxX, maxY;
  float pixelWidth, pixelH
        rWidth = 10.0F,
        rHeight = 7.5F,
        xP = -1, yP;

  CvAnisotr()
```

```
   { addMouseListener(new M
     { public void mousePre
       { xP = fx(evt.getX()
         repaint();
       }
     });
}
void initgr()
{ Dimension d = getSize();
  maxX = d.width - 1; maxY
  pixelWidth = rWidth/maxX
}

int iX(float x){return Mat
int iY(float y){return max
float fx(int x){return x *
float fy(int y){return (ma

public void paint(Graphics
```

```
{ initgr();
    int left = iX (0), rig
      bottom = iY (0), top
    if (xP >= 0) g.drawStr
       "Logical coordinate
       + xP + " " + yP, 20
    g.setColor(Color.red);
    g.drawLine(left, bottc
    g.drawLine(right, bott
    g.drawLine(right, top,
    g.drawLine(left, top,
  }
}
```

With the anisotropic mapping mode, the actual length of a vertical unit can be different from that of a horizontal unit. This is the case in Figure 1.7: although

the rectangle is 10 units wide and 7.5 units high, its real height is less than 0.75 of its width. In particular, the anisotropic mapping mode is not suitable for drawing squares, circles and other shapes that require equal units in the horizontal and vertical directions.

1.4.3 Isotropic Mapping Mode

We can arrange for horizontal and vertical units to be equal in terms of their real size by using the same scale factor for *x* and

y. Let us use the term *drawing rectangle* for the rectangle with dimensions *rWidth* and *rHeight*, in which we normally draw graphical output. Since these logical dimensions are constant, so is their ratio, which is not the case with that of the canvas dimensions. It follows that, with the isotropic mapping mode, the drawing rectangle will in general not be identical with the canvas. Depending on the current window size, either the top and bottom or the left and right edges of the drawing rectangle lie on those of the canvas.

Since it is normally desirable for a drawing to appear in the center of the canvas, it is often convenient with the isotropic mapping mode to place the origin of the logical coordinate system at that center. This implies that we will use the following logical-coordinate intervals:

$$-1/2\ rWidth \leq x \leq +1/2\ rWidth$$
$$-1/2\ rHeight \leq y \leq +1/2\ rHeight$$

Our methods *iX* and *iY* will map each logical coordinate pair (*x*, *y*) to a pair (*X*, *Y*) of device coordinates, where

$$X \in \{0, 1, 2, \ldots, maxX\}$$
$$Y \in \{0, 1, 2, \ldots, maxY\}$$

To obtain the same scale factor for *x* and *y*, we compute *rWidth*/*maxX* and *rHeight*/*maxY* and take the larger of these two values; this maximum value, *pixelSize*, is then used in the methods *iX* and *iY*, as this fragment shows:

```
Dimension d = getSize();
int maxX = d.width - 1, ma
pixelSize = Math.max(rWidt
centerX = maxX/2; centerY
...
int iX(float x){return Mat
int iY(float y){return Mat
```

```
float fx(int x){return (x
float fy(int y){return (ce
```

We will use this code in a program that draws a square, two corners of which touch either the midpoints of the horizontal canvas edges or those of the vertical ones. It also displays the coordinates of a point on which the user clicks, as the left window of Figure 1.8 shows.



Figure 1.8: Windows after changing their sizes

In this illustration, we pay special attention to the corners of the drawn square that touch the boundaries of the drawing rectangle. These corners do not lie on the window frame, but they

lie just inside it. For the square on the left we have:

Figure 1.8, left	logical coordinate *y*	device coordinat *iY*(*y*)
top corner	+*rHeight*/2	0
bottom corner	−*rHeight*/2	*maxY*

Open table as spreadsheet

By contrast, for the square that has been drawn in the narrow window on the right, it is the corners on the left and the right

that lie just within the frame:

Figure 1.8, right	logical coordinate x	device coordinate $iX(x)$
left corner	$-rWidth/2$	0
right corner	$+rWidth/2$	$maxX$

Open table as spreadsheet

The following program uses a drawing rectangle with logical dimensions *rWidth* = *rHeight* = 10.0. If we replaced this value 10.0 with any other positive

constant, the output would be the same.

```
// Isotrop.java: The isotr
//    Origin of logical cc
//    center; positive y-a
//    Square (turned 45 de
//    Mouse click displays
//    selected point.
import java.awt.*;
import java.awt.event.*;

public class Isotrop exten
{  public static void main

   Isotrop()
   { super("Isotropic mapp
     addWindowListener(new
        {public void windc
     setSize (400, 300);
```

```
        add("Center", new CvI
        setCursor(Cursor.getP
        show();
    }
}

class CvIsotrop extends Ca
{ int centerX, centerY;
 float pixelSize, rWidth =

  CvIsotrop()
  { addMouseListener(new M
    {  public void mousePr
       {  xP = fx(evt.getX
          repaint();
       }
    });
  }
```

```
void initgr()
{  Dimension d = getSize()
   int maxX = d.width - 1,
   pixelSize = Math.max(rW
   centerX = maxX/2; cente
  }

  int iX(float x){return M
  int iY(float y){return M
  float fx(int x){return (
  float fy(int y){return (

  public void paint(Graphi
  { initgr();
    int left = iX(-rWidth/
        bottom = iY(-rHeig
        xMiddle = iX (0),
    g.drawLine(xMiddle, bc
    g.drawLine(right,yMidc
```

```
        g.drawLine(xMiddle, tc
        g.drawLine(left, yMidd
        if (xP != 1000000)
            g.drawString(
            "Logical coordinate
            + xP + " " + yP, 20
    }
}
```

1.5 DEFINING A POLYGON BY USING THE MOUSE

We will use the conversion methods of the previous program in a more interesting application, which enables the user to define a polygon by clicking on points to indicate the positions of the vertices. Figure 1.9 shows such a polygon, just after the user has defined successive vertices, ending at the first one on the left, which is marked with a tiny rectangle.



Figure 1.9: Polygon defined by a user

The large rectangle surrounding the polygon is the drawing rectangle: only vertices inside this rectangle are guaranteed to appear again if the user changes the dimensions of the window. The very wide window of Figure 1.9 was obtained by dragging one of its corners. After the

polygon was drawn, the dimensions of the window were again changed, to obtain Figure 1.10. It is also possible to change these dimensions during the process of drawing the polygon. We now summarize the requirements for this application program:

- The first vertex is drawn as a tiny rectangle.
- If a later vertex is inside the tiny rectangle, the drawing of one polygon is complete.

- Only vertices in the drawing rectangle are drawn.

- The drawing rectangle (see Figures 1.9 and 1.10) is either as high or as wide as the window, yet maintaining its height/width ratio regardless of the window shape.

- When the user changes the shape of the window, the size of the drawn polygon changes in the same way as that of the

drawing rectangle, as does the surrounding white space of the polygon.


Define polygon vert...

Figure 1.10: Polygon still in the center of the window after resizing the window

We will use the isotropic mapping mode to implement this program, and use a data structure called *vertex vector* to store the vertices of the polygon to be drawn. We then design the program with the following algorithmic steps:

1. Activate the mouse;

2. When the left mouse

button is pressed

2.1 Get *x*- and *y*-coor
at where the mou
clicked;

If it is the first vert

Then emp
vertex ve

Else If th
is inside t
rectangle
last verte

- T
f

2.2

t
c
p

- E
s
t
v
v
v
(
la
v

3. Draw all vertices in vertex vector.

The last step to draw all the

polygon vertices can be detailed as follows:

1. Obtain the dimensions of the drawing rectangle based on logical coordinates;

2. Draw the drawing rectangle;

3. Get the first vertex from vertex vector;

4. Draw a tiny rectangle at the vertex location;

5. Draw a line between every two consecutive

vertices stored in vertex vector.

In both Figures 1.9 and 1.10 the drawing rectangle has a width of 10 and a height of 7.5 logical units, as the following program shows:

```
// DefPoly.java: Drawing a
// Uses: CvDefPoly (discus
import java.awt.*;
import java.awt.event.*;

public class DefPoly exten
{  public static void main

   DefPoly()
   {  super("Define polygc
```

```
        addWindowListener(ne
           {public void winc
        setSize (500, 300);
        add("Center", new Cv
        setCursor(Cursor.get
        show();
    }
}
```

The class *CvDefPoly*, used in this program, is listed below. We define this class in a separate file, *CvDefPoly.java*, so that it is easier to use elsewhere, as we will see in Section 2.13:

```
// CvDefPoly.java: To be u
//    A class that enables
//    a polygon by clicking
```

```
// Uses: Point2D (discusse

import java.awt.*;
import java.awt.event.*;
import java.util.*;

class CvDefPoly extends Ca
{  Vector v = new Vector()
   float x0, y0, rWidth =
   boolean ready = true;
   int centerX, centerY;

   CvDefPoly()
   { addMouseListener(new
     {  public void mouseP
        { float xA = fx(ev
          if (ready)
        { v.removeAllEleme
          x0 = xA; y0 = yA
```

```
                ready = false;
            }
            float dx = xA - x0
            if (v.size()>0&&
                dx * dx + dy *
                ready = true;
            else
                v.addElement(ne
            repaint();
        }
    });
}

void initgr()
{   Dimension d = getSize()
    int maxX = d.width - 1,
    pixelSize = Math.max(rW
    centerX = maxX/2; cente
}
```

```
int iX(float x){return Mat
int iY(float y){return Mat
float fx(int x){return (x
float fy(int y){return (ce

public void paint(Graphics
{  initgr();
   int left = iX(-rWidth/2
       bottom = iY(-rHeigh
   g.drawRect(left, top, r
   int n = v.size();
   if (n == 0) return;
   Point2D a = (Point2D)(v
   // Show tiny rectangle
   g.drawRect(iX(a.x)-2, i
   for (int i=1; i<=n; i++
   { if (i == n && !ready)
     Point2D b = (Point2D)
```

```
      g.drawLine(iX(a.x), i
    a=b;
    }
  }
}
```

The class *Point2D*, used in the above file, will also be useful in other programs, so that we define this in another separate file, *Point2D.java*:

```
// Point2D.java: Class for
class Point2D
{ float x, y;
  Point2D(float x, float y
}
```

After a complete polygon has

been shown (which is the case when the user has revisited the first vertex), the user can once again click a point. The polygon then disappears and that point will then be the first vertex of a new polygon.

Note that the comment line

```
// Uses: CvDefPoly (discus
```

occurring in the file *DefPoly.java*, indicates that the file *CvDefPoly.java* should be available in the current directory. Since the comment line

```
// Uses: Point2D (discusse
```

occurs in the file *CvDefPoly.java*, the program *DefPoly.java* also requires the class *Point2D*. Comments such as those above are very helpful if different directories are used, for example, one for each chapter. However, since class names are unique throughout this book, it is possible to place all program files in the same directory. In this way, each required class will be available.

EXERCISES

1.1 How many pixels are put on t
calls?

```
g.drawLine (10, 20, 1
g.drawRect (10, 10, 8
g.fillRect (10, 10, 8
```

Replace the triangles of prog
draw a great many of them,
in Figure 1.11.

1.2



Figure 1.11: A chessboar

As usual, this chessboard co
horizontal and vertical edges
actually consists of k square
Finally, the value $q = 0.2$ (an
each edge into two parts wit

Triangles.java in Section 1.3)
1.11 was obtained by reversi
$n \times n$ 'normal' squares, whic
squares of a normal chessbo
values n, k and q as program

Draw a set of concentric pair
square with horizontal and ve
45°. Except for the outermos
are the midpoints of the edge
square, as Figure 1.12 show
exactly straight, and that vert
the edges of larger ones.

1.3



Figure 1.12: Concentric s

Write a program that draws a
Figure 1.13. The vertices of a
called circumscribed circle. T
radius of this circle by clickin
of the drawing rectangle. The
and that corner is to be used
mentioned. There must be as
size as possible and the mar
equal. The same applies to t
Figure 1.13 shows.

1.4



Figure 1.13: Hexagons

Write a class *Lines* containin
draw dashed lines, in such a

```
Lines.dashedLine(g, x
```

where *g* is a variable of type
device coordinates of the enc
the desired length (in device
should be a dash, not a gap,
Figure 1.14 shows eight dasl
dashLength =20.

1.5



Figure 1.14: Dashed lines

Answers

1.1

Numbers of pixels:

```
g.drawLine (10, 20, 1
g.drawRect (10, 10, 8
g.fillRect (10, 10, 8
```

Program to draw many squa

```
// ManySq.java: This
//    consisting of k
//    Each edge is div
//     (1 - q)   : q. Th
                  argumen
```

```
import java.awt.*;
import java.awt.event

public class ManySq e
{  public static void
   {  if (args.length
      {  System.out.p
         System.exit(
      }
      int n = Integer
          k = Integer
      float q = Float
      new ManySq(n, k
    }
    ManySq(int n, int
    {  super("ManySq:
       addWindowListe
        {public void
```

```
                    Windo
        add("Center",
        setSize (600,
        show();
    }
}

class CvManySq exte
{   int centerX, cen
    float p0, q0;

    CvManySq(int nn,
                    1

    int iX(float x){
    int iY(float y){

    public void pain
    {   Dimension d =
```

1.2

```
int maxX = d.
   minMaxXY =
centerX = max

float r = 0.4
for (int x=0;
for (int y=0;
{  float xCne
          yCne
      xA, yA,
      xA1, yA
   if (x % 2
   xA = xD =
   yA = yB =
   for (int i
   {  g.drawL
      g.drawL
      g.drawL
      g.drawL
```

```
                    xA1 = p
                    xB1 = p
                    xC1 = p
                    xD1 = p
                    xA = xA
                    yA = yA
                }
            }
        }
    }
```

1.3 To draw all edges as exactly
exactly on the edges of their
pair of very small squares (◇
twice as large as those of th

The radius *r* of the circumscr

on this radius *r*, the following may be helpful:

```
int iX(float x){retur
int iY(float y){retur

void drawLine(Graphic
{  g.drawLine(iX(xA),
}
...

float halfr = r/2, ho
  w = r * (float)Math
                margi
int nhor = (int)Math.
   nvert = (int)Math
marginleft = -rWidth/
              horpitc
marginbottom = -rHeig
```

1.4

```
for (int i=0; i<nhor;
{  float x = marginle
    y0 = marginbottom
                hexagon
    int m = nvert - i
// There will be nver
                ...
// while there will b
                ...
// Special case: if n
                by
// horpitch/2 because
                the
// right.
    if (nvert == 1 &&
       x += horpitch/2
    for (int j=0; j<m;
    {  float y = y0+j*
       drawLine(g, x +
```

```
drawLine(g, x -
drawLine(g, x -
...
```

We begin by computing the l

$$L = \sqrt{u_1^2 + u_2^2}$$

where

$$u_1 = x_B - x_A$$

$$u_2 = y_B - y_A$$

1.5

Since there should be a dash
are about equal to *dashLeng*

$$L = (2n - 1) \times dashLength$$

to compute n, the number of
denoting the dashes by $i = 0$
endpoints $(x_A + 2ih_1, y_A + 2ih$

Chapter 2: Applied Geometry

Before we proceed with specific computer-graphics subjects, we will discuss some mathematics, which we will often use in this book. You can skip the first four sections of this chapter if you are very familiar with vectors and determinants. After this general part, we will deal with some useful algorithms needed for the exercises at the end of this chapter and for

the topics in the remaining chapters. For example, in Chapters 6 and 7 we will deal with polygons that are faces of 3D solid objects. Since polygons in general are difficult to handle, we will divide them into triangles, as we will discuss in the last section of this chapter.

2.1 VECTORS

We begin with the mathematical notion of a vector, which should not be confused with the standard class *Vector*, available in Java to store an arbitrary number of objects. Recall that we have used this *Vector* class in Section 1.5 to store polygon vertices.

A *vector* is a directed line segment, characterized by its length and its direction only. Figure 2.1 shows two representations of the same

vector **a** = **PQ** = **b** = **RS**. Thus a vector is not altered by a translation.



Figure 2.1: Two equal vectors

The sum **c** of the vectors **a** and **b**, written

$$\mathbf{c} = \mathbf{a} + \mathbf{b}$$

can be obtained as the diagonal of a parallelogram, with **a, b** and **c** starting at the same point, as shown in Figure 2.2.



Figure 2.2: Vector addition

The length of a vector **a** is denoted by |**a**|. A vector with zero length is the zero vector,

written as **0**. The notation $-\mathbf{a}$ is used for the vector that has length $|\mathbf{a}|$ and whose direction is opposite to that of **a**. For any vector **a** and real number c, the vector $c\mathbf{a}$ has length $|c||\mathbf{a}|$.If $\mathbf{a} = \mathbf{0}$ or $c = 0$, then $c\mathbf{a} = \mathbf{0}$;otherwise $c\mathbf{a}$ has the direction of **a** if $c > 0$ and the opposite direction if $c < 0$. For any vectors **u, v, w** and real numbers c, k, we have

$$\mathbf{u} + \mathbf{v} = \mathbf{v} + \mathbf{u}$$

$$(\mathbf{u} + \mathbf{v}) + \mathbf{w} = \mathbf{u} + (\mathbf{v} + \mathbf{w})$$

$$\mathbf{u} + 0 = \mathbf{u}$$

$$\mathbf{u} + (-\mathbf{u}) = 0$$

$$c(\mathbf{u} + \mathbf{v}) = c\mathbf{u} + c\mathbf{v}$$

$$(c + k)\mathbf{u} = c\mathbf{u} + k\mathbf{u}$$

$$c(k\mathbf{u}) = (ck)\mathbf{u}$$

$$1\mathbf{u} = \mathbf{u}$$

$$0\mathbf{u} = 0$$

Figure 2.3 shows three unit vectors **i, j** and **k** in a three-dimensional space. They are mutually perpendicular and have length 1. Their directions are the positive directions of the coordinate axes. We say that **i, j** and **k** form a triple of orthogonal *unit vectors*. The coordinate system is right-handed, which

means that if a rotation of **i** in the direction of **j** through 90° corresponds to turning a right-handed screw, then **k** has the direction in which the screw advances.



Figure 2.3: Right-handed coordinate system

We often choose the origin O of the coordinate system as the

initial point of all vectors. Any vector **v** can be written as a *linear combination* of the unit vectors **i**, **j**,and **k**:

$$\mathbf{v} = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$$

The real numbers *x*, *y* and *z* are the coordinates of the endpoint P of vector **v** = **OP**. We often write this vector **v** as

$$\mathbf{v} = [\, x \quad y \quad z \,] \qquad \text{or} \qquad \mathbf{v} = (x, y, z)$$

The numbers *x*, *y*, *z* are sometimes called the *elements* or *components* of vector **v**.

The possibility of writing a vector as a sequence of coordinates, such as (*x*, *y*, *z*) for three-dimensional space, has led to the use of this term for sequences in general. This explains the name *Vector* for a standard Java class. The only aspect this *Vector* class has in common with the mathematical notion of vector is that both are related to sequences.

2.2 INNER PRODUCT

The *inner product* or *dot product* of two vectors **a** and **b** is a real number, written as **a** · **b** and defined as

$$\mathbf{a}\cdot\mathbf{b} = |\mathbf{a}||\mathbf{b}|\cos\gamma \qquad \text{if } \mathbf{a}\neq 0 \text{ and } \mathbf{b}\neq 0$$
$$\mathbf{a}\cdot\mathbf{b} = 0 \qquad \text{if } \mathbf{a}=0 \text{ or } \mathbf{b}=0 \tag{2.1}$$

where γ is the angle between **a** and **b**. It follows from the first equation that **a** · **b** is also zero if γ = 90°. Applying this definition to the unit vectors **i**, **j** and **k**, we find

$$\mathbf{i}\cdot\mathbf{i}=\mathbf{j}\cdot\mathbf{j}=\mathbf{k}\cdot\mathbf{k}=1$$
$$\mathbf{i}\cdot\mathbf{j}=\mathbf{j}\cdot\mathbf{i}=\mathbf{j}\cdot\mathbf{k}=\mathbf{k}\cdot\mathbf{j}=\mathbf{k}\cdot\mathbf{i}=\mathbf{i}\cdot\mathbf{k}=0 \tag{2.2}$$

Setting **b** = **a** in Equation (2.1), we have $\mathbf{a} \cdot \mathbf{a} = |\mathbf{a}|^2$, so

$$|\mathbf{a}| = \sqrt{|\mathbf{a} \cdot \mathbf{a}|}$$

Some important properties of inner products are

$$c(k\mathbf{u} \cdot \mathbf{v}) = ck(\mathbf{u} \cdot \mathbf{v})$$
$$(c\mathbf{u} + k\mathbf{v}) \cdot \mathbf{w} = c\mathbf{u} \cdot \mathbf{w} + k\mathbf{v} \cdot \mathbf{w}$$
$$\mathbf{u} \cdot \mathbf{v} = \mathbf{v} \cdot \mathbf{u}$$
$$\mathbf{u} \cdot \mathbf{u} = 0 \text{ only if } \mathbf{u} = 0$$

The inner product of two vectors $\mathbf{u} = [u_1\ u_2\ u_3]$ and $\mathbf{v} = [v_1\ v_2\ v_3]$ can be computed as

$$\mathbf{u} \cdot \mathbf{v} = u_1v_1 + u_2v_2 + u_3v_3$$

We can prove this by developing the right-hand side of the following equality as the sum of nine inner products and then applying Equation (2.2):

$$\mathbf{u} \cdot \mathbf{v} = (u_1\mathbf{i} + u_2\mathbf{j} + u_3\mathbf{k}) \cdot (v_1\mathbf{i} + v_2\mathbf{j} + v_3\mathbf{k})$$

2.3 DETERMINANTS

Before proceeding with vector products, we will pay some attention to determinants. Suppose we want to solve the following system of two linear equations for x and y:

$$\begin{cases} a_1 x + b_1 y = c_1 \\ a_2 x + b_2 y = c_2 \end{cases} \tag{2.3}$$

We can then multiply the first equation by b_2, the second by $-b^1$, and add them, finding

$$(a_1 b_2 - a_2 b_1)x = b_2 c_1 - b_1 c_2$$

Then we can multiply the first equation by $-a_2$, the second by a_1, and add again, obtaining

$$(a_1b_2 - a_2b_1)y = a_1c_2 - a_2c_1$$

If $a_1b_2 - a_2b_1$ is not zero, we can divide and find

$$x = \frac{b_2c_1 - b_1c_2}{a_1b_2 - a_2b_1} \qquad y = \frac{a_1c_2 - a_2c_1}{a_1b_2 - a_2b_1} \tag{2.4}$$

The denominator in these expressions is often written in the form

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix}$$

and then called a *determinant*. Thus

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = a_1 b_2 - a_2 b_1$$

Using determinants, we can write the solution of Equation (2.3) as

$$x = \frac{D_1}{D} \qquad y = \frac{D_2}{D} \qquad (D \neq 0)$$

where

$$D = \begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} \quad D_1 = \begin{vmatrix} c_1 & b_1 \\ c_2 & b_2 \end{vmatrix} \quad D_2 = \begin{vmatrix} a_1 & c_1 \\ a_2 & c_2 \end{vmatrix}$$

Note that D_i is obtained by replacing the ith column of D with

the right-hand side of Equation (2.3) (i = 1 or 2). This method of solving a system of linear equations is called *Cramer's rule*. It is not restricted to systems of two equations (although it would be very expensive in terms of computer time to apply the method to large systems). Determinants with n rows and n columns are said to be of the nth order. We define determinants of third order by using the equation

$$D = \begin{vmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \\ a_{31} & a_{32} & a_{33} \end{vmatrix} = a_{11}M_{11} - a_{12}M_{12} + a_{13}M_{13}$$

where each so-called *minor determinant* M_{ij} is the 2×2 determinant that we obtain by deleting the *i*th row and the *j*th column of *D*. Determinants of higher order are defined similarly.

Determinants are very useful in linear algebra and analytical geometry. They have many interesting properties, some of which are listed below:

1. The value of a determinant remains the same if its rows are written as columns in the same order. For

example:

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = \begin{vmatrix} a_1 & a_2 \\ b_1 & b_2 \end{vmatrix}$$

2. If any two rows (or columns) are interchanged, the value of the determinant is multiplied by -1. For example:

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} = - \begin{vmatrix} a_1 & b_1 & c_1 \\ a_3 & b_3 & c_3 \\ a_2 & b_2 & c_2 \end{vmatrix}$$

3. If any row or column is multiplied by a factor,

the value of the determinant is multiplied by this factor. For example:

$$\begin{vmatrix} ca_1 & b_1 \\ ca_2 & b_2 \end{vmatrix} = c \begin{vmatrix} a_1 & a_2 \\ b_1 & b_2 \end{vmatrix}$$

4. If a row is altered by adding any constant multiple of any other row to it, the value of the determinant remains unaltered. This operation may also be applied to columns. For example:

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 + ka_1 & b_3 + kb_1 & c_3 + kc_1 \end{vmatrix} = \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$$

5. If a row (or a column) is a linear combination of some other rows (or columns), the value of the determinant is zero. For example:

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ 3a_1 - 2a_2 & 3b_1 - 2b_2 & 3c_1 - 2c_2 \end{vmatrix} = 0$$

In many cases, determinant equations expressing geometrical properties are elegant and easy

to remember. For example, the equation of the line in R_2 through the two points $P_1(x_1, y_1)$ and $P_2(x_2, y_2)$ can be written

$$\begin{vmatrix} x & y & 1 \\ x_1 & y_1 & 1 \\ x_2 & y_2 & 1 \end{vmatrix} = 0 \qquad (2.5)$$

This can be understood by observing, first, that Equation (2.5) is a special notation for a linear equation in x and y, and consequently represents a straight line in R_2, and second, that the coordinates of both P_1 and P_2 satisfy this equation, for if

we write them in the first row, we have two identical rows. Similarly, the plane in R_3 through three points $P_1(x_1, y_1, z_1)$, $P_2(x_2, y_2, z_2)$, $P_3(x_3, y_3, z_3)$ has the equation

$$\begin{vmatrix} x & y & z & 1 \\ x_1 & y_1 & z_1 & 1 \\ x_2 & y_2 & z_2 & 1 \\ x_3 & y_3 & z_3 & 1 \end{vmatrix} = 0 \qquad (2.6)$$

which is much easier to remember than one written in the conventional way.

2.4 VECTOR PRODUCT

The *vector product* or *cross product* of two vectors **a** and **b** is written

$$\mathbf{a} \times \mathbf{b}$$

and is a vector **v** with the following properties. If **a** = *c***b** for some scalar *c*,then **v** = **0**. Otherwise the length of **v** is equal to

$$|\mathbf{v}| = |\mathbf{a}||\mathbf{b}| \sin \gamma$$

where γ is the angle between **a** and **b**, and the direction of **v** is

perpendicular to both **a** and **b** and is such that **a**, **b** and **v**, in that order, form a right-handed triple. This means that if **a** is rotated through an angle $\gamma < 180°$ in the direction of **b**, then **v** has the direction of the advancement of a right-handed screw if turned in the same way. Note that the length $|\mathbf{v}|$ is equal to the area of a parallelogram of which the vectors **a** and **b** can act as edges, as Figure 2.4 shows.



Figure 2.4: Vector product a × b

The following properties of vector products follow from this definition:

$$(k\mathbf{a}) \times \mathbf{b} = k(\mathbf{a} \times \mathbf{b}) \qquad \text{for any real number } k$$

$$\mathbf{a} \times (\mathbf{b} + \mathbf{c}) = \mathbf{a} \times \mathbf{b} + \mathbf{a} \times \mathbf{c}$$

$$\mathbf{a} \times \mathbf{b} = -\mathbf{b} \times \mathbf{a}$$

In general, **a** × (**b** × **c**) ≠ (**a** × **b**) × **c**. If we apply our definition of

vector product to the unit vectors **i**, **j**, **k** (see Figure 2.3), we have

$$\begin{aligned} \mathbf{i}\times\mathbf{i}&=0 & \mathbf{j}\times\mathbf{j}&=0 & \mathbf{k}\times\mathbf{k}&=0\\ \mathbf{i}\times\mathbf{j}&=\mathbf{k} & \mathbf{j}\times\mathbf{k}&=\mathbf{i} & \mathbf{k}\times\mathbf{i}&=\mathbf{j}\\ \mathbf{j}\times\mathbf{i}&=-\mathbf{k} & \mathbf{k}\times\mathbf{j}&=-\mathbf{i} & \mathbf{i}\times\mathbf{k}&=-\mathbf{j} \end{aligned}$$

Using these vector products in the expansion of

$$\mathbf{a}\times\mathbf{b}=(a_1\mathbf{i}+a_2\mathbf{j}+a_3\mathbf{k})\times(b_1\mathbf{i}+b_2\mathbf{j}+b_3\mathbf{k})$$

we obtain

$$\mathbf{a}\times\mathbf{b}=(a_2b_3-a_3b_2)\mathbf{i}+(a_3b_1-a_1b_3)\mathbf{j}+(a_1b_2-a_2b_1)\mathbf{k}$$

which can be written as

$$\mathbf{a}\times\mathbf{b}=\begin{vmatrix} a_2 & a_3\\ b_2 & b_3 \end{vmatrix}\mathbf{i}+\begin{vmatrix} a_3 & a_1\\ b_3 & b_1 \end{vmatrix}\mathbf{j}+\begin{vmatrix} a_1 & a_2\\ b_1 & b_2 \end{vmatrix}\mathbf{k}$$

We rewrite this in a form that is very easy to remember:

$$\mathbf{a} \times \mathbf{b} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ a_1 & a_2 & a_3 \\ b_1 & b_2 & b_3 \end{vmatrix}$$

This is a mnemonic aid rather than a true determinant, since the elements of the first row are vectors instead of numbers.

If **a** and **b** are neighboring sides of a parallelogram, as shown in Figure 2.4, the area of this parallelogram is the length of vector **a** × **b**. This follows from our definition of vector product,

according to which $|\mathbf{a} \times \mathbf{b}| = |\mathbf{a}||\mathbf{b}| \sin \gamma$ is the length of vector $\mathbf{a} \times \mathbf{b}$.

2.5 THE ORIENTATION OF THREE POINTS

We will now deal with a subject that will be very useful in Chapters 6 and 7. Suppose that we are given an ordered triple (A, B, C) of three points in the *xy*-plane and we want to know their orientation; in other words, we want to know whether we turn counter-clockwise or clockwise when visiting these points in the given order. Figure 2.5 shows the possibilities, which we also refer to as *positive* and *negative* orientation, respectively.



Figure 2.5: Counter-clockwise and clockwise orientation of A, B, C

There is a third possibility, namely that the points A, B and C lie on a straight line. We will consider the orientation to be zero in this case. If we plot the points on paper, we see immediately which of these three

cases applies, but we now want a means to find the orientation by computation, using only the coordinates x_A, y_A, x_B, y_B, x_C, y_C.

Let us define the two vectors **a** = **CA** and **b** = **CB**, as shown in Figure 2.6. Clearly, the orientation of the original points A, B and C is positive if we can turn the vector **a** counter-clockwise through a positive angle less than 180° to obtain the direction of the vector **b**. Since vectors are only determined by their directions and lengths, we may let them start at the origin O

instead of at point C, as Figure 2.6 shows. Although this orientation problem is essentially two-dimensional, and can be solved using only 2D concepts, as we will see in a moment, it is convenient to use 3D space. As usual, the unit vectors **i**, **j** and **k** have the directions of the positive *x*-, *y*-and *z*-axes. In Figure 2.6, we imagine the vector **k**, like **i** and **j** starting at O, and pointing towards us. Denoting the endpoints of the translated vectors **a** and **b**,starting at O, by$(a_1, a_2,0)$ and $(b_1, b_2, 0)$, we have

$$\mathbf{a} = a_1\mathbf{i} + a_2\mathbf{j} + 0\mathbf{k}$$

$$\mathbf{b} = b_1\mathbf{i} + b_2\mathbf{j} + 0\mathbf{k}$$



Figure 2.6: Using vectors a and b instead of triangle edges CA and CB

and

$$\mathbf{a} \times \mathbf{b} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ a_1 & a_2 & 0 \\ b_1 & b_2 & 0 \end{vmatrix} = \begin{vmatrix} a_1 & a_2 \\ b_1 & b_2 \end{vmatrix} \mathbf{k} = (a_1 b_2 - a_2 b_1)\mathbf{k}$$

This expresses the fact that **a** × **b** is a vector perpendicular to the *xy*-plane and either in the same direction as

$$\mathbf{k} = \mathbf{i} \times \mathbf{j}$$

or in the opposite direction, depending on the sign of $a_1b_2 - a_2b_1$. If this expression is positive, the relationship between **a** and **b** is similar to that of **i** and **j**:we can turn **a** counter-clockwise through an angle less than 180° to obtain the direction of **b**, in the same way as we can do this with **i** to obtain **j**. In general, we have

$$a_1 b_2 - a_2 b_1 \begin{cases} > 0 : \text{orientation of A, B and C positive (counter-clockwise)} \\ = 0 : \text{A, B and C on the same line} \\ < 0 : \text{orientation of A, B and C negative (clockwise)} \end{cases}$$

2.5.1 An Alternative, Two-dimensional Solution

It would be unsatisfactory if we were unable to solve the above orientation problem by using only two-dimensional concepts. To provide such an alternative solution, we use the angles α between vector **a** and the positive *x*-axis and β between **b** and this axis (see Figure 2.6).

Then the orientation we are interested in depends upon the angle $\beta - \alpha$. If this angle lies between 0 and π, the orientation is clearly positive, but it is negative if this angle lies between π and 2π (or between $-\pi$ and 0). We can express this by saying that the orientation in question depends on the value of $\sin(\beta - \alpha)$ rather than on the angle $\beta - \alpha$ itself. More specifically, the orientation has the same sign as

$$\sin(\beta - \alpha) = \sin\beta\cos\alpha - \cos\beta\sin\alpha = \frac{b_2}{|\mathbf{b}|}\frac{a_1}{|\mathbf{a}|} - \frac{b_1}{|\mathbf{b}|}\frac{a_2}{|\mathbf{a}|} = \frac{a_1 b_2 - a_2 b_1}{|\mathbf{a}||\mathbf{b}|}$$

Since the denominator in this expression is the product of two vector lengths, it is positive, so that we have again found that the orientation of A, B and C and $a_1b_2 - a_2b_1$ have the same sign. Due to unfamiliarity with the above trigonometric formula, some readers may find the former, more visual 3D approach easier to remember.

2.5.2 A Useful Java Method

The method *area2* in the

following fragment is based on the results we have found. This method takes three arguments of class *Point2D*, discussed at the end of Chapter 1. We will use the class *Tools2D* for several static methods, to be used as two-dimensional tools (see also Section 2.13). Note that, in accordance with Java convention, we use lower-case variable names *a*, *b*, *c* for the points A, B and C:

```
class Tools2D
{    static float area2(Poi
     {  return (a.x - c.x)
     }
```

```
    ... // See Section 2.1
}
```

As we will see in Section 2.7, this method computes the area of the triangle ABC multiplied by 2, or, if A, B and C are clockwise, by -2. If we are interested only in the orientation of the points A, B and C, each of type *Point*2D, we can write:

```
if (Tools2D.area2(a, b, c)
{  ... // A, B and C count
}
else
{ ...
  // A, B and C clockwise
  // in that case A, B and
```

```
}
```

2.6 POLYGONS

A *polygon* is a sequence P_0, P_1, …, P_{n-1} of vertices, where $n \geq 3$, with associated edges P_0P_1, P_1P_2, …, $P_{n-2}P_{n-1}$, P_{n-1}, P_0. In this book we will restrict ourselves to simple polygons, of which non-adjacent edges do not intersect. Figure 2.7 shows two simple and two non-simple polygons, for all of which $n = 5$.



Figure 2.7: Two simple and two non-simple polygons

Besides non-simple polygons, such as those in Figure 2.7(c) and (d), we usually also ignore polygons in which three successive vertices lie on the same line. A vertex of a polygon is said to be *convex* if the interior

angle between the two edges meeting at that vertex is less than 180°. If all vertices of a polygon are convex, the polygon itself is said to be convex, as is the case with Figure 2.7(a). Non-convex vertices are referred to as *reflex*. If a polygon has at least one reflex vertex, the polygon is said to be *concave*. Figure 2.7(b) shows a concave polygon because the vertex in the middle is reflex. All triangles are convex, and each polygon has at least three convex vertices.

If we are given the vertices P_0,

P_1, ..., P_{n-1} of a polygon, it may be desirable to determine whether this vertex sequence is counter-clockwise. If we know that the second vertex, P_1, is convex, we can simply write

```
if (Tools2D.area2(p[0], p[
    ... // Counter-clockwis
else
    ... // Clockwise
```

The problem is more interesting if no information about any convex vertex is available. We then have to detect such a vertex. This is an easy task, since any vertex whose *x*-or *y*-coordinate is

extreme is convex. For example, we can use a vertex whose *x*-coordinate is not greater than that of any other vertex. If we do not want to exclude the case of three successive vertices lying on the same line, we must pay special attention to the case of three such vertices having the minimum *x*-coordinate. Therefore, among all vertices with an *x*-coordinate equal to this minimum value, we choose the lowest one, that is, the one with the least *y*-coordinate. The following method is based on this idea:

```
static boolean ccw(Point2D
{   int n = p.length,k=0;
    for (int i=1; i<n; i++)
        if (p[i].x <= p[k].x
            k=i;
    // p[k] is a convex ver
    int prev = k - 1, next
    if (prev = = -1) prev =
    if (next == n) next = 0
    return Tools2D.area2(p[
}
```

We should be aware that one very strange situation is still possible: all *n* vertices may lie on the same line. In that case, the method *ccw* will return the value *false*.

We will use this method in Section 2.13, in which program *PolyTria.java* will divide a user-entered polygon into triangles.

2.7 THE AREA OF A POLYGON

As we have seen in Figure 2.4, the cross product **a** × **b** is a vector whose length is equal to the area of a parallelogram of which **a** and **b** are two edges. Since this parallelogram is the sum of two triangles of equal area, it follows that for Figure 2.6 we have

$$2\ \text{Area}(\Delta ABC) = |a \times b| = \begin{vmatrix} a_1 & a_2 \\ b_1 & b_2 \end{vmatrix} = a_1 b_2 - a_2 b_1$$

Note that this is valid only if A, B and C are labeled counter-

clockwise; if this is not necessarily the case, we have to use the absolute value of $a_1b_2 - a_2b_1$.

Since $a_1 = x_A - x_C$, $a_2 = y_A - y_C$, $b_1 = x_B - x_C$, $b_2 = y_B - y_C$, we can also write

$$2\,\text{Area}(\Delta ABC) = (x_A - x_C)(y_B - y_C) - (y_A - y_C)(x_B - x_C)$$

After working this out, we find that we can replace this with

$$2\,\text{Area}(\Delta ABC) = (x_A y_B - y_A x_B) + (x_B y_C - y_B x_C) + (x_C y_A - y_C x_A)$$

Although the latter expression seems hardly an improvement, it

is useful to prepare for a more general one, which we can use to compute the area of any polygon, convex or concave, which has the vertices P_0P_1, P_1P_2, … , $P_{n-2}P_{n-1}$, P_{n-1}, labeled counter-clockwise:

$$2\ \text{Area}(P_0 \ldots P_{n-1}) = \sum_{i=0}^{n-1} (x_i y_{i+1} - y_i x_{i+1})$$

where (x_i, y_i) are the coordinates of P_i and P_n is the same vertex as P_0. As you can see, our last formula for the area of a triangle is a special case of this general one, in which the area of a

polygon is expressed directly in terms of the coordinates of its vertices. A complete proof of this formula is beyond the scope of this book.

2.7.1 Java Code

As we have seen in Section 2.6, we use the method *area*2 to determine the orientation of three points A, B and C. Recall that the digit 2 in the name *area*2 indicates that we have to divide the return value by 2 to obtain the area of triangle ABC, that is, if A, B and C are counter-clockwise;

otherwise, we have to take the absolute value |*area*2(*A*, *B*, *C*)/2|.

The same applies to the following method *area*2, whose return value divided by 2 gives the area, possibly preceded by a minus sign, of a polygon.

```
static float area2(Point2D
{  int n = pol.length,
       j = n - 1;
   float a = 0;

   for (int i=0; i<n; i++)
   {  // i and j denote ne
      // with i one step a
      a + = pol[j].x * pol
```

```
    }
    return a;
}
```

Note that this second *area2* method provides another means of deciding the orientation of a polygon vertex sequence: this orientation is counter-clockwise if *area2* returns a positive value and clockwise if it returns a negative one. However, the method *ccw* discussed in Section 2.6 is faster, especially if *n* is large, because for most vertices it will only perform the comparison

```
p[i].x <= p[k].x
```

while *area2* performs some more time-consuming arithmetic operations for each vertex.

We could add this second method *area2*totheclass *Tools2D*, but you will not find it in our final version of this class in Section 2.13 because we will never use it in this book; since we will use *Tools2D* several times, we prefer to omit superfluous methods for economic reasons.

2.8 POINT-IN-TRIANGLE TEST

Determining the orientation of three points as we have just been discussing is useful in a test to see if a given point P lies within a triangle ABC. As Figure 2.8 shows, this is the case if the orientation of the triangles ABP, BCP and CAP is the same as that of triangle ABC.



Figure 2.8: Orientation used to test if P lies within triangle ABC

Let us assume that we know that the orientation of ABC is counter-clockwise. We can then call the following method to test if P lies within triangle ABC (or on an

edge of it):

```
static boolean insideTrian
   Point2D p) // ABC is as
{ return
      Tools2D.area2(a, b, p
      Tools2D.area2(b, c, p
      Tools2D.area2(c, a, p

}
```

In this form, the method *insideTriangle* also returns the value *true* if P lies on an edge of the triangle ABC. If this is not desired, we should replace >= 0with > 0. The above form is the one we will need in Chapters 6 and 7, in which we will use this

method to triangulate complicated polygonal faces of 3D objects.

Incidentally, with a floating-point value *x*, we might consider replacing a test of the form *x* >= 0with *x* >=−*epsilon* and *x* > 0with *x* > *epsilon*,where *epsilon* is some small positive value, such as 10^{-6}. In this way a very small rounding-off error (less than *epsilon*) in the value of *x* will not affect the result of the test. This is not done here because the above method *insideTriangle* works well for our applications.

2.8.1 An Alternative Method insideTriangle

The above method *insideTriangle* is reasonably efficient, especially if point P does not lie within the triangle ABC. In such cases the chances are that not all three calls to *area*2 are executed because the first or the second of the three tests fails. However, it should be mentioned that there is an entirely different way of solving the problem in question, as we will see in Exercise 3.5. The corresponding alternative method *insideTriangle* (listed in

Appendix F), is slightly faster than the one above if a single triangle ABC is to be used for several points P. It is also more general in that it does not rely on ABC being counter-clockwise. We will not discuss this alternative method here because it is easier to understand after the discussion of matrix multiplication and inverse matrices in Chapter 3. To avoid confusion we will normally use the *insideTriangle* version discussed in this section and occurring in the file *Tools2D.java*, even in cases where the one in

Exercise 3.5 might be slightly faster.

2.9 POINT-IN-POLYGON TEST

The notion of orientation is also useful when we need to determine whether a given point P lies within a polygon. It will then be convenient if a method is available which accepts both the polygon in question and point P as arguments, and returns *true* if P lies inside and *false* if it lies outside the polygon. If P lies on a polygon edge, we do not care: in that case the method may return *true* or *false*. The method we will discuss is based on the idea of

drawing a horizontal half-line, which starts at P and extends only to the right. The number of intersections of this horizontal half-line with polygon edges is odd if P lies within the polygon and even if P lies outside it. Imagine that we move to the right, starting at point P. Then our state changes from *inside* to *outside* and vice versa each time we cross a polygon edge. The total number of changes is therefore odd if P lies within the polygon and even if it lies outside the polygon. It is not necessary to visit all intersections strictly

from left to right; the only thing we want to know is whether there are an odd or an even number of intersections on a horizontal line through P and to the right of P. However, we must be careful with some special cases, as shown in Figure 2.9.



Figure 2.9: Polygon and half-line starting at P

We simply ignore horizontal polygon edges, even if they have the same *y*- coordinate as P, as is the case with edge 4–5 in this example. If a vertex occurring as a 'local maximum or minimum' happens to have the same *y*-coordinate as P, as is the cases with vertices 8 and 12 in this example, it is essential that this is either ignored or counted twice. We can realize this by using the edge from vertex *i* to vertex *i* + 1 only if

$$y_i \leq y_P < y_{i+1} \text{ or } y_{i+1} \leq y_P < y_i$$

This implies that the lower endpoint of a non-horizontal edge is regarded as part of the segment, but the upper endpoint is not. For example, in Figure 2.9, vertex8(with $y_8 = y_P$) is not counted at all because it is the upper endpoint of both edge 7–8 and edge 8–9. By contrast, vertex 12 (with $y_{12} = y_P$) is the lower endpoint of the edges 11–12 and 12–13 and thus counted twice. Therefore, in this example, we count the intersections of the half-line through P with the seven

edges 2–3, 3–4, 5–6, 6–7, 10–11, 11–12, 12–13 and with no others.

Since we are considering only a half-line, we must impose another restriction on the set of edges satisfying the above test, selecting only those whose point of intersection with the half-line lies to the right of P. One way of doing this is by using the method *area*2 to determine the orientation of a sequence of three points. For example, this orientation is counter-clockwise for the triangle 2-3-P in Figure 2.9, which implies that P lies to

the left of edge 2–3. It is also counter-clockwise for the triangle 7-6-P. In both cases, the lower endpoint of an edge, its upper endpoint and point P, in that order, are counter-clockwise. The following method is based on these principles:

```
static boolean insidePolyg
{  int n = pol.length, j =
   boolean b = false;
   float x = p.x, y = p.y;
   for (int i=0; i<n; i++)
   { if (pol[j].y <= y &&
         Tools2D.area2(pol
         pol[i].y <= y &&
         Tools2D.area2(pol
     j = i;
```

```
        }
        return b;
}
```

This static method, like some others in this chapter, might be added to the class *Tools2D* (see Section 2.13).

2.9.1 The contains Method of the Java Class Polygon

There is a standard class *Polygon*, which has a member named *contains* to perform about

the same task as the above method *insidePolygon*. However, it is based on integer coordinates.

For example, to test if a point P(*xP*, *yP*) lies within the triangle with vertices A(20, 15), B(100, 30) and C(80, 150), we can use the following fragment:

```
int[] x = {20, 100, 80}, y
Polygon p = new Polygon(x,
if (p.contains(xP, yP)) ..
```

If P lies exactly on a polygon edge, the value returned by this method *contains* of the class *Polygon* can be *true* or *false*.

2.10 POINT-ON-LINE TEST

Testing whether a point P lies on a given line is very simple if this line is given as an equation, say,

$$ax + by = h \qquad (2.7)$$

Then all we need to do is to test whether the coordinates of P satisfy this equation. Due to inexact computations, such a test may fail when it should succeed. It may therefore be wise to be slightly more tolerant, so that we might write

```
if (Math.abs(a * p.x + b *
```

where *eps* is some small positive value, such as 10^{-5}.

If the line is not given by an equation but by two points A and B on it, we can use the above test after deriving an equation for the line, as discussed in Section 2.3, writing

$$\begin{vmatrix} x & y & 1 \\ x_A & y_A & 1 \\ x_B & y_B & 1 \end{vmatrix} = 0$$

which gives the following coefficients for Equation (2.7):

$$a = y_A - y_B$$

$$b = x_B - x_A$$

$$b = x_B y_A - x_A y_B$$

Instead, we can benefit from the *area*2 method, which we are now familiar with. After all, if and only if P lies on the line through A and B, the triangle ABP is degenerated and has a zero area. We can therefore write

```
if (Math.abs(Tools2D.area2
```

Again, if we simply test whether the computed area is equal to zero, such a test might fail when it should succeed, due to

rounding-off errors.

2.10.1 Testing Whether a Point Lies on a Line Segment

If three points A, B and P are given, we may want to determine whether P lies on the closed line segment AB. The adjective *closed* here means that we include the endpoints A and B, so that the question is to be answered affirmatively if P lies between A and B or coincides with one of these points. We

assume that A and B are different points, which implies that $x_A \neq x_B$ or $y_A \neq y_B$. If $x_A \neq x_B$ we test whether x_P lies between x_A and x_B; if not, we test whether y_P lies between y_A and y_B, where in both cases the word *between* includes the points A and B themselves. This test is sufficient if it is given that P lies on the infinite line AB. If that is not given, we also have to perform the above test, which is done in the following method:

```
static boolean onSegment(P
{  double dx = b.x - a.x,
```

```
        eps = 0.001 * (dx *
    return
        (a.x != b.x &&
        (a.x <= p.x && p.x <
        || a.x == b.x &&
        (a.y <= p.y && p.y <
        && Math.abs(Tools2D.
}
```

The expression following *return* relies on the operator && having higher precedence than ||. Since both operators && and || evaluate the second operand only if this is necessary, this test is more efficient than it looks. For example, if $x_A \neq x_B$ thetestonthelineoftheform(*a.y* <=

…) is not evaluated at all. The positive constant *eps* in the above code has been chosen in such a way that the area of triangle ABP is compared with a fraction of another area, for which the square of side AB is used. In this way, the compared areas depend in the same way on both the length of AB and the unit of length that is used.

Instead of testing if P lies on the segment AB, we may want to apply a similar test to the projection P′ of P on AB, as Figure 2.10 shows.



Figure 2.10: Projection P′ of P on line AB between A and B

We can solve this problem by computing the dot product of the vectors **AB** and **AP**. This dot product **AB** · **AP** is equal to 0 if P′ ≡ A(P′ coincides with A) and it is equal to **AB** · **AB** = AB^2 if P′ ≡ B. For any value of this dot product between these two values, P lies between A and B.

We can write this as follows in a program, where *len2* corresponds to **AB** · **AB**, *inprod* corresponds to **AB** · **AP**,and *eps* is some small positive value, as discussed for the above method *onSegment*:

```
// Does P' (P projected on
static boolean projOnSegme
{ double dx = b.x - a.x, d
      eps = 0.001 * (dx *
      len2 = dx * dx + dy
      inprod = dx * (p.x -
   return inprod > -eps &&
}
```

To determine whether P′ lies on the *open* segment AB (not

including A and B), we replace the return statement with

```
return inprod > eps && inp
```

2.11 DISTANCE BETWEEN A POINT AND A LINE

We can find the distance between a point P and a line *l* in different ways, depending on the way the line is specified. If two points A and B of the line are given, we can find the distance between a point P and the (infinite) line *l* through A and B by using the first of the two methods *area*2 defined in Section 2.7:

$$\text{distance between P and line AB} = d = \frac{|area2(\text{A},\text{B},\text{P})|}{|\text{AB}|}$$

This follows from the fact that the absolute value of *area*2(A, B, P) denotes the area of the parallelogram of which A, B and P are three vertices, as shown in Figure 2.11(a). This area is also equal to the product of the parallelogram's base AB and its height *d*. We can therefore compute *d* in the above way.



Figure 2.11: Distance between point P and line *l*

If the line *l* is given as an equation, we assume this to be in the form

$$ax + by = b$$

where

$$\sqrt{a^2 + b^2} = 1$$

If the latter condition is not satisfied, we only have to divide *a, b* and *h* by the above square root. We can then write the above equation of line *l* as the dot product

$$\mathbf{x} \cdot \mathbf{n} = h$$

where

$$\mathbf{n} = \begin{pmatrix} a \\ b \end{pmatrix} \text{ and } \mathbf{x} = \begin{pmatrix} x \\ y \end{pmatrix}$$

The normal vector **n** is

perpendicular to line *l* and has length 1. For any vector **x**, starting at O, the dot product **x** · **n** is the projection of vector **x** on **n**. This also applies if the endpoint of **x** lies on line *l*, as shown in Figure 2.11(b); in this case we have **x** · **n** = *h*. We find the desired distance between point P and line *l* by projecting **OP** also on **n** and computing the difference of the two projections:

$$\text{Distance between P and line } l = |\mathbf{OP}\cdot\mathbf{n} - h| = |ax_P + by_P - h|$$

Although Figure 2.11(b) applies to the case $h > 0$, this equation is also valid if *h* is negative or zero,

or if O lies between line *l* and the line through P parallel to *l*. Both **OP** · **n** and *h* are scale factors for the same vector **n**. The absolute value of the algebraic difference of these two scale factors is the desired distance between P and *l*. We will refer to this algebraic difference **OP** · **n** $- h = ax_P + by_P - h$ as a *signed distance* in the next section.

2.12 PROJECTION OF A POINT ON A LINE

Suppose that again a line *l* and a point P (not on *l*) are given and that we want to compute the projection P′ of P on *l* (see Figure 2.10). This point P′ has three interesting properties:

1. P′ is the point on *l* that is closest to P.

2. The length of PP′ is the distance between P and *l* (computed in the previous section).

3. PP′ and *l* are perpendicular.

As in the previous section, we discuss two solutions: one for a line *l* given by two points A and B, and the other for *l* given as the equation $\mathbf{x} \cdot \mathbf{n} = h$.

With given points A and B on line *l*, the situation is as shown in Figure 2.10. Recall that in Section 2.10 we discussed the method *projOnSegment* to test if the projection P′ of P on the line through A and B lies between A and B. In that method, we did not actually compute the position of

P′. We will now do this (see Figure 2.10), first by introducing the vector **u** of length 1 and direction **AB**:

$$\mathbf{u} = \frac{1}{|\mathrm{AB}|}\mathrm{AB}$$

Then the length of the projection AP′ of AP is equal to

$$\lambda = \mathbf{AP} \cdot \mathbf{u}$$

which we use to compute

$$\mathbf{AP'} = \lambda \mathbf{u}$$

Doing this straightforwardly would require a square-root

operation in the computation of the distance between A and B, used in the computation of **u**. Fortunately, we can avoid this by rewriting the last equation, using the two preceding ones:

$$AP' = (AP \cdot u)u = \left(AP \cdot \frac{1}{|AB|}AB\right)\frac{1}{|AB|}AB = \frac{1}{|AB|^2}(AP \cdot AB)AB$$

The advantage of the last form is that the square of the segment length AB is easier to compute than that length itself. The following method, which returns the projection P′ of P on AB, demonstrates this:

```
// Compute P' (P projected
```

```
static Point2D projection(
{  float vx = b.x - a.x, v
      inprod = vx * (p.x -
   return new Point2D(a.x
                      a.y
}
```

So much for a line given by two points A and B.

Let us now turn to a line *l* given by its equation, which we again write as

$$\mathbf{x} \cdot \mathbf{n} = h$$

where

$$\mathbf{n} = \begin{pmatrix} a \\ b \end{pmatrix} \text{ and } \mathbf{x} = \begin{pmatrix} x \\ y \end{pmatrix}$$

and

$$\sqrt{a^2 + b^2} = 1$$

Using the ‘signed distance’

$$d = \mathrm{OP} \cdot \mathbf{n} - b$$

as introduced at the end of the previous section and illustrated by Figure 2.11, we can write the following vector equation to compute the desired projection P ′ of P on *l*:

$$\mathrm{OP}' = \mathrm{OP} - d\mathbf{n} = \begin{pmatrix} x_P \\ y_P \end{pmatrix} - d \begin{pmatrix} a \\ b \end{pmatrix}$$

This should make the following method clear:

```
// Compute P', the project
// ax + by = h, where a *
static Point2D projection(
    Point2D p)
{   floatd = p.x * a + p.y
    return new Point2D(p.x
}
```

2.13 TRIANGULATION OF POLYGONS

In many graphics applications, such as those to be discussed in Chapters 6 and 7, it is desirable to divide a polygon into triangles. This triangulation problem can be solved in many ways. We will discuss a comparatively simple algorithm. It accepts a polygon in the form of an array of *Point2D* elements (see Section 1.5), containing the polygon vertices in counter-clockwise order. The *triangulate* method that we will discuss takes such an array as

an argument. To store the resulting triangles, it also takes a second argument, an array with elements of type *Triangle*, which is defined as follows:

```
// Triangle.java: Class tc
//    vertices in logical
// Uses: Point2D (Section

class Triangle
{  Point2D a, b, c;
   Triangle(Point2D a, Poi
   { this.a = a; this.b =
   }
}
```

If the given polygon has *n* vertices, this triangle array should

have length $n - 2$. The algorithm works as follows. Traversing the vertices of the polygon in counter-clockwise order, for every three successive vertices P, Q and R of which Q is a convex vertex (with an angle less than 180°), we cut the triangle PQR off the polygon if this triangle does not contain any of the other polygon vertices. For example, starting with polygon ABCDE in Figure 2.12, we cannot cut triangle ABC, because this contains vertex D. Nor is triangle CDE a good candidate, because D is not a convex

vertex. There are no such problems with triangle BCD, so that we will cut this off the polygon, reducing the polygon ABCDE to the simpler one ABDE.



Figure 2.12: Cutting off a triangle

For this purpose we use the static method *triangulate*, which, along with some others already discussed, is listed in the class *Tools2D* below:

```
// Tools2D.java: Class to
// Uses: Point2D (Section

class Tools2D
{  static float area2(Poin
   { return (a.x - c.x) *
   }

   static boolean insideTr
      Point2D p) // ABC is
   { return
        Tools2D.area2(a, b,
        Tools2D.area2(b, c,
```

```
    Tools2D.area2(c, a,
}

static void triangulate
{  // p contains all n
   // The resulting tri
   // This array tr mus
   int n = p.length, j
   int[] next = new int
   for (int i=0; i<n; i
   {  next[j] = i;
      j = i;
   }
   for (int k=0; k<n-2;
   {  // Find a suitabl
      // and an interna
      Point2D a, b, c;
      boolean triaFound
      int count = 0;
```

```
while (!triaFound
{   iB = next[iA];
    a = p[iA]; b =
    if (Tools2D.ar
    {   // Edges AB
        // Test to
        // lies wit
        j = next[iC
        while (j !=
            j = next
        if (j == iA
        {   // Trian
            tr[k] =
            next[iA]
            triaFoun
        }
    }
    iA = next[iA];
}
```

```
            if (count == n)
            {   System.out.pri
                  " or vertex
               System.exit(1)
            }
         }
      }

      static float distance2(
      {   float dx = p.x - q.x
            dy = p.y - q.y;
      return dx * dx + dy * d
      }
}
```

In Appendix D we will use the method *distance*2, shown at the end of this class; it simply computes the square of the

distance of two points P and Q. If we only want to compare two distances, we may as well compare their squares to save the rather costly operation of computing the square roots.

The program below enables the user to define a polygon, in the same way as wedidwithprogram *DefPoly.java* in Section 1.5, but this time the polygon will be divided into triangles, which appear in different colors. This program, *PolyTria.java*, uses the above classes *Triangle* and *Tools2D*,as well as the class

CvDefPoly, which occurs in program *DefPoly.java* of Section 1.5. In our subclass, *CvPolyTria*, we apply the method *ccw*, discussed in Section 2.6, to the given polygon to examine the orientation of its vertex sequence. If this happens to be clockwise, we put the vertices in reverse order in the array *P*,sothat the vertex sequence will be counter-clockwise in this array, which we can then safely pass on to the *triangulate* method:

```
// PolyTria.java: Drawing
// Uses: CvDefPoly, Point2
```

```
//          Triangle, Tools2D

import java.awt.*;
import java.awt.event.*;
import java.util.*;
public class PolyTria exte
{  public static void main

   PolyTria()
   {  super("Define polygc
      addWindowListener(ne
         {public void winc
      setSize (500, 300);
      add("Center", new Cv

   setCursor(Cursor.getPre
         show();
   }
}
```

```
class CvPolyTria extends C
{  public void paint(Graph
   { int n = v.size();
   if (n > 3 && ready)
   {  Point2D[] p = new Pc
      for (int i=0; i<n; i
      // If not counter-cl
      if (!ccw(p))
         for (int i=0; i<n
            p[i] = (Point
      int ntr = n - 2;
      Triangle[] tr = new
      Tools2D.triangulate(
      initgr();

      for (int j=0; j<ntr;
      {  g.setColor(new Cc
         int[] x = new int
         x[0] = iX(tr[j].a
```

```
            x[1] = iX(tr[j].b
            x[2] = iX(tr[j].c
            g.fillPolygon(x,
        }
    }
    g.setColor(Color.black)
    super.paint(g);
}


int rand(){return (int)(Ma

static boolean ccw(Point2D
  {  int n = p.length, k =
     for (int i=1; i<n; i+
        if (p[i].x <= p[k]
          k = i;
     // p[k] is a convex ve
     int prev = k - 1, next
```

```
        if (prev == -1) prev =
        if (next == n) next =
        return Tools2D.area2(p
    }
}
```

The canvas class *CvPolyTria* is a subclass of *CvDefPoly* so that the construction of a polygon with vertices specified by the user is done in the same way as in Section 1.5. In this subclass, we call the method *triangulate* to construct the array *tr* of triangles. These are then displayed in colors generated with a random number generator, so that we can clearly distinguish them. The

result on the screen is much better than Figure 2.13, because the latter shows only shades of gray instead of the real colors.



Figure 2.13: Triangulation of a polygon

EXERCISES

2.1

Write a program that draws a square ABCD. The points A and B are arbitrarily specified by the user by clicking the mouse button. The orientation of the points A, B, C and D should be counter-clockwise.

Write a program that, for four points A, B, C and P,

- draws a triangle formed by ABC

and a small cross showing the position of P; and

2.2

- displays a line of text indicating which of the following three cases applies: P lies (a) inside ABC, (b) outside ABC, or (c) on an edge of ABC.

The user will specify the four points by clicking.

2.3

The same as Exercise 2.2, but, instead of displaying a line of text, the program computes the distances from P to the (infinite) lines AB, BC and CA, and draws the shortest possible line that connects P with the nearest of those three lines.

Write a program that computes the intersection point of two (infinite) lines AB and CD. The user will

2.4 specify the points A, B, C and D by clicking. Draw a small circle around the intersection point. If the two lines AB and CD do not have a unique intersection point (because they are parallel or coinciding), display a line of text indicating this.

Write a program that constructs the bisector of the angle ABC

(which divides the angle at B into two equal angles). After the user has specified the points A, B and C by clicking, the program should compute the intersection point D of this bisector with the opposite side AC, and draw both triangle ABC and bisector BD.

2.5 Write a program that draws the *circumscribed*

circle (also known as the *circumcircle*) of a given triangle ABC; this circle passes through the points A, B and C. These points will be specified by the user by clicking the mouse button. Remember, the three perpendicular bisectors of the three edges of a triangle all pass through one point, the *circumcenter*, which is the center of the circumscribed circle.

2.6

Write a program that, for

three given points P, Q and R specified by the user, draws a circular arc, starting at P, passing through Q and ending at R (see also Exercise 2.6).

2.7

Construct a fillet to replace a sharp corner with a rounded one, as illustrated by the solid lines and the arc in Figure 2.14. The four points A, B, C and D are specified by the user by clicking. Point D may or may not lie on AB; if it does not, it is projected onto AB, giving D′, as

2.8 Figure 2.14 illustrates. The arc starts at point D′.



Figure 2.14: Fillet

Construct the *inscribed circle* (or *incircle*) of a given triangle ABC. The

center of this circle lies on the point of intersection of the (internal) bisectors of the three angles A, B and C. Draw also the three *excircles*, which, like the incircle, are tangent to the sides of the triangle, as shown in Fig. 2.15. The centers of the excircles lie on the points of intersection of the external bisectors of the angles A, B and C.

2.9



Figure 2.15: Incircle and excircles of triangle
ABC

Write a program that draws a tree of Pythagoras as shown in Figure 2.16. Two vertices A and B, the

basis of the tree, are specified by the user by clicking. Then both a square ABCD and an isosceles, right-angled triangle DCE, with right angle E, are constructed. The orientation of both ABCD and DCE is counter-clockwise.

2.10 Finally, the points D and E form the basis of another tree of Pythagoras, and so do the points E and C. Use a recursive method,

which does nothing at all if the two supplied basis points are closer together than some limit.



Figure 2.16: Tree of Pythagoras

Answers

2.1 After rotating the vector **v**
vector $(-v_2, v_1)$. Setting **v**
points D and C by adding

2.2 To determine the posit
whether P lies on one
onSegment, discussed
whether P lies inside A
To do this properly, we
which we can use the
clockwise, we use C, B
insideTriangle, so that
clockwise, as required.

triangle, it lies outside

Section 2.11 shows how t
perform this computation t
BC and CA (or rather the i
then use the method *proje*
triangle side in question (o
segment PP′. If the projec
this point to the side (AB,
been used. For example, i
draw P′B.

2.3

Using the vector **AB** = **u** =
represent the line through

$$\mathbf{A} + \lambda \mathbf{u}$$

Similarly, with **CD** = **v** = (v
C and D is represented by

$$\mathbf{C} + \lambda\mathbf{v}$$

We find the intersection po

$$\mathbf{A} + \lambda\mathbf{u} = \mathbf{C} + \lambda\mathbf{v}$$

for λ (rewriting this vector
y- coordinates of A and C
computed in this way to fi

$$\mathbf{S} = \mathbf{A} + \lambda\mathbf{u}$$

2.4

When deriving the desired
expression $u_2v_1 - u_1v_2$ (w
and CD do not have a unic

coincide. Since the points
small) rounding-off errors,

$$determinant = 0$$

with this one:

$$|determinant| \leq epsilon$$

where *epsilon* is some ve
of length and in view of th

$$epsilon = 10^{-3}(u_1^2 + u_2^2 + v_1^2 + v_2^2)$$

To construct the bisector o
v = **BC**/|**BC**|. We can view
C, respectively. Since both

$$\mathbf{w} = \mathbf{u} + \mathbf{v}$$

2.5 can then be regarded as a
so that, with parameter α,

$$\mathbf{B} + \alpha\mathbf{w}$$

denotes the bisector of an
side AC can then be found

Using **AB**=**u**=(u_1, u_2)=(x_B
following vector form for tl

$$\mathbf{A} + 0.5\mathbf{u} + \lambda\mathbf{v} \qquad \text{(F.1)}$$

To find the circumcenter D

$$\mathbf{B} + 0.5\mathbf{w} + \mu\mathbf{t} \qquad \text{(F.2)}$$

2.6

for the perpendicular bisec
lines by solving the vector

$$A + 0.5u + \lambda v = B + 0.5w + \mu t$$

for λ (or μ). Then the circu
value λ in Equation (F.1). *A*
and *iY* to convert real logi
the circle through A, B and

```
int xLeft = iX(xD -
    yTop = iY(yD +
g.drawOval(xLeft, y
```

Compute the center C and
2.6). Although there is a m
purpose because it require

if *r* is large, this may caus
of the arc. We therefore s
this by using *Point2D* obje
of P, Q and R into account
2.13), we can write:

```
double alpha = Math
       beta  = Math
if (Tools2D.area2(P
   arcCcw(g, C, r,
else
   arcCcw(g, C, r,
```

The method *arcCcw*, u
it draws the arc with s
the circle with center (

2.7

```
void arcCcw(Graphic
   double alpha, do
```

```
{   double pi2=2* Ma
    // Reduce delta
    delta = (delta +
    int X0=0, Y0=0,
        n = (int)Math
    double theta = d
    for (int i=0; i<
    {   double phi =
            x = C.x +
            y = C.y +
        int X = iX((f
        if (i > 0) g.
        X0 = X; Y0 =
    }
}
```

We can use the first of
the projection D' of D
the bisector of the ang

and **v** = **BC**/|**BC**| and v
C and M, respectively.
w. Since the cosine of

2.8

′|, we can compute λ =
on BC and the center I
the radius of the arc is
angles α and β and dra
method *arcCcw*, depen
Exercise 2.7).

Refer to Exercise 2.8 for t
two lines. This will provide

2.9

radius of each circle as th
have discussed the distan

2.10 Use vector **AB** = (u_1, u_2) t

+ 0.5 $\{(u_1, u_2) + (-u_2, u_1)$

Chapter 3: Geometrical Transformations

To understand perspective projection, which we will discuss in Chapter 5, we need to be familiar with 3D rotations. These and other transformations will be discussed in this chapter. They are closely related to matrix multiplication, which is the subject we start with.

3.1 MATRIX MULTIPLICATION

A *matrix* (plural *matrices*) is a rectangular array of numbers enclosed in brackets (or parentheses). For example,

$$\begin{bmatrix} 2 & 0 & 0.1 & 3 \\ 1 & 4 & 2 & 10 \end{bmatrix}$$

is a 2 × 4 matrix: it consists of two rows and four columns. If a matrix consists of only one row, we call it a *row matrix* or *row vector*. In the same way, we use the term *column matrix* or

column vector for a matrix that has only one column.

If A and B are matrices and the number of columns of A is equal to the number of rows of B, we can compute the *matrix product* AB. This product is another matrix, which has as many rows as A and as many columns as B. We will discuss this in detail for a particular case with regard to the dimensions of A and B: we will use a 2×3matrix A and a 3×4 matrix B. Then the product $C = AB$ exists and is a 2×4 matrix. It will be clear that the matrix

product AB can be computed for A and B of other dimensions in a similar way, provided the number of columns of A is equal to the number of rows of B.

Writing

$$A = \begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \end{bmatrix}$$

and similar expressions for both the matrix B and the product matrix $C = AB$, we have

$$\begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \end{bmatrix} \begin{bmatrix} b_{11} & b_{12} & b_{13} & b_{14} \\ b_{21} & b_{22} & b_{23} & b_{24} \\ b_{31} & b_{32} & b_{33} & b_{34} \end{bmatrix} = \begin{bmatrix} c_{11} & c_{12} & c_{13} & c_{14} \\ c_{21} & c_{22} & c_{23} & c_{23} \end{bmatrix}$$

Each element c_{ij} (found in row i and column j of the product matrix C) is equal to the dot product of the ith row of A and the jth column of B. For example, to find c_{23}, we need the numbers a_{21}, a_{22} and a_{23} in the second row of A and b_{13}, b_{23} and b_{33} in the third column of B. Using these two sequences as vectors, we can compute their dot product, finding

$$c_{23} = (a_{21}, a_{22}, a_{23}) \cdot (b_{13}, b_{23}, b_{33}) = (a_{21}b_{13} + a_{22}b_{23} + a_{23}b_{33})$$

In general, the elements of the above matrix C are computed as

follows:

$$c_{ij} = (a_{i1}, a_{i2}, a_{i3}) \cdot (b_{1j}, b_{2j}, b_{3j}) = a_{i1}b_{1j} + a_{i2}b_{2j} + a_{i3}b_{3j}$$

3.2 LINEAR TRANSFORMATIONS

A transformation *T* is a mapping

$$\mathbf{v} \rightarrow T\mathbf{v} = \mathbf{v}'$$

such that each vector **v** (in the vector space we are dealing with) is assigned its unique image **v′**. Let us begin with the *xy*-plane and associate with each vector **v** the point P, such that

$$\mathbf{v} = \mathrm{OP}$$

Then the transformation *T* is also a mapping

$$\mathrm{P} \rightarrow \mathrm{P}'$$

for each point P in the *xy*-plane, where $\mathbf{OP}' = \mathbf{v}'$.

A transformation is said to be *linear* if the following is true for any two vectors **v** and **w** and for any real number λ:

$$T(\mathbf{v}+\mathbf{w}) = T(\mathbf{v}) + T(\mathbf{w})$$

$$T(\lambda\mathbf{v}) = \lambda T(\mathbf{v})$$

By using λ = 0 in the last equation, we find that, for any linear transformation, we have

$$T(0) = 0$$

We can write any linear transformation as a matrix multiplication. For example, consider the following linear transformation:

$$\begin{cases} x' = 2x \\ y' = x + y \end{cases}$$

We can write this as the matrix product

$$\begin{bmatrix} x' \\ y' \end{bmatrix} = \begin{bmatrix} 2 & 0 \\ 1 & 1 \end{bmatrix} \begin{bmatrix} x \\ y \end{bmatrix} \tag{3.1}$$

or as the following:

$$[\,x' \quad y'\,] = [\,x \quad y\,]\begin{bmatrix} 2 & 1 \\ 0 & 1 \end{bmatrix} \qquad (3.2)$$

The notation of (3.1) is normally used in standard mathematics textbooks; in computer graphics and other applications in which transformations are combined, the notation of (3.2) is also popular because it avoids a source of mistakes, as we will see in a moment. We will therefore adopt this notation, using row vectors.

It is interesting to note that, in

(3.2), the rows of the 2 × 2 transformation matrix are the images of the unit vectors (1, 0) and (0, 1), respectively, while these images are the columns in (3.1). You can easily verify this by substituting [1 0] and [0 1] for [*x y*] in (3.2), as the bold matrix elements below illustrate:

$$\begin{bmatrix} 2 & 1 \end{bmatrix} = \begin{bmatrix} 1 & 0 \end{bmatrix} \begin{bmatrix} 2 & 1 \\ 0 & 1 \end{bmatrix}$$

$$\begin{bmatrix} 0 & 1 \end{bmatrix} = \begin{bmatrix} 0 & 1 \end{bmatrix} \begin{bmatrix} 2 & 1 \\ 0 & 1 \end{bmatrix}$$

This principle also applies to other linear transformations. It

provides us with a convenient way of finding the transformation matrices.

3.2.1 Rotation

To rotate all points in the *xy*-plane about O through the angle ϕ, we can now easily write the transformation matrix, using the rule we have just been discussing. We simply find the images of the unit vectors (1, 0) and (0, 1). As we know from elementary trigonometry, rotating the points P(1, 0) and Q(0, 1) about O through the angle ϕ

gives $P'(\cos \phi, \sin \phi)$ and $Q'(-\sin \phi, \cos \phi)$. It follows that $(\cos \phi, \sin \phi)$ and $(-\sin \phi, \cos \phi)$ are the desired images of the unit vectors (1, 0) and (0, 1), as Figure 3.1 illustrates.



Figure 3.1: Rotation of unit vectors

Then all we need to do is to write these two images as the rows of our rotation matrix:

$$[\,x' \quad y'\,] = [\,x \quad y\,] \begin{bmatrix} \cos\varphi & \sin\varphi \\ -\sin\varphi & \cos\varphi \end{bmatrix} \qquad (3.3)$$

3.2.2 A Programming Example

To see rotation in action, let us rotate an arrow about the origin O. Before this rotation, the arrow is vertical, points upward and can be found to the right of O. We will rotate this angle through 120° about the origin O, which is the

center of the canvas. Figure 3.2 shows the coordinate axes (intersecting at O) and the arrow before and after the rotation.



Figure 3.2: Arrow before and after rotation through 120° about the

origin

If we change the dimensions of the window, the origin remains in the center and the sizes of the arrows and of the circle on which they lie change accordingly, while this circle remains a circle. Recall that we also placed the origin at the center of the canvas in the *Isotrop.java* program in Section 1.4, when dealing with the isotropic mapping mode. The following program also uses this mapping mode and contains the same methods *iX* and *iY* for the conversion from logical to device coordinates:

```
// Arrow.java: Arrow rotat
//                origin O, w
import java.awt.*;
import java.awt.event.*;

public class Arrow extends
{  public static void main

   Arrow()
   {  super("Arrow rotated
      addWindowListener(ne
         {public void winc
      setSize (400, 300);
      add("Center", new Cv
      show();
   }
}
class CvArrow extends Canv
{  int centerX, centerY, c
```

```
float pixelSize, rWidth

void initgr()
{  Dimension d = getSiz
   int maxX = d.width -
   pixelSize = Math.max
   centerX = maxX/2; ce
}

int iX(float x){return
int iY(float y){return

void moveTo(float x, fl
{  currentX = iX(x); cu
}

void lineTo(Graphics g,
{  int x1 = iX(x), y1 =
   g.drawLine(currentX,
```

```
    currentX = x1; curre
}

void drawArrow(Graphics
{  moveTo(x[0], y[0]);
   lineTo(g, x[1], y[1]
   lineTo(g, x[2], y[2]
   lineTo(g, x[3], y[3]
   lineTo(g, x[1], y[1]
}

public void paint(Graph
{ float r = 40.0F;
  float[] x = {r, r, r-
          y = {-7, 7, 0
  initgr();
// Show coordinate axes
moveTo (30, 0); lineTo(
// Show initial arrow:
```

```
    drawArrow(g, x, y);
    float phi = (float)(2 *
       c = (float)Math.cos(
         r11 = c, r12 = s,
     for (int j=0; j<4; j++
     {  float xNew = x[j] *
                yNew = x[j] *
        x[j] = xNew; y[j] =
     }
     // Arrow after rotatic
     drawArrow(g, x, y);
  }
}
```

The logical coordinates of the four relevant points of the arrow are stored in the arrays *x* and *y*, and the variables *r*11, *r*12, *r*21 and *r*22 denote the elements of

the rotation matrix. When programming rotations, we should be careful with two points. First, with a constant angle ϕ, we should compute cos ϕ and sin ϕ only once, even though they occur twice in the rotation matrix. Second, a serious and frequently occurring error is modifying *x*[*j*] too early, that is, while we still need the old value for the computation of *y*[*j*], as the following, incorrect fragment shows:

```
x[j] = x[j] * r11 + y[j] *
y[j] = x[j] * r12 + y[j] *
```

There is no such problem if we use temporary variables *xNew* and *yNew* (although only the former is really required), as is done in the program.

3.2.3 Scaling

Suppose that we want to perform scaling with scale factors s_x for x and s_y for y and with point O remaining at the same place; the latter is also expressed by referring to O as a *fixed point* or by a *scaling with reference to* O. This can obviously be written as

$$\begin{cases} x' = s_x x \\ y' = s_y y \end{cases}$$

which can also be written as a very simple matrix multiplication:

$$[\, x' \quad y' \,] = [\, x \quad y \,] \begin{bmatrix} s_x & 0 \\ 0 & s_y \end{bmatrix}$$

There are some important special cases:

$s_x = s_y = -1$	gives a reflection about O;
$s_x = 1,$ $s_y = -1$	gives a reflection about the *x*-axis;

s_x = −1, s_y = 1 gives a reflection about the *y*-axis.

3.2.4 Shearing

Consider the linear transformation given by

$$(1, 0) \rightarrow (1, 0)$$

$$(0, 1) \rightarrow (a, 1)$$

Since the images of the unit vectors appear as the rows of the transformation matrix, we can write this transformation, known

as *shearing*,as

$$[\,x' \quad y'\,] = [\,x \quad y\,]\begin{bmatrix} 1 & 0 \\ a & 1 \end{bmatrix}$$

or

$$\begin{cases} x' = x + ay \\ y' = y \end{cases}$$

This set of equations expresses that each point (x, y) moves a distance ay to the right, which has the effect of shearing along the x-axis, as illustrated in Figure 3.3. We can use this transformation to turn regular

characters into italic ones; for example, **L** becomes ***L***.



Figure 3.3: Shearing effects (dashed lines) on a square object (solid lines)

Shearing along the *y*-axis, also depicted in Figure 3.3, can be

similarly expressed as

$$[\ x' \quad y'\ ] = [\ x \quad y\ ] \begin{bmatrix} 1 & b \\ 0 & 1 \end{bmatrix}$$

or

$$\begin{cases} x' = x \\ y' = bx + y \end{cases}$$

3.3 TRANSLATIONS

Shifting all points in the *xy*-plane a constant distance in a fixed direction is referred to as a *translation*. This is another transformation, which we can write as:

$$x' = x + a$$

$$y' = y + b$$

We refer to the number pair (*a*, *b*) as the *shift vector*,or *translation vector*. Although this transformation is a very simple one, it is not linear, as we can

easily see by the fact that the image of the origin (0, 0) is (*a*, *b*), while this can only be the origin itself with linear transformations. Consequently, we cannot obtain the image (x', y') by multiplying (x, y) by a 2 × 2 transformation matrix T, which prevents us from combining such a matrix with other transformation matrices to obtain composite transformations. Fortunately, there is a solution to this problem as described in the following section.

3.4 HOMOGENEOUS COORDINATES

To express all the transformations introduced so far as matrix multiplications in order to combine various transformation effects, we add one more dimension. As illustrated in Figure 3.4, the extra dimension W makes any point P = (x, y) of normal coordinates have a whole family of homogeneous coordinate representations (wx, wy, w) for any value of w except 0. For example, (3, 6, 1), (0.3, 0.6,

0.1), (6, 12, 2), (12, 24, 4) and so on, represent the same point in two-dimensional space. Similarly, 4-tuples of coordinates represent points in three-dimensional space. When a point is mapped onto the W = 1 plane, in the form (*x*, *y*, 1), it is said to be *homogenized*. In the above example, point (3, 6, 1) is homogenized, and the numbers 3, 6 and 1 are *homogeneous coordinates*. In general, to convert a point from normal coordinates to homogeneous coordinates, add a new dimension to the right with value

1. To convert a point from homogeneous coordinates to normal coordinates, divide all the dimension values by the rightmost dimension value, and then discard the rightmost dimension.



Figure 3.4: A homogeneous coordinate system with the plane $W = 1$

Having introduced homogeneous coordinates, we are able to describe a translation by a matrix multiplication using a 3 × 3

instead of a 2 × 2 matrix. Using a shift vector (*a*, *b*), we can write the translation of Section 3.3 as the following matrix product:

$$[\,x' \quad y' \quad 1\,] = [\,x \quad y \quad 1\,] \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ a & b & 1 \end{bmatrix} \tag{3.4}$$

Since we cannot multiply a 3 × 3 by a 2 × 2 matrix, we will also add a row and a column to linear transformation matrices if we want to combine these with translations (and possibly with other non-linear transformations). These additional rows and columns simply consist of zeros followed by a one at the end. For

example, we can use the following equation instead of 3.3 (in Section 3.2) for a rotation about O through the angle ϕ:

$$[\,x' \quad y' \quad 1\,] = [\,x \quad y \quad 1\,] \begin{bmatrix} \cos\varphi & \sin\varphi & 0 \\ -\sin\varphi & \cos\varphi & 0 \\ 0 & 0 & 1 \end{bmatrix} \qquad (3.5)$$

3.5 INVERSE TRANSFORMATIONS AND MATRIX INVERSION

A linear transformation may or may not be reversible. For example, if we perform a rotation about the origin through an angle ϕ and follow this by another rotation, also about the origin but through the angle $-\phi$, these two transformations cancel each other out. Let us denote the rotation matrix of Equation (3.3) (in Section 3.2) by R. It follows

that the inverse rotation, through the angle $-\phi$ instead of ϕ, is described by the equation

$$[\ x' \quad y'\ ] = [\ x \quad y\ ]\, R^{-1}$$

where

$$R^{-1} = \begin{bmatrix} \cos(-\varphi) & \sin(-\varphi) \\ -\sin(-\varphi) & \cos(-\varphi) \end{bmatrix} = \begin{bmatrix} \cos\varphi & -\sin\varphi \\ \sin\varphi & \cos\varphi \end{bmatrix}$$

The second equality in this equation is based on

$$\cos -\varphi = \cos\varphi$$

$$\sin -\varphi = -\sin\varphi$$

Matrix R^{-1} is referred to as the

inverse of matrix *R*. In general, if a matrix *A* has an inverse, this is written A^{-1} and we have

$$AA^{-1} = A^{-1}A = I$$

where *I* is the identity matrix, consisting of zero elements except for the main diagonal, which contains elements one. For example, in the case of a rotation through ϕ, followed by one through $-\phi$, we have

$$RR^{-1} = \begin{bmatrix} \cos\varphi & \sin\varphi \\ -\sin\varphi & \cos\varphi \end{bmatrix} \begin{bmatrix} \cos\varphi & -\sin\varphi \\ \sin\varphi & \cos\varphi \end{bmatrix} = \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} = I$$

The identity matrix clearly maps

each point to itself, that is,

$$[\ x \quad y\ ]I = [\ x \quad y\ ]$$

Not all linear transformations are reversible. For example, the one that projects each point onto the *x*-axis is not. This transformation is described by

$$\begin{cases} x' = x \\ y' = 0 \end{cases}$$

which we can also write as

$$[\ x' \quad y'\ ] = [\ x \quad y\ ]\begin{bmatrix} 1 & 0 \\ 0 & 0 \end{bmatrix}$$

The 2×2 matrix in this equation has no inverse. This corresponds to the impossibility of reversing the linear transformation in question: since any two point $P_1(x, y_1)$ and $P_2(x, y_2)$ have the same image $P'(x, 0)$, it is impossible to find a unique point P of which P' is the image.

A (square) matrix has an inverse if and only if its determinant is non-zero. Recall that we have discussed determinants in Section 2.3. For example, the determinant

$$\begin{vmatrix} \cos\varphi & \sin\varphi \\ -\sin\varphi & \cos\varphi \end{vmatrix}$$

is equal to $\cos\phi \times \cos\phi - (-\sin\phi \times \sin\phi) = \cos^2\phi + \sin^2\phi = 1$. Since this value is non-zero for any angle ϕ, the corresponding matrix

$$\begin{bmatrix} \cos\varphi & \sin\varphi \\ -\sin\varphi & \cos\varphi \end{bmatrix}$$

has an inverse.

Exercise 3.4 shows how to compute the inverse of any 2×2 matrix that has a non-zero

determinant. A useful application of this follows in Exercise 3.5.

3.6 ROTATION ABOUT AN ARBITRARY POINT

So far we have only performed rotations about the origin O. A rotation about any point other than O is not a linear transformation, since it does not map the origin onto itself. It can nevertheless be described by a matrix multiplication, provided we use homogeneous coordinates. A rotation about the point C(x_C, y_C) through the angle ϕ can be performed in three steps:

1. A translation from C to O, described by [x' y'

1] = [x y 1]T^{-1}, where

$$T^{-1} = \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ -x_C & -y_C & 1 \end{bmatrix}$$

2. A rotation about O through the angle ϕ described by [x' y' 1] = [x y 1] R_O, where

$$R_O = \begin{bmatrix} \cos\varphi & \sin\varphi & 0 \\ -\sin\varphi & \cos\varphi & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

3. A translation from O to C, described by [x' y'

1] = [*x* *y* 1]*T*, where

$$T = \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ x_C & y_C & 1 \end{bmatrix}$$

Note that we deliberately use the notations T^{-1} and T, since these two matrices are each other's inverse. This is understandable, since the operations of translating from C to O and then back from O to C cancel each other out.

The purpose of listing the above three matrices is that we can

combine them by forming their product. Therefore, the desired rotation about point C through the angle ϕ can be described by

$$\begin{bmatrix} x' & y' & 1 \end{bmatrix} = \begin{bmatrix} x & y & 1 \end{bmatrix} R$$

where

$$\begin{aligned} R &= T^{-1} R_\theta T \\ &= \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ -x_C & -y_C & 1 \end{bmatrix} \begin{bmatrix} \cos\varphi & \sin\varphi & 0 \\ -\sin\varphi & \cos\varphi & 0 \\ 0 & 0 & 1 \end{bmatrix} \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ x_C & y_C & 1 \end{bmatrix} \\ &= \begin{bmatrix} \cos\varphi & \sin\varphi & 0 \\ -\sin\varphi & \cos\varphi & 0 \\ -x_C\cos\varphi + y_C\sin\varphi + x_C & -x_C\sin\varphi - y_C\cos\varphi + y_C & 1 \end{bmatrix} \end{aligned} \quad (3.6)$$

3.6.1 An Application

To see this general type of

rotation in action, we will now discuss a program which rotates an arrow through 30° about a point selected by the user. Initially, one arrow, pointing vertically upward, appears in the center of the canvas. As soon as the user clicks a mouse button, a second arrow appears. This is the image of the first one, resulting from a rotation through an angle of 30° about the cursor position. This position is displayed as a crosshair cursor in Figure 3.5.



Figure 3.5: Arrow before and after rotation through 30° about a point selected by the user

This action can be done repeatedly, in such a way that the

most recently rotated arrow is again rotated when the user clicks, and this last rotation is performed about the most recently selected point. Since the rotation is counter-clockwise, the new arrow would have appeared below the old one in Figure 3.5 if the user had selected a point to the right instead of to the left of the first arrow. Program *ArrowPt.java* shows how this rotation is computed.

```
// ArrowPt.java: Arrow rot
//     about a point select
import java.awt.*;
import java.awt.event.*;
```

```
public class ArrowPt exten
{  public static void main
   ArrowPt()
   {  super("Arrow rotated
      addWindowListener(ne
         {public void winc
      setSize (400, 300);
      add("Center", new Cv
      setCursor(Cursor.get
      show();
   }
}

class CvArrowPt extends Ca
{  int centerX, centerY, c
   float pixelSize, xP = 1
      rWidth = 100.0F, rHe
   float[] x = {0, 0, -2,
```

```
CvArrowPt()
{  addMouseListener(new
   {  public void mouse
      {  xP = fx(evt.ge
         repaint();
      }
   });
 }
 void initgr()
 {  Dimension d = getSi
 int maxX = d.width - 1
 pixelSize = Math.max(r
 centerX = maxX/2; cent
 }

 int iX(float x){return
 int iY(float y){return
```

```
float fx(int x){return
float fy(int y){return

void moveTo(float x, f
{ currentX = iX(x); cu
}
void lineTo(Graphics g
{   int x1 = iX(x), y1
    g.drawLine(currentX
    currentX = x1; curr
}

void drawArrow(Graphic
{   moveTo(x[0], y[0]);
    lineTo(g, x[1], y[1
    lineTo(g, x[2], y[2
    lineTo(g, x[3], y[3
    lineTo(g, x[1], y[1
}
```

```
    public void paint(Grap
    { initgr();
      // Show initial arrc
      drawArrow(g, x, y);
      if (xP > 1e8F) retur
      float phi = (float)(
         c = (float)Math.c
         r11 = c, r12 = s,
         r21 = -s, r22 = c
         r31 = -xP * c + y
      for (int j=0; j<4; j
      {  float xNew = x[j]
                yNew = x[j]
         x[j] = xNew; y[j]
      }
      // Arrow after rotat
      drawArrow(g, x, y);
}
```

```
}
```

In contrast to program *Arrow.java* of Section 3.2, this new program *ArrowPt. java* uses the 3 × 3 rotation matrix displayed in Equation (3.6), as you can see in the fragment

```
float xNew = x[j] * r11 +
      yNew = x[j] * r12 +
```

The matrix elements r_{31} and r_{32} of the third row of the matrix depend on the point (x_P, y_P), selected by the user and acting as the center $C(x_C, y_C)$ in our previous discussion. As in

program *Isotrop.java* of Section 1.4, the device coordinates of the selected point P are converted to logical coordinates by the methods *fx* and *fy*.

3.7 CHANGING THE COORDINATE SYSTEM

In the preceding sections, we have used a fixed coordinate system and applied transformations to points given by their coordinates for that system, using certain computations. We can use exactly the same computations for a different purpose, leaving the points unchanged but changing the coordinate system. It is important to bear in mind that the direction in which the coordinate system moves is

opposite to that of the point movement. We can see this very clearly in the case of a translation. In Figure 3.6(a) we have a normal translation with any point P(x, y) mapped to its image P′ (x', y'), where

$$x' = x + a$$

$$y' = y + b$$



Figure 3.6: (a) Translation; (b) change of coordinates

which can be written in matrix form as shown in Equation (3.4) (in Section 3.4). In Figure 3.6(b) we do not map the point P to another point but we express the position of this point in the $x'y'$-

coordinate system, while coordinates *x* and *y* are given. As you can see, a translation upward and to the right in (a), corresponds with a movement of the coordinate system downward and to the left in (b): these two directions are exactly each other's opposite. It follows that the inverse translation matrix would have applied if, in (b), we had moved the axes in the same direction as that of the point translation. The same principle applies to other transformations, such as rotations, for which the inverse of the transformation

matrix exists. We will use this principle in the next section.

3.8 ROTATIONS ABOUT 3D COORDINATE AXES

Let us use a right-handed three-dimensional coordinate system, with the positive *x*-axis pointing toward us, the *y*-axis pointing to the right and the *z*-axis pointing upward, as shown in Figure 3.7.



Figure 3.7: Rotations about coordinate
axes

This figure also shows what we mean by rotations about the axes. A rotation about the *z*-axis through a given angle implies a

rotation of all points in the *xy*-plane through that angle. For example, if this angle is 90°, the image of all points of the positive *x*-axis will be those of the positive *y*-axis. In the same way, a rotation about the *x*-axis implies a similar rotation of the *yz*-plane and a rotation about the *y*-axis implies a similar rotation of the *zx*-plane. Note that we deliberately write *zx* in that order: when we are dealing with the *x*-, *y*-and *z*-axes in a cyclic way, *x* follows *z*. It is important to remember this when we have to write down the transformation

matrices for the rotations about the *x*-, *y*-and *z*-axis through the angle ϕ:

$$R_x = \begin{bmatrix} 1 & 0 & 0 \\ 0 & \cos\varphi & \sin\varphi \\ 0 & -\sin\varphi & \cos\varphi \end{bmatrix}$$

$$R_y = \begin{bmatrix} \cos\varphi & 0 & -\sin\varphi \\ 0 & 1 & 0 \\ \sin\varphi & 0 & \cos\varphi \end{bmatrix}$$

$$R_z = \begin{bmatrix} \cos\varphi & \sin\varphi & 0 \\ -\sin\varphi & \cos\varphi & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

These matrices are easy to

construct. Matrix R_z is derived in a trivial way from the well-known 2 × 2 rotation matrix of Equation (3.3) (in Section 3.2). If you check this carefully, you will not find the other two matrices difficult. First, there is a 1 on the main diagonal in the position that corresponds to the axis of rotation (1 for *x*, 2 for *y* and3for *z*). The other elements in the same row or column as this matrix element 1 are equal to 0. Second, we use the elements of the 2 × 2 matrix just mentioned for the remaining elements of the 3 × 3 matrices, beginning just to

the right and below the element 1, if that is possible; if not, we remember that *x* follows *z*. For example, in R_y, the first element, cos ϕ, of this imaginary 2 × 2 matrix is placed in row 3 and column 3 because the element 1 has been placed in row 2 and column 2. Then, since we cannot place sin ϕ to the right of this element cos ϕ as we would like, we place it instead in column 1 of the same third row. In the same way, we cannot place − sin ϕ below cos ϕ, as it occurs in Equation (3.3), so instead we put it in the first row of the same

third column, and so on.

We should remember that the above matrices should be applied to row vectors. For example, using the above matrix R_x, we write

$$[\, x' \quad y' \quad z' \,] = [\, x \quad y \quad z \,] R_x$$

to obtain the image (x', y', z') of point (x, y, z) when the latter is subjected to a rotation about the x-axis through an angle ϕ.

3.9 ROTATION ABOUT AN ARBITRARY AXIS

To prepare for a three-dimensional rotation about an arbitrary axis, let us first perform such a rotation about an axis through the origin O. Actually, the rotation will take place about a vector, so that we can define its orientation, as illustrated by Figure 3.8.



Figure 3.8: Rotation about a vector starting at O

If a point is rotated about the vector **v** through a positive angle α, this rotation will be such that it corresponds to a movement in the direction of the vector in the same way as turning a (right-handed) screw corresponds to its forward movement.

Instead of its Cartesian coordinates (v_1, v_2, v_3), we will use the angles θ and ϕ to specify the direction of the vector **v**. The length of this vector is irrelevant to our present purpose. As you can see in Figure 3.8, θ is the angle between the positive *x*-

axis and the projection of **v** in the *xy*-plane and ϕ is the angle between the positive *z*-axis and the vector **v**. If v_1, v_2 and v_3 are given and we want to find θ and ϕ, we can compute them in Java in the following way, writing *theta* for θ and *phi* for ϕ:

```
theta = Math.atan2(v2, v1)
phi = Math.atan2(Math.sqrt
```

We will now derive a rather complicated 3 × 3 rotation matrix, which describes the rotation about the vector **v** through an angle α. First, we will change the coordinate system such that **v**

will lie on the positive *z*-axis. This can be done in two steps:

1. A rotation of the coordinate system about the *z*-axis, such that the horizontal component of **v** lies on the new *x*-axis.

2. A rotation of the coordinate system about the new *y*-axis though the angle ϕ.

As discussed at the end of the previous section, coordinate transformations require the

inverses of the matrices that we would use for normal rotations of points. Referring to Section 3.8, we now have to use the following matrices $R^{-1}{}_z$ and $R^{-1}{}_y$ for the above steps 1 and 2, respectively:

$$R_z^{-1} = \begin{bmatrix} \cos\theta & -\sin\theta & 0 \\ \sin\theta & \cos\theta & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

$$R_y^{-1} = \begin{bmatrix} \cos\varphi & 0 & \sin\varphi \\ 0 & 1 & 0 \\ -\sin\varphi & 0 & \cos\varphi \end{bmatrix}$$

To combine these two coordinate

transformations, we have to use the product of these two matrices. Before doing this matrix multiplication, let us first find the matrices of some more operations that are required.

Now that the new positive *z*-axis has the same direction as the vector **v**,the desired rotation about **v** through the angle α is also a rotation about the *z*-axis through that angle, so that, expressed in the new coordinates, we have the following rotation matrix:

$$R_v = \begin{bmatrix} \cos\alpha & \sin\alpha & 0 \\ -\sin\alpha & \cos\alpha & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

Although this may seem to be the final operation, we must bear in mind that we want to express the image point P' of an original point P in terms of the original coordinate system. This implies that the first two of the above three transformations are to be followed by their inverse transformations, in reverse order. Therefore, in this order, we have to use the following two matrices after the three above:

$$R_y = \begin{bmatrix} \cos\varphi & 0 & -\sin\varphi \\ 0 & 1 & 0 \\ \sin\varphi & 0 & \cos\varphi \end{bmatrix}$$

$$R_z = \begin{bmatrix} \cos\theta & \sin\theta & 0 \\ -\sin\theta & \cos\theta & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

The resulting matrix *R*, to be used in the equation

$$[\, x' \quad y' \quad z' \,] = [\, x \quad y \quad z \,]R$$

to perform a rotation about **v** through the angle α, can now be found as follows:

$$R = R_z^{-1} R_y^{-1} R_v R_y R_z = \begin{bmatrix} r_{11} & r_{12} & r_{13} \\ r_{21} & r_{22} & r_{23} \\ r_{31} & r_{32} & r_{33} \end{bmatrix}$$

where the matrix elements r_{ij} are rather complicated expressions in ϕ, θ and α. Before discussing how to compute these, let us first turn to the original problem, which was the same as the above, except that we want to use any point A(a_1, a_2, a_3) as the start point of vector **v**. We can do this by performing, in this order:

- a translation that shifts the point A to the origin

O;

- the desired rotation using the above matrix *R*;

- the inverse of the translation just mentioned.

As discussed in Sections 3.4 and 3.6, we need to use homogeneous coordinates in order to describe translations by matrix multiplications. Since we use 3 × 3 matrices for linear transformations in three-dimensional space, we have to use 4 × 4 matrices in connection

with these homogenous coordinates. Based on the coordinates a_1, a_2 and a_3 of the point A on the axis of rotation, the following matrix describes the translation from A to O:

$$T^{-1} = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ -a_1 & -a_2 & -a_3 & 1 \end{bmatrix}$$

After this translation, we perform the rotation about the vector **v**, which starts at point A, using the above matrix *R*, which we write as *R** after adding an additional row and column in the usual way:

$$R^* = \begin{bmatrix} r_{11} & r_{12} & r_{13} & 0 \\ r_{21} & r_{22} & r_{23} & 0 \\ r_{31} & r_{32} & r_{33} & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix}$$

Finally, we use a translation from O back to A:

$$T = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ a_1 & a_2 & a_3 & 1 \end{bmatrix}$$

Writing R_{GEN} for the desired general (4 × 4) rotation matrix, we have

$$R_{GEN} = T^{-1} R^* T$$

Since R_{GEN} is a 4 × 4 matrix, we use it as follows:

$$[\, x' \quad y' \quad z' \quad 1 \,] = [\, x \quad y \quad z \quad 1 \,] R_{GEN}$$

3.9.1 Implementation

Since we are now dealing with points in three-dimensional space, let us begin by defining the following class to represent such points:

```
// Point3D.java: Represent
class Point3D
{  float x, y, z;
```

```
    Point3D(double x, doubl
    {  this.x = (float)x;
       this.y = (float)y;
       this.z = (float)z;
    }
}
```

As we normally have a great many points that are to be rotated, it is worth-while to compute the matrix R_{GEN} beforehand. Although this could be done numerically, it is also possible to make our program slightly faster by doing this symbolically, that is, by expressing all matrix elements r_{ij} of R_{GEN} in six constant values for

the rotation: the angles ϕ, θ and α and the coordinates a_1, a_2 and a_3 of point A on the axis of rotation. Instead of writing these matrix elements here in the usual mathematical formulas (which would be quite complicated), we may as well immediately present the resulting Java code. This has been done in the class *Rotate*3*D* below.

The actual rotation is performed by the *rotate* method, which is called as many times as there are relevant points (usually the vertices of polyhedra). Prior to

this, the method *initRotate* is called only once, to build the above matrix R_{GEN}. There are actually two methods *initRotate*, of which we can choose one as we like. The first accepts two points A and B to specify the directed axis of rotation AB and computes the angles θ and ϕ. The second accepts these two angles themselves instead of point B:

```
// Rota3D.java: Class used
//    for rotations about
// Uses: Point3D (discusse
class Rota3D
{  static double r11, r12,
```

```
                    r31, r32,

/* The method initRotate c

                | r11 r12 r13
          R =   | r21 r22 r23
                | r31 r32 r33
                | r41 r42 r43

   to be used as [x1 y1 z1
   by the method 'rotate'.
   Point (x1, y1, z1) is t
   The rotation takes plac
   AB and through the angl
*/
   static void initRotate(
      double alpha)
   {  double v1 = b.x - a.
              v2 = b.y - a.
```

```
                v3 = b.z - a.
            theta = Math.atan
            phi = Math.atan2(
            initRotate(a, the
    }

    static void initRotate(
        double phi, double a
    {   double cosAlpha, sin
        cosTheta, sinTheta,
        cosTheta2, sinTheta2
        a1 = a.x, a2 = a.y,
        cosPhi = Math.cos(ph
        cosPhi2 = cosPhi * c
        cosTheta = Math.cos(
        sinTheta = Math.sin(
        cosTheta2 = cosTheta
        sinTheta2 = sinTheta
        cosAlpha = Math.cos(
```

```
        sinAlpha = Math.sin(
        c = 1.0 - cosAlpha;
        r11 = cosTheta2 * (c
              + cosAlpha * s
        r12 = sinAlpha * cos
        r13 = sinPhi * (cosP
        r21 = sinPhi2 * cosT
        r22 = sinTheta2 * (c
              + cosAlpha * c
        r23 = sinPhi * (cosP
        r31 = sinPhi * (cosP
        r32 = sinPhi * (cosP
        r33 = cosAlpha * sin
        r41 = a1 - a1 * r11
        r42 = a2 - a1 * r12
        r43 = a3 - a1 * r13
    }

    static Point3D rotate(P
```

```
    { return new Point3D(
          p.x * r11 + p.y *
          p.x * r12 + p.y *
          p.x * r13 + p.y *
    }
}
```

Note that the actual rotation of points is done very efficiently in the method *rotate* at the end of this class. This is important because it will be called for each relevant point of the object to be rotated. Remember, the more time-consuming method *initRotate* is called only once.

Let us now see this class *Rota*3*D*

in action. Although it can be used for any rotation axis and any angle of rotation, it is used here only in a very simple way so that we can easily check the result, even without graphics output. As Figure 3.9 shows, we have chosen the axis AB parallel to the diagonals 0–2 and 4–6 of the cube. The cube has a height 1 and point A has coordinates (0, 0, 2).



Figure 3.9: Rotation of a cube about the axis AB

The following program uses the above classes *Point3D* and *Rota3D* to perform the rotation shown in Figure 3.9:

```
// Rota3DTest.java: Rotati
//     parallel to a diagon
//     Uses: Point3D, Rota3
public class Rota3DTest
{  public static void main
   {  Point3D a = new Poin
      double alpha = Math.
      // Specify AB as dir
      // and alpha as the
      Rota3D.initRotate(a,
      // Vertices of a cub
      // 4, 5, 6, 7 at the
      Point3D[] v = {
```

```
      new Point3D (0, 0
      new Point3D (1, 1
      new Point3D (0, 0
      new Point3D (1, 1
   System.out.println(
      "Cube rotated thr
   System.out.println(
      "where A = (0, 0,
   System.out.println("
   System.out.println(
      "    Before rotat
   for (int i=0; i<8; i
   {  Point3D p = v[i];
      // Compute P1, th
      Point3D p1 = Rota
      System.out.printl
         p.x + " " +p.y
         f(p1.x) + "" +
   }
```

```
    }

    static double f(double
}
```

Since we have not yet discussed how to produce perspective views, we produce only text output in this program, as listed below:

```
Cube rotated through 180 d
where A = (0, 0, 2) and B
Vertices of cube:
     Before rotation    Afte
0:   0.0 0.0 0.0          0.0
1:   1.0 0.0 0.0          0.0
2:   1.0 1.0 0.0          1.0
```

```
3:   0.0 1.0 0.0          1.0
4:   0.0 0.0 1.0          0.0
5:   1.0 0.0 1.0          0.0
6:   1.0 1.0 1.0          1.0
7:   0.0 1.0 1.0          1.0
```

EXERCISES

In Section 3.2 we discussed
O, that is, with O as a fixed p
different fixed point, say C(x_0
dimensional space, we need
coordinates), writing

$$[\, x' \quad y' \quad 1 \,] = [\, x \quad y \quad 1 \,]M$$

3.1 Using scale factors s_x and s_y

Hint: You can perform a trans
scaling as discussed in Secti
matrix, followed by a translat
you can start with the followi
very clearly what actually hap

$$\begin{cases} x' - x_C = s_x(x - x_C) \\ y' - y_C = s_y(y - y_C) \end{cases}$$

3.2 Describe scaling in three-dim
point C and three scale facto
matrix (similar to matrix *M* of

How can you apply shearing
O (such that this point will re
program that draws a square

3.3 before and after shearing, se
of Section 3.2 equal to 0.5. *A*
with reference to their center
square will remain at the sam
circle.

(This exercise prepares for t
$a_{11}a_{22} - a_{12}a_{21}$ of the matrix

$$A = \begin{bmatrix} a_{11} & a_{12} \\ a_{21} & a_{22} \end{bmatrix}$$

3.4 is non-zero, then the matrix

$$A^{-1} = \begin{bmatrix} \frac{a_{22}}{D} & -\frac{a_{12}}{D} \\ -\frac{a_{21}}{D} & \frac{a_{11}}{D} \end{bmatrix}$$

is the inverse of A, that is, AA

$AA^{-1} = A^{-1}A = I = \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix}$. Pro

Our way of testing whether a
discussed in Section 2.8, res
which assumes that A, B and
different method for the sam
(a_1, a_2) = **CA** and **b** = $(b_1, b_2$
2.5). Let us write

$$\mathrm{CP} = \mathrm{p} = (p_1, p_2) = \lambda \mathrm{a} + \mu \mathrm{b}$$

or, in the form of a matrix pro

$$[\,p_1 \quad p_2\,] = [\,\lambda \quad \mu\,] \begin{bmatrix} a_1 & a_2 \\ b_1 & b_2 \end{bmatrix} \qquad (3.7)$$

Since we saw in Exercise 3.4
× 2 matrix, we can now comp

3.5

$$[\,\lambda \quad \mu\,] = [\,p_1 \quad p_2\,] \begin{bmatrix} a_1 & a_2 \\ b_1 & b_2 \end{bmatrix}^{-1} \qquad (3.8)$$

The point P lies in triangle AB
only if $\lambda \geq 0$, $\mu \geq 0$and $\lambda + \mu$
which we can use as follows:

```
Point2D a, b, c, p;
TriaTest tt = new Tri
if (tt.area2() != 0 &
    // Point P within
```

As in Section 2.5, the metho
triangle ABC, preceded by a
return value is also equal to t
Equation (3.7).We must not
insideTriangle if this determi
inverse matrix of Equation (3

Answers

3.1 $$M = \begin{bmatrix} s_x & 0 & 0 \\ 0 & s_y & 0 \\ x_C(1-s_x) & y_C(1-s_y) & 1 \end{bmatrix}$$

3.2 Similar to Exercise 3.1.

For shearing a set of points
shearing equations at the en

$$x' - x_C = (x - x_C) + a(y - y_C)$$

$$y' - y_C = (y - y_C)$$

which reduces to $x' = x + a($

3.3

The sharing operation will tra
horizontal axis, so that we ca
Therefore, for some large va
C(x_C, y_C) and radius r by cor
circle:

$$x_i = x_C + r \cos i\theta$$

$$y_i = y_C + r \sin i\theta$$

where $\theta = 2\pi / n$ and $i = 0,$

connecting these points by st
we first subject each x_i to the

3.4

Just compute the product AA
example, the upper-left elem
product of the first row of A a
$a_{11}(a_{22}/D) + a_{12}(-a_{21}/D) = D$

If there are many points for w
within a single triangle (or on
the following class is more ef
since most of the work is don
called only once for that trian

```
class TriaTest
{  private Point2D C;
   private double a1,
```

3.5

```
TriaTest(Point2D A
{  this.C = C;
   a1 = A.x - C.x;
   b1 = B.x - C.x;
   det= a1 * b2 -
   if (det != 0)
   {  c1 = b2/det;
      d1 = -b1/det
   }
}

double area2(){ret

boolean insideTria
{  double p1 = P.x
      lambda, mu;
   return (lambda
        (mu = p1 *
        lambda + mu
```

```
        }
    }
```

Chapter 4: Some Classic Algorithms

Although programming is a very creative activity, often requiring entirely new (little) problems to be solved, we can sometimes benefit from well-known algorithms, published by others and usually providing more efficient or more elegant solutions than those we would have been able to invent ourselves. This is no different in computer graphics. This chapter is about some well-

known graphics algorithms for (a) computing the coordinates of pixels that comprise lines and circles, (b) clipping lines and polygons, and (c) drawing smooth curves. These are the most primitive operations in computer graphics and should be executed as fast as possible. Therefore, the algorithms in this chapter ought to be optimized to avoid time-consuming executions, such as multiplication, division, and calculations on floating point numbers.

4.1 BRESENHAM'S ALGORITHM FOR LINE DRAWING

We will now discuss how to draw lines by placing pixels on the screen. Although, in Java, we can simply use the method *drawLine* without bothering about pixels, it would be unsatisfactory if we had no idea how this method works. We will be using integer coordinates, but when discussing the slope of a line it would be very inconvenient if we had to use a *y*-axis pointing downward, as is the case with the Java

device coordinate system. Therefore, in accordance with mathematical usage, the positive *y*-axis will point upward in our discussion.

Unfortunately, Java lacks a method with the sole purpose of putting a pixel on the screen, so that we define the following, rather strange method to achieve this:

```
void putPixel(Graphics g,
{  g.drawLine(x, y, x, y);
}
```

We will now develop a *drawLine* method of the form

```
void drawLine(Graphics g,
{  ...
}
```

which only uses the above *putPixel* method for the actual graphics output.

Figure 4.1 shows a line segment with endpoints P(1, 1) and Q(12, 5), as well as the pixels that we have to compute to approximate this line.



Figure 4.1: Grid points approximating a line segment

To draw the line of Figure 4.1, we then write

```
drawLine(g, 1, 1, 12, 5);
```

Let us first solve the problem for situations such as Figure 4.1, in

which point Q lies to the right and not lower than point P. More precisely, we will be dealing with the special case

$$\begin{aligned} x_P &< x_Q \\ y_P &\leq y_Q \\ y_Q - y_P &\leq x_Q - x_P \end{aligned} \tag{4.1}$$

where the last condition expresses that the angle of inclination of line PQ is not greater than 45°. We then want to find exactly one integer *y* for each of the integers

$$x_P, x_P + 1, x_P + 2, \ldots, x_Q$$

Except for the first and the last (which are given as y_P and y_Q) the most straightforward way of computing these *y*-coordinates is by using the slope

$$m = \frac{y_Q - y_P}{x_Q - x_P} \qquad (4.2)$$

so that, for each of the given integer *x*-coordinates, we can find the desired integer *y*-coordinate by rounding the value

$$y_{exact} = y_P + m(x - x_P)$$

to the nearest integer. Since two such successive *x*-coordinates

differ by 1, the corresponding difference of two successive values of y_{exact} is equal to m. Figure 4.2 shows this interpretation of m, as well as that of the 'error'

$$d = y_{exact} - y \qquad (4.3)$$



Figure 4.2: Slope *m* **and error** *d*

Since *d* is the error we make by rounding y_{exact} to the nearest integer, we can require *d* to satisfy the following condition:

$$-0.5 \leq d < +0.5 \qquad (4.4)$$

The following first version of the desired *drawLine* method is based on this observation:

```
void drawLine1(Graphics g,
{  int x = xP, y = yP;
   float d = 0, m = (float
   for (;;)
   {  putPixel(g, x, y);
      if (x == xQ) break;
      x++;
      d + = m;
      if (d >= 0.5){y++; d
   }
}
```

This version is easy to understand if we pay attention to

Figure 4.2. Since the first call to *putPixel* applies to point P, we begin with the error $d = 0$. In each step of the loop, x is increased by 1. Assuming for the moment that y will not change, it follows from Equation (4.3) that the growth of d will be the same as that of y_{exact}, which explains why d is increased by m. We then check the validity of this assumption in the following if-statement. If d is no longer less than 0.5, this violates Equation (4.4), so that we apply a correction, consisting of increasing y and decreasing d by

1. The latter action makes Equation (4.4) valid again. By doing these two actions at the same time, Equation (4.3) also remains valid.

We use *drawLine*1 as a basis for writing a faster version, which no longer uses type *float*. This is possible because the slope variable *m* represents a rational number, that is, an integer numerator divided by an integer denominator, as Equation (4.2) shows. Since the other float variable, *d*, starts with the value zero and is altered only by

adding m and -1 to it, it is also a rational number. In view of both the denominator $x_Q - x_P$ of these rational numbers and the constant 0.5 used in the if-statement, we will apply the scaling factor

$$c = 2(x_Q - x_P)$$

to m, to d and to this constant 0.5, introducing the *int* variables M and D instead of the *float* variables m and d. We will also use Δx instead of the constant 0.5.

These new values M, D and x

are *c* times as large as *m*, *d* and 0.5, respectively:

$$M = cm = 2(y_Q - y_P)$$

$$D = cd$$

$$\Delta x = x_Q - x_P = c \times 0.5$$

In this way we obtain the following integer version, which is very similar to the previous one and equivalent to it but faster. In accordance with the Java naming conventions for variables, we write *m* and *d* again instead of *M* and *D*, and *dx* instead of Δ*x*:

```
void drawLine2(Graphics g,
```

```
{   int x = xP, y = yP, d =
       m = 2 * (yQ - yP);
    for (;;)
    {  putPixel(g, x, y);
       if (x == xQ) break;
       x++;
       d += m;
       if (d >= dx){y++; d
    }
}
```

Having dealt with this special case, with points P and Q satisfying Equation (4.1), we now turn to the general problem, without any restrictions with regard to the relative positions of P and Q. To solve this, we have several symmetric cases to

consider. As long as

$$|y_Q - y_P| \leq |x_Q - x_P|$$

we can again use *x* as the independent variable, that is, we can increase or decrease this variable by one in each step of the loop. In the opposite case, with lines that have an angle of inclination greater than 45°, we have to interchange the roles of *x* and *y* to prevent the selected pixels from lying too far apart. All this is realized in the general line-drawing method *drawLine* below. We can easily verify that this version plots exactly the same

points approximating line PQ as version *drawLine*2 if the coordinates of P and Q satisfy Equation (4.1).

```
void drawLine(Graphics g,
{  int x = xP, y = yP, d =
      c, m, xInc = 1, yInc
   if (dx < 0){xInc = -1;
   if (dy < 0){yInc = -1;
   if (dy <= dx)
   {  c = 2 * dx; m = 2 *
      if (xInc < 0) dx++;
      for (;;)
      {  putPixel(g, x, y);
         if (x == xQ) break
         x += xInc;
         d += m;
         if (d >= dx){y +=
```

```
        }
    }
    else
    {   c = 2 * dy; m = 2 *
        if (yInc < 0) dy++;
        for (;;)
        {   putPixel(g, x, y)
            if (y == yQ) brea
            y += yInc;
            d += m;
            if (d >= dy){x +=
    }
  }
}
```

Just before executing one of the above two for-statements, an if-statement is executed in the cases that *x* or *y* decreases

instead of increases, which is required to guarantee that drawing PQ always plots exactly the same points as drawing QP.

The idea of drawing sloping lines by means of only integer variables was first realized by *Bresenham*; his name is therefore associated with this algorithm.

The above *drawLine* method is very easy to use if we are dealing with the floating-point logical-coordinate system used so far. For example, in Section 4.5, there will be a program

ClipPoly.java, in which the following method occurs:

```
void drawLine(Graphics g,
{  g.drawLine(iX(xP), iY(y
}
```

Here our own method *drawLine* calls the Java method *drawLine* of the class *Graphics*. If, instead, we want to use our own method *drawLine* with four int arguments, listed above, we can replace the last three program lines with

```
void drawLine(Graphics g,
{  drawLine(g, iX(xP), iY(
}
```

provided that we also add the

method *putPixel*, listed at the beginning of this section. This may at first be confusing because there are now two *drawLine* methods of our own. As the comment after the above call to *drawLine* indicates, the Java compiler will select our Bresenham method *drawLine* because there is an argument *g*, followed by four arguments of type *int*. It is also interesting to note that the direction of the positive *y*-axis in our discussion causes no practical problem.

4.2 DOUBLING THE LINE-DRAWING SPEED

As one of the primitive graphics operations, line drawing should be performed as rapidly as possible. In fact, graphics hardware is typically benchmarked by the speed in which it generates lines. Bresenham's line algorithm is simple and efficient in generating lines. The algorithm works incrementally by computing the position of the next pixel to be drawn. Hence it iterates as many times as the number of pixels in

the line it generates. The double-step line-drawing algorithm by Rokne, Wyvill, and Wu (1990) aims at reducing the number of iterations by half, by computing the positions of the next *two* pixels.

Let us again start with the lines within the slope range of [0, 1] and consider the general case of any slopes later (as Exercise 4.2). For a line PQ, starting from P, we increment the *x*-coordinate by two pixels instead of one as in Bresenham's algorithm. All the possible positions of the two pixels in the above slope range

form four patterns, expressed in a 2×2 mesh illustrated in Figure 4.3. It has been mathematically proven that patterns 1 and 4 would never occur on the same line, implying that a line would possibly involve patterns 1, 2 and 3, or patterns 2, 3 and 4, depending the slope of the line. The lines within the slope range of [0, 1/2) involve patterns 1, 2 and 3, and lines within the slope range of (1/2, 1] involve patterns 2, 3 and 4. At the exact slope of 1/2, the line involves either pattern 2 or 3, not 1 or 4.



Figure 4.3: Four double-step patterns when $0 \leq$ slope ≤ 1

Figure 4.4 shows four sloping lines, all passing through the same point at a distance *d* above the point A. By approximating this common point of the four lines we make an error $d = y_{\text{exact}} - y$, which should not be greater than 0.5.



Figure 4.4: Choice of patterns based on initial error *d* and slope *m*

Since the slope of a line is equal to *m*,the exact *y*-coordinate of that line is equal to *d* + *m* at its point of intersection with BD, and *d* + 2*m* at its point of intersection with CF, as indicated in Figure

4.4 for the lowest of the four lines. With these two points of intersection lying closer to BC than to DE, it is clear that this lowest sloping line should be approximated by the points A, B, C, that is, by pattern 1 of Figure 4.3. Thus we have

If $d + 2m < 0.5$, we use pattern 1(ABC)

Otherwise, we use point E instead of C if E is the best approximation of the point where the sloping line intersects CF, that is, if $0.5 \leq d + 2m \leq 1.5$. However, we should now also

pay attention to the point where the sloping line intersects BD. Comparing $d + m$ with 0.5 determines whether B or D should be taken. More precisely,

if $0.5 \leq d + 2m < 1.5$(so that point E is to be used), we choose B or D as follows:

if $d + m < 0.5$, we use pattern 2(ABE)

if $d + m \geq 0.5$, we use pattern 3(ADE)

Finally, there is this remaining case:

if $d + 2m \geq 1.5$, we use pattern 4(ADF).

As in the previous section when discussing Bresenham's algorithm, we begin with a preliminary method that still uses floating-point variables to make it easier to understand, so it is not yet optimized for speed. This version also works for lines drawn from right to left, that is, when $x_Q < x_P$, as well as for lines with negative slope. However, the absolute value of the slope should not be greater than 1. So *doubleStep*1 applies only to

endpoints P and Q that satisfy the following conditions:

$$x_Q \neq x_P$$

$$|y_Q - y_P| \leq |x_Q - x_P|$$

It is wise to begin with the simplest case

$$x_P < x_Q$$

$$0 \leq y_Q - y_P \leq x_Q - x_P$$

when you read the following code for the first time:

```
void doubleStep1(Graphics
{   int dx, dy, x, y, yInc;
    if (xP >= xQ)
```

```
{  if (xP == xQ) // Not
      return;
   // xP > xQ, so swap
   int t;
   t = xP; xP = xQ; xQ
   t = yP; yP = yQ; yQ
}
// Now xP < xQ
if (yQ >= yP){yInc = 1;
else                {yInc =
dx = xQ - xP;       // dx
float d = 0,
      m = (float)dy/(fl
putPixel(g, xP, yP);
y = yP;
for (x=xP; x<xQ-1;)
{  if (d + 2 * m < 0.5)
   {  putPixel(g, ++x,
      putPixel(g, ++x,
```

```
      d += 2 * m; // Er
                  // un
   }
   else
   if (d + 2 * m < 1.5)
   {  if (d + m < 0.5)
      {  putPixel(g, ++
         putPixel(g, ++
         d += 2 * m - 1

      }
      else  // Pattern
      {  putPixel(g, ++
         putPixel(g, ++
         d += 2 * m - 1
      }
    }
    else // Pattern 4:
    {  putPixel(g, ++x,
```

```
                putPixel(g, ++x,
                d += 2 * m - 2;

            }
        }
        if (x < xQ)   // x = xQ
            putPixel(g, xQ, yQ)
}
```

Before the above for-loop is entered, there is a call to *putPixel* for $x = x_P$. The loop terminates as soon as the test

$$x < x_Q - 1$$

fails. This test is executed for the following values of x:

$$x_P,\ x_P + 2,\ x_P + 4, \text{and so on.}$$

If it succeeds, *putPixel* is called for the next two values of x, not for the value of x used in the test. There are two cases to consider. If $x_Q - x_P$ is even, the test still succeeds when $x = x_Q - 2$, and *putPixel* is executed for both $x = x_Q - 1$ and $x = x_Q$, after which we are done and the next test, with $x = x_Q$, fails. On the other hand, if $x_Q - x_P$ is odd, the test succeeds when $x = x_Q - 3$, and *putPixel* is called for both $x = x_Q - 2$and $x = x_Q - 1$, after which

the test fails with $x = x_Q - 1$. Then, after loop termination, the remaining call to *putPixel* is executed in the following if-statement:

```
if (x < xQ)
    putPixel(g, xQ, yQ);
```

We will now derive a fast, integer version from the above method *doubleStep*1. Let us use the notation

$$\Delta x = x_Q - x_P$$

$$\Delta y = y_Q - y_P$$

so that slope $m = \Delta y/\Delta x$. We

now want to introduce an *int* variable *v*, in such a way that the test

$$d + 2m < 0.5 \qquad (4.5)$$

reduces to

$$v < 0 \qquad (4.6)$$

To achieve this, we start writing (4.5) as $d + 2m - 0.5 < 0$ and, since this inequality contains the two fractions $m = \Delta y/\Delta x$ and 0.5, we multiply both sides of it by $2\Delta x$, obtaining

$$2d\Delta x + 4\Delta y - \Delta x < 0$$

Therefore, instead of the floating-point error variable $d = y_{exact} - y$, we will use the integer variable v, which relates to d as follows:

$$v = 2d\Delta x + 4\Delta y - \Delta x \qquad (4.7)$$

We can now replace the test (4.5) with the more efficient one (4.6). It follows from (4.7) that increasing d by $2m$ is equivalent to increasing v by $2\Delta x \times 2m$, which is equal to $4\Delta y$. This explains both the test $v < 0$ and adding $dy4$ to v in the for-loop below. These operations on the variable v are marked by

comments of the form //*Equivalent to* …, as are some others, which are left to the reader to verify.

```
void doubleStep2(Graphics
{  int dx, dy, x, y, yInc;
   if (xP >= xQ)
   {  if (xP == xQ) // Not
         return;
      int t;              // xP
      t = xP; xP = xQ; xQ
      t = yP; yP = yQ; yQ
   }
   // Now xP < xQ
   if (yQ >= yP){yInc = 1;
   else             {yInc = -1
   dx = xQ - xP;
   int dy4 = dy * 4, v = c
```

```
    dy4Minusdx2 = dy4 -
putPixel(g, xP, yP);
y = yP;
for (x=xP; x<xQ-1;)
{  if (v < 0)
   {  putPixel(g, ++x,
      putPixel(g, ++x,
      v += dy4;
   }
   else
      if (v < dx2)
      {  // Pattern 2 c
         if (v < dy2)
         {  putPixel(g,
            putPixel(g,
            v += dy4Min
         }
         else
         {  putPixel(g,
```

```
                    putPixel(g,
                    v += dy4Min
                }
            }
            else
            {   putPixel(g, ++
                putPixel(g, ++
                v += dy4Minusc
            }
        }
        if (x < xQ)
            putPixel(g, xQ,
}
```

Remember, the above method *doubleStep2* works only if $|y_Q - y_P| \leq |x_Q - x_P|$. In Exercise 4.2 the reader is asked to generalize

the method to work for any line.

Like Bresenham's line algorithm, the above double-step algorithm computes on integers only. For long lines, it outperforms Bresenham's algorithm by a factor of almost two. One can further optimize the algorithm to achieve another factor of two of speed-up by taking advantage of the symmetry around the midpoint of the given line. We leave this as an exercise for interested readers. The double-step algorithm can in fact be generalized to draw circles, which will be left for readers to

explore by consulting the papers by Wu and Rokne (1987) and Rokne, Wyvill, and Wu (1990) listed in the Bibliography. Adapting Bresenham's algorithm for circles will be the topic of the next section.

4.3 CIRCLES

In this section we will ignore the normal way of drawing a circle in Java by a call of the form

```
g.drawOval(xC - r, yC - r,
```

since it is our goal to construct such a circle, with center C(x_C, y_C) and radius r ourselves, where the coordinates of C and the radius are given as integers.

If speed is not a critical factor, we can apply the method *drawLine* to a great many neighboring points (x, y),

computed as

$$x = x_C + r\cos\varphi$$

$$y = y_C + r\sin\varphi$$

where

$$\varphi = i \times \frac{2\pi}{n} (i = 0, 1, 2, \ldots, n-1)$$

for some large value of *n*.

Instead of the above two ways of drawing a circle, we will develop a method of the form

```
void drawCircle(Graphics g
{   ...
}
```

which uses only the method *putPixel* of the previous section as a graphics ‘primitive’, and which is an implementation of *Bresenham's algorithm for circles*. The circle drawn in this way will be exactly same as that produced by the above call to *drawOval*. In both cases, x will range from $x_C - r$ to $x_C + r$, including these two values, so that $2r + 1$ different values of x will be used.

As in the previous sections, we begin with a simple case: we use the origin of the coordinate

system as the center of the circle, and, dividing the circle into eight arcs of equal length, we restrict ourselves to one of these, the arc PQ. The points P(0, r) and Q($r/\sqrt{2}$, $r/\sqrt{2}$) are shown in Figure 4.5.



Figure 4.5: Arc PQ in sector O of a circle with origin O and radius *r*

The equation of this circle is

$$x^2 + y^2 = r^2 \qquad (4.8)$$

Figure 4.6 shows the situation, including the grid of pixels, for the case $r = 8$. Beginning at the top at point P, with $x = 0$ and $y = r$, we will use a loop in which we increase x by 1 in each step; as in the previous section, we need some test to decide whether we can leave y unchanged. If not, we have to decrease y by 1.



Figure 4.6: Pixels that approximate the arc PQ

Since, just after increasing *x* by

1, we have to choose between (x, y) and $(x, y-1)$, we could simply compute both

$$x^2+y^2 \qquad \text{and} \qquad x^2+(y-1)^2$$

to see which lies closer to r^2. Note that this can be done by using only integer arithmetic, so that in principle our problem is solved. To make our algorithm faster, we will avoid computing the squares x^2 and y^2, by introducing the three new, non-negative integer variables u, v and E denoting the differences between two successive squares and the 'error':

$$u = (x+1)^2 - x^2 = 2x + 1 \tag{4.9}$$

$$v = y^2 - (y-1)^2 = 2y - 1 \tag{4.10}$$

$$E = x^2 + y^2 - r^2 \tag{4.11}$$

Initially, we have $x = 0$ and $y = r$, so that $u = 1$, $v = 2r - 1$ and $E = 0$. In each step in the loop, we increase x by 1, as previously discussed. Since, according to Equation (4.9), this will increase the value of x^2 by u, we also have to increase E by u to satisfy Equation (4.11). We can also see from Equation (4.9) that increasing x by 1 implies that we

have to increase u by 2. We now have to decide whether or not to decrease y by 1. If we do, Equation (4.10) indicates that the square y^2 decreases by v, so that according to Equation (4.11) E also has to decrease by v. Since we want the absolute value of the error E to be as small as possible, the test we are looking for can be written

$$|E - v| < |E| \qquad (4.12)$$

We will decrease y by 1 if and only if this test succeeds. It is interesting that we can write the condition (4.12) in a simpler form,

by first replacing it with the equivalent test

$$(E - v)^2 < E^2$$

which can be simplified to

$$v(v - 2E) < 0$$

Since *v* is positive, we can simplify this further to

$$v < 2E$$

On the basis of the above discussion, we can now write the following method to draw the arc PQ (in which we write *e* instead

of *E*):

```
void arc8(Graphics g, int
{   int x = 0, y = r, u = 1
    while (x <= y)
    {   putPixel(g, x, y);
        x++; e += u; u += 2;
        if (v < 2 * e){y--;
    }
}
```

Equations (4.10) and (4.11) show that in the case of decreasing *y* by 1, we have to decrease *E* by *v* and *v* by 2, as implemented in the if-statement. Note the symmetry between the three actions (related to *y*) in the if-statement and those (related to

x) in the preceding program line.

The method *arc*8 is the basis for our final method, *drawCircle*, listed below. Besides drawing a full circle, it is also more general than *arc*8 in that it allows an arbitrary point C to be specified as the center of the circle. The comments in this method indicate directions of the compass. For example, *NNE* stands for north-north-east, which we use to refer to the arc between the north and the north-east directions (see Figure 4.5). As usual, we think of the *y*-axis pointing upward, so

that *y* = *r* corresponds to north:

```
void drawCircle(Graphics g
{   int x = 0, y = r, u = 1
    while (x < y)
    {   putPixel(g, xC + x,
        putPixel(g, xC + y,
        putPixel(g, xC - x,
        putPixel(g, xC - y,
        x++; e += u; u += 2;
        if (v < 2 * e){y--;
        if (x > y) break;
        putPixel(g, xC + y,
        putPixel(g, xC + x,
        putPixel(g, xC - y,
        putPixel(g, xC - x,
    }
}
```

This version has been programmed in such a way that *putPixel* will not visit the same pixel more than once. This is important if we want to use the XOR paint mode, writing

```
g.setXORMode(Color.white);
```

before the call to *drawCircle*. Setting the paint mode in this way implies that black pixels are made white and vice versa, so that we can remove a circle in the same way as we draw it. It is then essential that a single call to *drawCircle* does not put the same pixel twice on the screen,

for then it would be erased the second time. To prevent pixels from being used twice, the eight calls to *putPixel* in the loop are divided into two groups of four: those in the first group draw the arcs 0, 2, 4 and 6 (see Figure 4.5), which include the starting points $(0, r)$, $(r,0)$, $(0, -r)$ and $(-r, 0)$. The arcs 1, 3, 5 and 7 of the second group do not include these starting points because these calls to *putPixel* take place after x has been increased. As for the endpoint of each arc, we take care (a) that x is not greater than y for any call to *putPixel*,

and (b) that the situation $x = y$ is covered by at most one of these two groups of *putPixel* calls. This situation will occur, for example, if $r = 6$; in this case the following eight points (relative to the center of the circle) are selected in this order, as far as the north-east quadrant of the circle (*NNE* and *ENE*) is concerned: (0, 6), (6, 1), (1, 6), (6, 2), (2, 6), (5, 3), (3, 5), (4, 4). In this situation the test after *while* terminates the loop. In contrast, the situation $x = y$ will not occur if $r = 8$, since in this case the eleven points (0, 8), (8, 1), (1, 8), (8, 2), (2, 8), (7, 3), (3,

7), (7, 4), (4, 7), (6, 5), (5, 6) are chosen, in that order. The loop now terminates because the break-statement in the middle of it is executed.

4.4 COHEN–SUTHERLAND LINE CLIPPING

In this section we will discuss how to draw line segments only as far as they lie within a given rectangle. For example, given a point P inside and a point Q outside a rectangle. It is then our task to draw only the line segment PI, where I is the point of intersection of PQ and the rectangle, as shown in Figure 4.7. The rectangle is given by the four numbers x_{min}, x_{max}, y_{min} and

y_{max}. These four values and the coordinates of P and Q are floating-point logical coordinates, as usual.



Figure 4.7: Line segment PQ to be clipped

Since PQ intersects the upper edge of the rectangle in I, we have

$$y_{\mathrm{I}} = y_{\max}$$

As the triangles PAI and PBQ are similar, we can write

$$\frac{x_{\mathrm{I}} - x_{\mathrm{P}}}{y_{\mathrm{I}} - y_{\mathrm{P}}} = \frac{x_{\mathrm{Q}} - x_{\mathrm{P}}}{y_{\mathrm{Q}} - y_{\mathrm{P}}}$$

After replacing y_{I} with $y_{\max}$ and multiplying both sides of this equation by $y_{\max} - y_{\mathrm{P}}$, we easily obtain

$$x_I = x_P + \frac{(y_{max} - y_P)(x_Q - x_P)}{(y_Q - y_P)}$$

so that we can draw the desired line segment PI.

This easy way of computing the coordinates of point I is based on several facts that apply to Figure 4.7, but that must not be relied on in a general algorithm. For example, if Q lies farther to the right, it may not be immediately clear whether the point of intersection lies on the upper edge $y = y_{max}$ or on the right edge $x = x_{max}$. In general, there are many more cases to

consider. The logical decisions needed to find out which actions to take make line clipping an interesting topic from an algorithmic point of view. The Cohen–Sutherland algorithm solves this problem in an elegant and efficient way. We will express this algorithm in Java.

The four lines $x = x_{min}$, $x = x_{max}$, $y = y_{min}$, $y = y_{max}$ divide the xy-plane into nine regions. With any point P(x, y) we associate a four-bit code

$$b_3 b_2 b_1 b_0$$

identifying that region, as Figure 4.8 shows.



Figure 4.8: Code values

For any point (x, y), the above four-bit code is defined as follows:

b_3 = 1 if and only if x <

x_{min}

$b_2 = 1$ if and only if $x >$ x_{max}

$b_1 = 1$ if and only if $y <$ y_{min}

$b_0 = 1$ if and only if $y >$ y_{max}

Based on this code, the Cohen–Sutherland algorithm replaces the endpoints P and Q of a line segment, if they lie outside the rectangle, with points of intersection of PQ and the

rectangle, that is, if there are such points of intersection. This is done in a few steps. For example, in Figure 4.8, the following steps are taken:

1. Since P lies to the left of the left rectangle edge, it is replaced with P′ (on $x = x_{min}$), so that only P′Q remains to be dealt with.

2. Since P′ lies below the lower rectangle edge, it is replaced with P′′ (on $y = y_{min}$), so that P′′Q remains to be dealt

with.

3. Since Q lies to the right of the right rectangle edge, it is replaced with Q′ (on $x = x_{max}$), so that P′′Q′ remains to be dealt with.

4. Line segment P′′Q′ is drawn.

Steps 1, 2 and 3 are done in a loop, which can terminate in two ways:

- If the four-bit codes of P (or P′ or P′′, which we

again refer to as P in the program) and of Q are equal to zero; the (new) line segment PQ is then drawn.

- If the two four-bit codes contain a 1-bit in the same position; this implies that P and Q are on the same side of a rectangle edge, so that nothing has to be drawn.

The method *clipLine* in the following program shows this in greater detail:

```
// ClipLine.java: Cohen-Su
```

```
import java.awt.*;
import java.awt.event.*;
import java.util.*;

public class ClipLine exte
{   public static void mai

        ClipLine()
        {  super("Click on t
           addWindowListener
              {public void w
           setSize (500, 300
           add("Center", new

           setCursor(Cursor.
           show();
        }
}
```

```
class CvClipLine extends C
{   float xmin, xmax, ymin
      rWidth = 10.0F, rHei
      int maxX, maxY, cent

      CvClipLine()
      {   addMouseListener
      {   public void mous
       {   float x = fx(ev
          if (np == 2) np
          if (np == 0){xmi
          else
          {   xmax = x; ym
             if (xmax < xm
             {    float t
             }
             if (ymax < ym
             {    float t
             }
```

```
                }
                np++;
                repaint();
            }
        });
}

void initgr()
{   Dimension d = getSize(
      maxX = d.width - 1;
      pixelSize = Math.max
      centerX = maxX/2; ce
}

int iX(float x){return Mat
int iY(float y){return Mat
float fx(int x){return (x
float fy(int y){return (ce
```

```
void drawLine(Graphics g,
      float xQ, float yQ)
{      g.drawLine(iX(xP),
}

int clipCode(float x, floa
{   return
        (x < xmin ? 8 : 0)
        (y < ymin ? 2 : 0)
}

void clipLine(Graphics g,
      float xP, float yP,
      float xmin, float ym
{   int cP = clipCode(xP,
      float dx, dy;
      while ((cP  |  cQ) !
      {   if ((cP & cQ) !=
        dx = xQ - xP; dy =
```

```
if (cP != 0)
{   if ((cP & 8) =
    else
    if ((cP & 4) ==
    else
    if ((cP & 2) ==
    else
    if ((cP & 1) ==
    cP = clipCode(x
}
else
if (cQ != 0)
{   if ((cQ & 8) =
    else
    if ((cQ & 4) ==
    else
    if ((cQ & 2) ==
    else
    if ((cQ & 1) ==
```

```
                cQ = clipCode(x
            }
        }
            drawLine(g, xP, yP
}
public void paint(Graphics
{   initgr();
        if (np == 1)
        {   // Draw horizont
            // first defined p
            drawLine(g, fx (0)
            drawLine(g, xmin,
        } else
         if (np == 2)
         {     // Draw rectan
            drawLine(g, xmin,
            drawLine(g, xmax,
            drawLine(g, xmax,
             drawLine(g, xmin,
```

```
// Draw 20 concen
// far as they li
float rMax = Math
   deltaR = rMax/

for (int j=1; j<=
{   float r = j *
   // Draw a pent
   float xA, yA,

   for (int i=1;
   {   float phi
      xA = xB; yA
      xB = (float)
      yB = (float)
      clipLine(g,
   }
}
```

```
            }
        }
}
```

The program draws 20 concentric (regular) pentagons, as far as these lie within a rectangle, which the user can define by clicking on any two opposite corners. When he or she clicks for the third time, the situation is the same as at the beginning: the screen is cleared and a new rectangle can be defined, in which again parts of 20 pentagons appear, and so on. As usual, if the user changes the window dimensions, the size of

the result is changed accordingly. Figure 4.9 shows the situation just after the pentagons are drawn.



Figure 4.9: Demonstration of program *ClipLine.java*

If we look at the while-loop in the method *clipLine*, it seems that this code is somewhat inefficient because of the divisions *dy*/*dx* and *dx*/*dy* inside that loop while *dx* and *dy* are not changed in it. However, we should bear in mind that *dx* or *dy* may be zero. The if-statements in the loop guarantee that no division by *dx* or *dy* will be performed if that variable is zero. Besides, this loop is different from most other program loops in that the inner part is usually executed only once or not at all, and rarely more than once.

4.5 SUTHERLAND–HODGMAN POLYGON CLIPPING

In contrast to line clipping, discussed in the previous section, we will now deal with polygon clipping, which is different in that it converts one polygon into another within a given rectangle, as Figures 4.10 and 4.11 illustrate.



Figure 4.10: Nine polygon vertices defined; final edge not yet drawn



Figure 4.11: Polygon completed and clipped

The program that we will discuss draws a fixed rectangle and enables the user to specify the vertices of a polygon by clicking, in the same way as discussed in Section 1.5. As long as the first

vertex, in Figure 4.10 on the left, is not selected for the second time, successive vertices are connected by polygon edges. As soon as the first vertex is selected again, the polygon is clipped, as Figure 4.11 shows. Some vertices of the original polygon do not belong to the clipped one. On the other hand, the latter polygon has some new vertices, which are all points of intersection of the edges of the original polygon and those of the rectangle. In general, the number of vertices of the clipped polygon can be greater than, equal to or

less than that of the original one. In Figure 4.11 there are five new polygon edges, which are part of the rectangle edges.

The program that produced Figure 4.11 is based on the Sutherland–Hodgman algorithm, which first clips all polygon edges against one rectangle edge, or rather, the infinite line through such an edge. This results in a new polygon, which is then clipped against the next rectangle edge, and so on. Figure 4.12 shows a rectangle and a polygon, ABCDEF. Starting at vertex A, we find that AB

intersects the line $x = x_{max}$ in point I, which will be a new vertex of the clipped polygon. The same applies to point J, the point of intersection of DE with the same vertical rectangle edge.



Figure 4.12: The Sutherland–Hodgman algorithm

Let us refer to the original polygon as the *input polygon* and the new one as the *output polygon*. We represent each polygon by a sequence of successive vertices. Let us start with the right rectangle edge and treat it as an infinite clipping line, which can be expressed as $x = x_{max}$, and see how to clip the polygon against this line. In general, when working on one clipping line, we ignore all other

rectangle edges. Initially, the output polygon is empty. When following all successive polygon edges such as AB, we focus on the endpoint, B, and decide as follows which points will belong to the output polygon:

If A and B lie on different sides of the clipping line, the point of intersection, I, is added to the output polygon. Regardless of this being the case, B is added to the output polygon if and only if it lies on the same side of the clipping line as the rectangle.

Starting with the directed edge AB in Figure 4.12, point I is the first to be added to the output polygon. Vertex B is not added because it is not on the same side of the clipping line as the rectangle, and the same applies to the endpoints of the following directed edges, BC and CD. When dealing with edge DE, we first add J and then E to the output polygon since they are both on the same side of the clipping line as the rectangle. The endpoints of the next two edges, EF and FA, lie on the same side of the clipping line as the

rectangle and are therefore added to the output polygon. In this way we obtain the vertices I, J, E, F and A, in that order. We then use this output polygon as the input polygon to clip against the top rectangle edge. Using the same method as described above on the right edge, we obtain the vertices I, J, K, L, F and A, which forms the output polygon IJKLFA. Although in this example IJKLFA is the desired clipped polygon, it will in general be necessary to use the output polygon as input for working with another rectangle edge. The

program below shows an implementation in Java:

```
// ClipPoly.java: Clip
// Uses: Point2D (Sect
import java.awt.*;
import java.awt.event.
import java.util.*;
public class ClipPoly
{  public static void

   ClipPoly()
   {  super("Define pc
      addWindowListene
         {public void
               {Syste
      setSize (500, 30
      add("Center", ne

      setCursor(Cursor
```

```
                                    (
            show();
            }
    }

    class CvClipPoly exten
    {   Poly poly = null;
        float rWidth = 10.
        int x0, y0, center
        boolean ready = tr

        CvClipPoly()
        {   addMouseListen
            {  public voic
                {  int x =
                   if (read
                   {   poly
                       x0 =
                       read
```

```
                    }
                    if (poly
                       Math.
                       ready
                    else
                       poly.
                    repaint(
                 }
              });
        }
    void initgr()
    {   Dimension d = getSi
        int maxX = d.width
        pixelSize = Math.ma
        centerX = maxX/2; c
    }

    int iX(float x){return
    int iY(float y){return
```

```
float fx(int x){return
float fy(int y){return

void drawLine(Graphics
                    float
{    g.drawLine(iX(xP),
}

void drawPoly(Graphics
{   int n = poly.size()
    if (n == 0) return;
    Point2D a = poly.ve
    for (int i=0; i<n;
    {    Point2D b = pol
         drawLine(g, a.x
         a = b;
    }
  }
```

```
public void paint(Grap
{   initgr();
    float xmin = -rWid
          ymin = -rHei
    // Draw clipping r
    g.setColor(Color.b
    drawLine(g, xmin,
    drawLine(g, xmax,
    drawLine(g, xmax,
    drawLine(g, xmin,
    g.setColor(Color.b
    if (poly == null)
    int n = poly.size(
    if (n == 0) return
    Point2D a = poly.v
    if (!ready)
    {  // Show tiny re
       g.drawRect(iX(a
       // Draw incompl
```

```
            for (int i=1; i
            {   Point2D b =
                drawLine(g,
                a = b;
            }
        }  else
        {  poly.clip(xmin,
           drawPoly(g, pol
        }
    }
}
class Poly
{  Vector v = new Vect
   void addVertex(Poin
   int size(){return v

   Point2D vertexAt(in
   {  return (Point2D)
   }
```

```
void clip(float xmi
{  // Sutherland-Hc
   Poly poly1 = new
   int n;
   Point2D a, b;
   boolean aIns, bI


   // Clip against
   if ((n = size())
   b = vertexAt(n-1
   for (int i=0; i<
   {   a = b; b = v
       aIns = a.x <
       if (aIns !=
          poly1.add
          (b.y - a.
       if (bIns) pc
```

```
}
v = poly1.v; pol

// Clip against
if ((n = size())
b = vertexAt(n-1
for (int i=0; i<
{   a = b; b = v
    aIns = a.x >
    if (aIns !=
       poly1.add
       (b.y - a.
    if (bIns) pc
}
v = poly1.v; pol

// Clip against
if ((n = size())
b = vertexAt(n-1
```

```
for (int i=0; i<
{    a = b; b = v
     aIns = a.y <
     if (aIns !=
        poly1.add
        (b.x - a.
     if (bIns) pc
}
v = poly1.v; pol

// Clip against
if ((n = size())
b = vertexAt(n-1
for (int i=0; i<
{    a = b; b = v
     aIns = a.y >
     bIns = b.y >
     if (aIns !=
        poly1.add
```

```
                    (b.x - a.
                if (bIns) pc
            }
            v = poly1.v; pol
        }
    }
```

The Sutherland–Hodgman algorithm can be adapted for clipping regions other than rectangles and for three-dimensional applications.

4.6 BÉZIER CURVES

There are many algorithms for constructing curves. A particularly elegant and practical one is based on specifying four points that completely determine a curve segment: two endpoints and two control points. Curves constructed in this way are referred to as (*cubic*) *Bézier curves*. In Figure 4.13, we have the endpoints P_0 and P_3, the control points P_1 and P_2, and the curve constructed on the basis of these four points.



Figure 4.13: Bézier curve based on four points

Writing a method to draw this curve is surprisingly easy, provided we use recursion. As Figure 4.14 shows, we compute

six midpoints, namely:

- A, the midpoint of P_0P_1
- B, the midpoint of P_2P_3
- C, the midpoint of P_1P_2
- A_1, the midpoint of AC
- B_1, the midpoint of BC
- C_1, the midpoint of A_1B_1



Figure 4.14: Constructing points for two smaller curve segments

After this, we can divide the original task of drawing the Bézier curve P_0P_3 (with control

points P_1 and P_2) into two simpler tasks:

- drawing the Bézier curve P_0C_1, with control points A and A_1
- drawing the Bézier curve C_1P_3, with control points B_1 and B

All this needs to be done only if the original points P_0 and P_3 are further apart than some small distance, say, ϵ. Otherwise, we simply draw the straight line P_0P_3. Since we are using pixels

on a raster, we can also base the test just mentioned on device coordinates: we will simply draw a straight line from P_0 to P_3 if and only if the corresponding pixels are neighbors or identical, writing

```
if (Math.abs(x0 - x3) <= 1
      g.drawLine(x0, y0, x
else ...
```

The recursive method *bezier* in the following program shows an implementation of this algorithm. The program expects the user to specify the four points P_0, P_1,P_2 and P_3, in that order, by clicking the mouse. After the fourth point,

P_3, has been specified, the curve is drawn. Any new mouse clicking is interpreted as the first point, P_0, of a new curve; the previous curve simply disappears and another curve can be constructed in the same way as the first one, and so on.

```
// Bezier.java: Bezier cur
// Uses: Point2D (Section

import java.awt.*;
import java.awt.event.*;
import java.util.*;

public class Bezier extend
{  public static void main
```

```
        Bezier()
        {   super("Define en
            addWindowListene
                {public void
            setSize (500, 30
            add("Center", ne

            setCursor(Cursor
            show();
        }
}

class CvBezier extends Can
{  Point2D[] p = new Point
   int np = 0, centerX, ce
   float rWidth = 10.0F, r

   CvBezier()
   {  addMouseListener(new
```

```
    {  public void mouse
       {  float x = fx(e
          if (np == 4) n
          p[np++] = new
          repaint();
       }
    });
}

void initgr()
{  Dimension d = getSiz
   int maxX = d.width -
   pixelSize = Math.max
   centerX = maxX/2; ce
}

int iX(float x){return
int iY(float y){return
float fx(int x){return
```

```
float fy(int y){return
Point2D middle(Point2D
{  return new Point2D((
}
void bezier(Graphics g,
   Point2D p2, Point2D
{  int x0 = iX(p0.x), y
       x3 = iX(p3.x), y
   if (Math.abs(x0 - x3
      g.drawLine(x0, y0
   else
   {  Point2D a = middl
         c = middle(p1
         b1 = middle(b
      bezier(g, p0, a,
      bezier(g, c1, b1,
   }
}
```

```
    public void paint(Graph
    {   initgr();
        int left = iX(-rWidt
            bottom = iY(-rHe
        g.drawRect(left, top

        for (int i=0; i<np;
        {   // Show tiny rec
            g.drawRect(iX(p[
            if (i > 0)
                // Draw line
                g.drawLine(i
                           i

        }
        if (np == 4) bezier(
    }
}
```

Since this program uses the

isotropic mapping mode with logical coordinate ranges 0–10.0 for *x* and 0–7.5 for *y*, we should only use a rectangle whose height is 75 % of its width. As in Sections 1.4 and 1.5, we place this rectangle at the center of the screen and make it as large as possible. It is shown in Figure 4.15; if the four points for the curve are chosen within this rectangle, they will be visible regardless of how the size of the window is changed by the user. The same applies to the curve, which is automatically scaled, in the same way as we did in

Sections 1.4 and 1.5.



Figure 4.15: A constructed Bézier curve

This way of constructing a Bézier curve may look like magic. To understand what is going on, we must be familiar with the notion of

parametric representation, which, in 2D, we can write as

$$\begin{cases} x = f(t) \\ y = g(t) \end{cases}$$

where t is a parameter, which we may think of as *time*. Variable t ranges from 0 to 1: as if we move from P_0 to P_3 with constant velocity, starting at $t = 0$ and finishing at $t = 1$. At time $t = 0.5$ we are half-way. With cubic Bézier curves, both $f(t)$and $g(t)$ are third degree polynomials in t.

Before we proceed, let us pay some attention to expressions

such as

$$\mathrm{A} = \tfrac{1}{2}(\mathrm{P}_0 + \mathrm{P}_1)$$

to compute the midpoint A of line segment P_0P_1. The points in such expressions actually denote vectors, which enables us to form their sum and to multiply them by a scalar. Without this shorthand notation, we would have to write

$$\mathbf{OA} = \tfrac{1}{2}(\mathbf{OP}_0 + \mathbf{OP}_1)$$

which would be rather awkward. Let us write each P_i as the column vector

$$\mathrm{P}_i = \begin{pmatrix} P[i].x \\ P[i].y \end{pmatrix}$$

(where we have taken the liberty of mixing mathematical and programming notations). In the same way, we combine the above functions $f(t)$and $g(t)$,

writing

$$B(t) = \begin{pmatrix} x \\ y \end{pmatrix} = \begin{pmatrix} f(t) \\ g(t) \end{pmatrix}$$

Then the cubic Bézier curve is defined as follows:

$$B(t) = (1-t)^3\mathrm{P}_0 + 3t(1-t)^2\mathrm{P}_1 + 3t^2(1-t)\mathrm{P}_2 + t^3\mathrm{P}_3 \qquad (4.13)$$

Substituting 0 and 1 for *t*, we find $B(0) = P_0$ and $B(1) = P_3$. Before discussing the relation between this definition and the recursive midpoint construction, let us see this definition in action. It enables us to replace the recursive method *bezier* with the following non-recursive one:

```
void bezier1(Graphics g, P
{  int n = 200;
   float dt = 1.0F/n, x =
   for (int i=1; i<=n; i++
   {   float t = i * dt, u
          tuTriple  = 3 *
          c0 = u * u * u,
          c1 = tuTriple *
          c2 = tuTriple *
```

```
            c3 = t * t * t;
        x0 = x; y0 = y;
        x = c0*p[0].x + c1*
        y = c0*p[0].y + c1*
        g.drawLine(iX(x0),
    }
}
```

This method produces the same curve as that produced by *bezier*,provided we also replace the call to *bezier* with this one:

```
bezier1(g, P);
```

We will discuss a more efficient non-recursive method, *bezier*2, equivalent to *bezier*1, at the end of this section.

Since $B(t)$ denotes the position at time t, the derivative $B'(t)$ of this function (which is also a column vector depending on t) can be regarded as the *velocity*. After some algebraic manipulation and differentiating, we find

$$B'(t) = -3(t-1)^2\mathrm{P}_0 + 3(3t-1)(t-1)\mathrm{P}_1 - 3t(3t-2)\mathrm{P}_2 + 3t^2\mathrm{P}_3 \quad (4.14)$$

which gives

$$B'(0) = 3(\mathrm{P}_1 - P_0)$$
$$B'(1) = 3(\mathrm{P}_3 - P_2)$$

These two results are velocity vectors at the starting point P_0 and the endpoint P_3. They show

that the direction we move at on these points is along the vectors P_0P_1 and P_2P_3, as Figure 4.16 illustrates.



Figure 4.16: Velocity at the points P_0 and P_3

We have been discussing two

entirely different ways to construct a curve between the points P_0 and P_3, and, without an experiment, it is not clear that these curves are identical. For the time being, we will distinguish between the two curves and refer to them as

- the *midpoint curve*, constructed by a recursive process of computing mid-points, and implemented in the method *bezier*;

- the *analytical curve*, given by Equation (4.13)

and implemented in the method *bezier*1.

Although both methods are based on the four points P_0,P_1,P_2 and P_3, the ways we compute hundreds of curve points (to connect them by tiny straight lines) are very different. It would be unsatisfactory if it remained a mystery why these curves are identical. Let us therefore briefly discuss a way to prove this fact.

Using the function $B(t)$ of Equation (4.13), we find

$$B(0.5) = \tfrac{1}{8}(P_0 + 3P_1 + 3P_2 + P_3)$$

Since point C_1 in Figure 4.14 was used to divide the whole midpoint curve into two smaller curves, we might suspect that C_1 and $B(0.5)$ are two different expressions for the same point. We verify this by expressing C_1 in terms of the four given points, using Figure 4.14. Because C_1 is the midpoint of A_1B_1 and both A_1 and B_1 are also midpoints, and so on, we find

$$\begin{aligned} A &= \tfrac{1}{2}(P_0 + P_1) \\ B &= \tfrac{1}{2}(P_2 + P_3) \\ C &= \tfrac{1}{2}(P_1 + P_2) \end{aligned} \tag{4.15}$$

$$\begin{aligned} A_1 &= \tfrac{1}{2}(A + C) = \tfrac{1}{4}(P_0 + 2P_1 + P_2) \\ B_1 &= \tfrac{1}{2}(C + B) = \tfrac{1}{4}(P_1 + 2P_2 + P_3) \end{aligned} \tag{4.16}$$

$$C_1 = \frac{1}{2}(A_1 + B_1) = \frac{1}{8}(P_0 + 3P_1 + 3P_2 + P_3) \qquad (4.17)$$

which is indeed the expression that we found for $B(0.5)$. This proves that point C_1, which obviously belongs to the midpoint curve, also lies on the analytical curve. Besides P_0 and P_3, there is now only one point, C_1, which we have proved lies on both curves, so it seems we are still far away from the proof that these curves are identical. However, we can now apply the same argument recursively, which would enable us to find as many points that lie on both curves as

we like. Restricting ourselves to the first half of each curve, we focus on the points P_0, A, A_1 and C_1, which we can again use to construct both midpoint and analytical curves. For the latter we use the following equation, which is similar to Equation (4.13):

$$b(u) = (1-u)^3 P_0 + 3u(1-u)^2 A + 3u^2(1-u)A_1 + u^3 C_1 \qquad (4.18)$$

It is then obvious that $b(0) = P_0$, $b(1) = C_1$ and $b(0.5)$ is identical with a midpoint (between P_0 and C_1) used in the recursive process, in the same way as

$B(0.5)$ is identical with the midpoint C_1. There is one remaining difficulty: is the analytical curve given by Equation (4.18) really the same as the first part of that given by Equation (4.13)? We will show that this is indeed the case. Using $u = 2t$ (since u = 1and t = 0.5 at point C_1) we have

$$b(u) = B(t)$$

To verify this, note that, according to Equation (4.18), we have

$$b(u) = b(2t) = (1-2t)^3 P_0 + 6t(1-2t)^2 A + 12t^2(1-2t)A_1 + 8t^3 C_1$$

Using Equations (4.15), (4.16) and (4.17), we can write the last expression as

$$(1-2t)^3 P_0 + 3t(1-2t)^2(P_0+P_1) + 3t^2(1-2t)(P_0+2P_1+P_2) + t^3(P_0+3P_1+3P_2+P_3)$$

Rearranging this formula, we find that it is equal to the expression for $B(t)$in Equation (4.13), which is what we had to prove.

4.6.1 Building Smooth Curves from Curve Segments

Suppose that we want to

combine two Bézier curve segments, one based on the four points P_0, P_1, P_2, P_3 and the other on Q_0,Q_1,Q_2 and Q_3, in such a way that the endpoint P_3 of the first segment coincides with the starting point Q_0 of the second. Then the combined curve will be smoothest if the final velocity $B'(1)$ (see Figure 4.16) of the first segment is equal to the initial velocity $B'(0)$ of the second. This will be the case if the point $P_3(= Q_0)$ lies exactly at the middle of the line segment P_2Q_1. The high degree of

smoothness obtained in this way is referred to as second-order continuity. It implies not only that the two segments have the same tangent at their common point $P_3 = Q_0$, but also that the curvature is continuous at this point. By contrast, we have first-order continuity if P_3 lies on the line segment P_2Q_1 but not at the middle of it. In this case, although the curve looks reasonably smooth because both segments have the same tangent in the common point $P_3 = Q_0$, there is a discontinuity in the curvature at this point.

4.6.2 Matrix Notation

It will be clear that we can write Equation (4.13) as follows:

$$B(t) = \begin{bmatrix} (1-t)^3 & 3t(1-t)^2 & 3t^2(1-t) & t^3 \end{bmatrix} \begin{bmatrix} P_0 \\ P_1 \\ P_2 \\ P_3 \end{bmatrix} \qquad (4.19)$$

Since the row vector in this matrix product is equal to

$$\begin{bmatrix} -t^3+3t^2-3t+1 & 3t^3-6t^2+3t & -3t^3+3t^2 & t^3 \end{bmatrix}$$

we can also write it as the product of a simpler row vector, $[t^3\ t^2\ t\ 1]$, and a 4 × 4 matrix, obtaining the following result for

the Bézier curve:

$$B(t) = \begin{bmatrix} t^3 & t^2 & t & 1 \end{bmatrix} \begin{bmatrix} -1 & 3 & -3 & 1 \\ 3 & -6 & 3 & 0 \\ -3 & 3 & 0 & 0 \\ 1 & 0 & 0 & 0 \end{bmatrix} \begin{bmatrix} P_0 \\ P_1 \\ P_2 \\ P_3 \end{bmatrix} \tag{4.20}$$

As we know, any matrix product *ABC* of three matrices is equal to both (*AB*)*C* and *A*(*BC*). If we do the first matrix multiplication first, as in (*AB*)*C*, Equation (4.20) reduces to Equation (4.19). On the other hand, if we do the second first, as in *A*(*BC*), we obtain the following result:

$$B(t) = (-P_0 + 3P_1 - 3P_2 + P_3)t^3 + 3(P_0 - 2P_1 + P_3)t^2 - 3(P_1 - P_0)t + P_0$$

This is interesting because it

provides us with a very efficient way of drawing a Bézier curve segment, as the following improved method shows:

```
void bezier2(Graphics g, P
{  int n = 200;
   float dt = 1.0F/n,
   cx3 = -p[0].x  + 3 * (p
   cy3 = -p[0].y  + 3 * (p
   cx2 = 3 *  (p[0].x - 2
   cy2 = 3 *  (p[0].y - 2
   cx1 = 3 * (p[1].x - p[0
   cy1 = 3 * (p[1].y - p[0
   cx0 = p[0].x,
   cy0 = p[0].y,
   x = p[0].x, y = p[0].y,
   for (int i=1; i<=n; i++
```

```
    {    float t = i * dt;
         x0 = x; y0 = y;
         x = ((cx3 * t + cx2
         y = ((cy3 * t + cy2
         g.drawLine(iX(x0),
    }
}
```

The above computation of *x* and *y* is an application of *Horner's rule*, according to which we can efficiently compute polynomials by using the right-hand rather than the left-hand side of the following equation:

$$a_3t^3 + a_2t^2 + a_1t + a_0 = ((a_3t + a_2)t + a_1)t + a_0$$

Although *bezier2* does not look

simpler than *bezier*1, it is much more efficient because of the reduced number of arithmetic operations in the for-loop. With a large number of steps, such as $n = 200$ in these versions of *bezier*1 and *bezier*2, it is the number of operations inside the loop that counts, not the preparatory actions that precede the loop.

4.6.3 3D Curves

Although the curves discussed here are two-dimensional, three-dimensional curves can be

generated in the same way. We simply add a z-component to $B(t)$ and to the control points, and compute this in the same way as the x-and y-components are computed. The possibility of generating curves that do not lie in a plane is related to the degree of the polynomials we have been discussing. If the four given points do not lie in the same plane, the generated cubic curve segment does not either. By contrast, quadratic curves are determined by only three points, which uniquely define a plane (unless they are collinear); the

quadratic curve through those three points lies in that plane. In other words, polynomial curves can be non-planar only if they are at least of degree 3.

4.7 B-SPLINE CURVE FITTING

Besides the techniques discussed in the previous section, there are other ways of generating curves $x = f(t)$, $y = g(t)$, where f and g are polynomials in t of degree 3. A popular one, known as *B-splines*, has the characteristic that the generated curve will normally not pass through the given points. We will refer to all these points as *control points*. A single segment of such a curve, based on four control points A, B, C and

D, looks rather disappointing in that it seems to be related only to B and C. This is shown in Figure 4.17, in which, from left to right, the points A, B, C and D are again marked with tiny squares.



Figure 4.17: Single B-spline segment, based on four points

However, a strong point in favor of B-splines is that this technique makes it easy to draw a very smooth curve consisting of many curve segments. To avoid confusion, note that each curve segment consists of many straight-line segments. For example, Figure 4.17 shows one curve segment which consists of 50 line segments. Since four control points are required for a single curve segment, we have

$$\text{number of control points} = \text{number of curve segments} + 3$$

in this case. This equation also applies if there are several curve

segments. At first sight, Figure 4.18 seems to violate this rule, since there are five curve segments, and it looks as if there are only six control points. However, two of these were used twice. This curve was constructed by clicking first on the lower-left vertex (= point 0), followed by clicking on the upper-left one (= point 1), then the upper-right one (= point 2), and so on, following the polygon clockwise. Altogether,the eight control points 0, 1, 2, 3, 4, 5, 0, 1 were selected, in that order. If after this, a key on the keyboard

is pressed, only the curve is redrawn, not the control points and the lines that connect them.



Figure 4.18: B-spline curve consisting of five curve segments

If we had clicked on yet another control point (point 2, at the top, right), we would have had a closed curve. In general, to produce a closed curve, there must be three overlapping vertices, that is, two overlapping polygon edges. As you can see in Figure 4.18, the curve is very smooth indeed: we have second-order continuity, as discussed in the previous section. Recall that this implies that even the curvature is continuous in the points where two adjacent curve segments meet. As the part of the curve near the lower-right

corner shows, we can make the distance between a curve and the given points very small by supplying several points close together.

The mathematics of B-splines can be expressed by the following matrix equation, similar to Equation (4.20):

$$B(t) = \frac{1}{6}\begin{bmatrix} t^3 & t^2 & t & 1 \end{bmatrix}\begin{bmatrix} -1 & 3 & -3 & 1 \\ 3 & -6 & 3 & 0 \\ -3 & 0 & 3 & 0 \\ 1 & 4 & 1 & 0 \end{bmatrix}\begin{bmatrix} P_0 \\ P_1 \\ P_2 \\ P_3 \end{bmatrix} \qquad (4.21)$$

If we have n control points P_0, P_1, …, P_{n-1} ($n \geq 4$) then, strictly speaking, Equation (4.21) applies

only to the first curve segment. For the second, we have to replace the points P_0, P_1, P_2 and P_3 in the column vector with P_1, P_2, P_3 and P_4, and so on. As with Bézier curves, the variable t ranges from 0 to 1 for each curve segment. Multiplying the above 4 × 4 matrix by the column vector that follows it, we obtain

$$B(t) = \frac{1}{6}\begin{bmatrix} t^3 & t^2 & t & 1 \end{bmatrix}\begin{bmatrix} -P_0 + 3P_1 - 3P_2 + P_3 \\ 3P_0 - 6P_1 + 3P_2 \\ -3P_0 + 3P_2 \\ P_0 + 4P_1 + P_2 \end{bmatrix}$$

or

$$B(t) = \tfrac{1}{6}(-P_0 + 3P_1 - 3P_2 + P_3)t^3 + \tfrac{1}{2}(P_0 - 2P_1 + P_2)t^2 + \tfrac{1}{2}(-P_0 + P_2)t + \tfrac{1}{6}(P_0 + 4P_1 + P_2)$$

The following program is based on this equation. The user can click any number of points, which are used as the points P_0, P_1, …, P_{n-1}. The first curve segment appears immediately after the fourth control point, P_3, has been defined, and each additional control point causes a new curve segment to appear. To show only the curve, the user can press any key, which also terminates the input process. After this, we can generate another curve by clicking again. The old curve then

disappears. Figures 4.17 and 4.18 have been produced by this program:

```
// Bspline.java: B-spline
// Uses: Point2D (Section

import java.awt.*;
import java.awt.event.*;
import java.util.*;

public class Bspline exten
{  public static void main

   Bspline()
   {  super("Define points
      addWindowListener(ne
         {public void winc
      setSize (500, 300);
```

```
        add("Center", new Cv

        setCursor(Cursor.get
        show();
    }
}

class CvBspline extends Ca
{   Vector V = new Vector(
    int np = 0, centerX, c
    float rWidth = 10.0F,
    boolean ready = false;

    CvBspline()
    {  addMouseListener(ne
       {  public void mous
          {  float x = fx(
             if (ready)
             {  V.removeAl
```

```
                np = 0;
                ready = fa
            }
            V.addElement(
            np++;
            repaint();
        }
    });

    addKeyListener(new
    {  public void keyT
        {  evt.getKeyCha
            if (np >= 4)
            repaint();
        }
    });
}

void initgr()
```

```
{  Dimension d = getSi
   int maxX = d.width
   pixelSize = Math.ma
   centerX = maxX/2; c
}
int iX(float x){return
int iY(float y){return
float fx(int x){return
float fy(int y){return

void bspline(Graphics
{  int m = 50, n = p.l
   float xA, yA, xB, y

   a0, a1, a2, a3, b0,
boolean first = true;
   for (int i=1; i<n-2
   {   xA=p[i-1].x; xB
       yA=p[i-1].y; yB
```

```
            a3=(-xA+3*(xB-x
            a2=(xA-2*xB+xC)
            a1=(xC-xA)/2;
            a0=(xA+4*xB+xC)
            for (int j=0; j
            {   x0 = x;
                y0 = y;
                float t = (f
                x = ((a3*t+a
                y = ((b3*t+b
                if (first) f
                else
                    g.drawLin
             }
    }
}

public void paint(Grap
{  initgr();
```

```
            int left = iX(-rWid
                bottom = iY(-rH
            g.drawRect(left, to
            Point2D[] p = new P
            V.copyInto(p);
            if (!ready)
            {   for (int i=0; i
                {   // Show tin
                    g.drawRect(
                    if (i > 0)
                        // Draw
                        g.drawL
                                i
                }
            }
            if (np >= 4) bsplin
        }
    }
```

To see why B-splines are so smooth, you should differentiate $B(t)$twiceand verify that, for any curve segment other than the final one, the values of $B(1)$, $B'(1)$ and $B''(1)$ at the endpoints of these segments are equal to the values $B(0)$, $B'(0)$ and $B''(0)$ at the start point of the next curve segment. For example, for the continuity of the curve itself we find

$$\begin{aligned} B(1) &= \tfrac{1}{6}(-P_0 + 3P_1 - 3P_2 + P_3) + \tfrac{1}{2}(P_0 - 2P_1 + P_2) + \tfrac{1}{2}(-P_0 + P_2) \\ &\quad + \tfrac{1}{6}(P_0 + 4P_1 + P_2) \\ &= \tfrac{1}{6}(P_1 + 4P_2 + P_3) \end{aligned}$$

for the first curve segment,

based on P_0, P_1, P_2 and P_3, while we can immediately see that we obtain exactly this value if we compute $B(0)$ for the second curve segment, based on P_1, P_2, P_3 and P_4.

EXERCISES

Replace the *drawLine* meth
algorithm and listed near the
faster version that benefits
halves of the line. For exam
satisfying Equation (4.1), ar
halfway between x_P and x_Q

4.1 x_P to x_{Mid} and also use a va
runs backward from x_Q to x
is increased by 1 and x_2 is
be either one point or two p
depending on the number of
even. Be sure that no pixel
pixel is put twice on the scre
XOR mode so that writing t
same effect as omitting a pi

4.2 Generalize the method *doub*
it work for any lines.

Since normal pixels are very
clearly which of them are se
Use a grid to simulate a scr

Demonstrate both the meth
argument) of Section 4.1 ar
Section 4.3. Only the gridpc
the centers of ‘superpixels’.
small circle with such a cent
neighboring gridpoints as its
methods *drawLine* and *draw*
but use *dGrid*,just mentione
different from the one show
Figure 4.19 shows a grid (w
a circle drawn in this way. A
has the endpoints P(1, 1) ar
positive *y*-axis points downv
corner of the drawing rectar
and is approximated by the
for one eighth of this circle.
by the following calls to the

4.3

of Sections 4.1 and 4.3 (but

```
drawLine(g, 1, 1, 12
drawCircle(g, 23, 10
```



Figure 4.19: Bresenham
circle (see also Figures 4

In the *Bezier.java* program v
segment, using the points P
program to enable the user
consisting of more than one
has been drawn, the second
Q_0,Q_1,Q_2 and Q_3 (similar to

- Q_0 is identical with l
  that we want to star

- Q_1 is not specified by
  constructed by reflec
  P_3 (= Q_0) will be the
  make the curve very

- Q_2 and Q_3 are defir
  clicking on these po

It should also be possible to
starting at Q_3, and so on. W
arbitrary number of segmen
a point other than the final c
the starting point (similar to
drawn in addition to the prev
user clicks on this new point
the same point will be the si
soon as a curve is complete
displaying any straight lines
without any little squares ma

Extend the program *Bspline*
with visible gridpoints lying,

and vertically. Any control p
mouse should be pulled to t
easier for the user to specif
same horizontal or vertical l
program will also be differe
be able to store several B-s
The following characters ar

+ Increase the distance

4.5 – Decrease the distar
one.

n After this command, s
the previous ones.

d Delete the last curve.

g Change the visibilit
(visible/invisible).

c Show only the cur
points or lines con

Implement a restricted vers
algorithm as a demonstratic
to visualize how this algorith
execution on an exaggerate
Draw the grid on the left ha
main body of method *drawL*

4.6 right half with text font size
space, add both a button la
displaying the values of the
and *y*. When the user clicks
Q, satisfying Equations (4.1
and the initial values of the
displayed. Just after the de
putPixel is highlighted (by c
indicating that this program
whenever the user clicks on
is executed, the next progra
highlighted, and the values
time *putPixel* is executed, a
appropriate grid intersectio

Answers

4.1 Adapt the Java program for endpoints towards the midd beforehand or check on-the middle. There may be one o an odd or even number of p after exiting the loop. Check consisting of one or two pix any two endpoints P and Q.

4.2 You should add a second fo example, the calls to *putPix* their second. If $|y_Q - y_P| \leq |$ second.

The following program prod to specify the two endpoints circle.

```
// Bresenham.java: B
//                 d
import java.awt.*;
import java.awt.even
import java.util.*;

public class Bresenh
{  public static voi

   Bresenham()
   {  super("Bresenh
      addWindowListe
       {public void
                {Syst
       setSize (340,
       add("Center",
       show();
   }
}
```

```
class CvBresenham ex
{  float rWidth = 10
   int centerX, cent

   void initgr()
   {  Dimension d;
      d = getSize();
      maxX = d.width
      maxY = d.heigh
      pixelSize = Ma
      centerX = maxX
   }
      int iX(float x
      int iY(float y

      void putPixel(
      {  int x1 = x
         g.drawOval(
      }
```

4.3

```
void drawLine(
{  int x = xP,
       c, M, xI
   if (HX < 0)
   if (HY < 0)
   if (HY <= H
   {  c = 2 *
      for (;;)
      {  putPi
         if (x
         x +=
         D +=
         if (D
      }
   }
   else
   {  c = 2 *
      for (;;)
```

```
                {  putPi
                   if (y
                   y +=
                   D +=
                   if (D
                }
             }
    }

    void drawCircle(Grap
    {  int x = 0, y = r,
       while (x < y)
       {  putPixel(g, xC
          putPixel(g, xC
          putPixel(g, xC
          putPixel(g, xC
          x++; E += u; u
          if (v < 2 * E)
          if (x > y) bre
```

```
      putPixel(g, xC
      putPixel(g, xC
      putPixel(g, xC
      putPixel(g, xC
    }
  }

  void showGrid(Gra
  {  for (int x=dGr
       for (int y=
         g.drawLi
  }

  public void paint
  {  initgr();
     showGrid(g);
     drawLine(g, 1,
     drawCircle(g,
  }
```

```
}
```

Since an unknown number c
concept of *Vector*, as we ha
objects representing the ver
class *CurveSegment* andtou
shows:

```
class CurveSegment
{   Point2D[] P;
    CurveSegment(Poin
    ...
}
```

Writing

4.4 `Vector curves = new`

and using the array *P*, decla

```
Point2D[] P = new Po
```

containing the most recent f
we can add a new curve se

```
curves.addElement(ne
```

The object *curves* can store
elements.

In program *Bspline.java* of
terminate the process of ex

```
char ch = evt.getKey
```

in the method *keyTypec*

between different chara
commands.

4.5 Use a *Vector* element for ea
statement

```
V.copyInto(P);
```

in the *paint* method of progr
P. Using a different *Vector* c
The deletion of the last curv

```
curves.setSize(curve
```

Represent the grid on the s
ten equidistant vertical lines
lines, transform the device c
9, and use these gridpoint c

been defined. On the right c

$$algorithm[0], algorithm[1], \ldots, algorithm[7]$$

below each other, where th

```
String[] algorithm =
    "int x=xP,y=yP,d=
    "    m=2*(yQ-yP);
    "for (;;)",
    "{ putPixel(g, x,
    " if (x == xQ) br
    " x++; d += m;",
    " if (d > dx){y++
    "}"};
```

As soon as the user has
should be highlighted, i
executed. You can realiz

the above eight progran
to, say, −1 if all prograr
with $j \neq i$ are displayed
value of *i* in a method *s*
4.6 the following form in th

```
addMouseListener(new
{  public void mouse
   {  // When the mo
      // it is on th
      // action, if
      int xClick = 0
      // Get the coo
      xClick = evt.g
      yClick = evt.g
      // Check to se
      if (xClick, yC
```

```
                stepPressed
            else
            if (xClick, yC
            {   ...
            }
            repaint();
        }
});
```

In the switch statement
in the program line (sto
highlighted and update
will use this variable *i* to
others in black.

Chapter 5: Perspective

We now turn to the exciting subject of 3D graphics. As soon as we know how to compute the perspective image of a single point, we can easily produce more interesting images. To obtain the perspective image of a straight line, we simply connect the images of its endpoints, using the fact that the image of a straight line is also a straight line. In this chapter, the computation of

the perspective image of a point is done in two steps: a viewing transformation followed by a perspective transformation.

5.1 INTRODUCTION

In Figure 5.1 a two-dimensional representation of a cube is shown along with some auxiliary lines. Although AB is a horizontal edge, it is not a horizontal line in the picture. Lines that in 3D space are horizontal and parallel meet in the picture in a so-called *vanishing point*. All these vanishing points lie on the same line, which is called the *horizon*. The horizon and vanishing points refer to the 2D image space, not to the 3D object space. For many centuries these concepts have

been used by artists to draw realistic images of three-dimensional objects. This way of representing three-dimensional objects is usually referred to as *perspective*.



Figure 5.1: Vanishing points on the horizon

The invention of photography offered a new (and easier) way

of producing images in perspective. There is a strong analogy between a camera used in photography and the human eye. Our eye is a very sophisticated instrument of which a camera is an imitation. In the following discussion the word *eye* may be replaced with *camera* if we want to emphasize that a two-dimensional hard copy is desired.

It is obvious that the image will depend upon the position of the eye. An important aspect is the distance between the eye and the object, since the effect of

perspective will be inversely proportional to this distance. If the eye is close to the object, the effect of perspective is strong, as shown in Figure 5.2(a). Here we can very clearly see that in the image the extensions of parallel line segments meet.



Figure 5.2: (a) Eye nearby;

(b) eye far away

Besides the classical and the photographic method, there is a way of producing perspective images which is based on analytical geometry. Let us write X and Y for 2D and x, y and z for 3D coordinates.

If we want to produce a drawing in perspective, we are given a great many points P(x, y, z) of the object and we want their images P′(X, Y) in the picture.

Thus all we need is a mapping

from the *world coordinates* (x, y, z) of a point P to the *screen coordinates* (X, Y) of its central projection P′. We imagine a screen between the object and the eye E. For every point P of the object the line PE intersects the screen at point P′. It is convenient to perform this mapping in two stages. The first is called a *viewing transformation*; point P is left at its place, but we change from world coordinates to so-called *eye coordinates*. The second stage is called a *perspective transformation*. This is a proper

transformation from P to P′, combined with a transition from the three-dimensional eye coordinates to the two-dimensional screen coordinates:



5.2 THE VIEWING TRANSFORMATION

To perform the viewing transformation we must be given not only an object but also a viewpoint E. Let us require that the world-coordinate system be right-handed. It is convenient if its origin O lies more or less centrally in the object; we then view the object from E to O. We will assume this to be the case; in practice this might require a coordinate transformation consisting of decreasing the original world coordinates by the

coordinates of the central object point. We will include this very simple coordinate transformation in our program, without writing it down in mathematical notation.

Let the viewpoint E be given by its spherical coordinates ρ(= *rho*), θ(= *theta*), φφ(= *phi*), relative to the world-coordinate system. Thus its world-coordinates are

$$\begin{aligned} x_E &= \rho \sin\varphi \cos\theta \\ y_E &= \rho \sin\varphi \sin\theta \\ z_E &= \rho \cos\varphi \end{aligned} \qquad (5.1)$$

as shown in Figure 5.3.



Figure 5.3: Spherical coordinates of viewpoint E

The direction of vector **EO**(=

$-\mathbf{OE}$) is said to be the viewing direction. From our eye at E we can only see points within some cone whose axis is EO and whose apex is E. If the Cartesian coordinates x_E, y_E, z_E of viewpoint E were given, we could derive the spherical coordinates from them as follows:

```
rho = Math.sqrt(xE * xE +
theta = Math.atan2(yE, xE)
phi = Math.acos(zE/rho);
```

Our final objective will be to compute the screen coordinates *X*, *Y*,where we have an *X*-axis and a *Y*-axis, lying in a screen

between E and O and perpendicular to the viewing direction **EO**. This is why the eye-coordinate system will have its x_e-axis and y_e-axis perpendicular to **EO**, leaving the z_e-axis in the direction of OE. The origin of the eye-coordinate system is viewpoint E, as shown in Figure 5.4. Viewing from E to O, we find the positive x_e-axis pointing to the right and the positive y_e-axis upwards. These directions will enable us later to establish screen axes in the same directions. We could have used a positive z_e-axis pointing

from E to O; on the one hand this is attractive because it makes the z_e-coordinates of all object points positive, but, on the other hand, it would have required a left-handed eye-coordinate system. In this book we will use a right-handed eye-coordinate system (as shown in Figure 5.4) to avoid confusion with regard to the use of the cross product, taking the minus sign of z_e-coordinates into the bargain.



Figure 5.4: Eye-coordinate system

The viewing transformation can be written as a matrix multiplication, for which we need the 4 × 4 *viewing matrix* V:

$$[x_e \quad y_e \quad z_e \quad 1] = [x_w \quad y_w \quad z_w \quad 1]V \qquad (5.2)$$

To find *V*, we imagine this transformation to be composed of three elementary ones, for which the matrices can easily be written down. Matrix *V* will be the product of these three matrices. Each of the three transformations is in fact a change of coordinates and has therefore a matrix which is the inverse of the matrix for an equivalent point transformation.

1. **Moving the origin from O to E**

   We perform a translation of the coordinate system such

that viewpoint E becomes the new origin. The matrix for this change of coordinates is

$$T = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ -x_E & -y_E & -z_E & 1 \end{bmatrix} \tag{5.3}$$

(Do not confuse x_E, y_E, z_E, the world coordinates of viewpoint E, with x_e, y_e, z_e, the eye coordinates of any point.) The new

coordinate system is shown in Figure 5.5.



Figure 5.5: Situation before rotation about the *z*-axis

2. **Rotating the coordinate system about the z-axis**

Starting with Figure 5.5 we rotate the coordinate system about the *z*-axis through the angle θ + 90°, so the new *x*-axis points to the right and is perpendicular to the vertical plane through E and O. The matrix for this change of coordinates is the same as that for a rotation of

points through the angle $-(\theta + 90°)$, which equals $-\theta - 90°$. We obtain the 4×4 matrix R_z for this rotation by including a 2×2 matrix, as discussed in Section 3.2, and adding the third and fourth columns and rows of a 4×4 unit matrix:

$$R_z = \begin{bmatrix} \cos(-\theta - 90°) & \sin(-\theta - 90°) & 0 & 0 \\ -\sin(-\theta - 90°) & \cos(-\theta - 90°) & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix}$$

$$= \begin{bmatrix} -\sin\theta & -\cos\theta & 0 & 0 \\ \cos\theta & -\sin\theta & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix} \tag{5.4}$$

If you find the simplifications

$$\cos(-\theta - 90^\circ) = -\sin\theta \quad \text{and} \quad \sin(-\theta - 90^\circ) = -\cos\theta$$

difficult, it will be helpful to plot the two angles of this formula in a unit circle for some value of θ, as Figure 5.6 illustrates.



Figure 5.6: Relating the sine and cosine of $-\theta - 90°$ to those of θ

After applying the above matrix R_z, the new position of the *x*-,

y- and *z*-axes is as shown in Figure 5.7.



Figure 5.7: Situation before rotation about

x -
axis

3. Rotating the coordinate system about the x-axis

Since the *z*-axis is to have the direction **OE**, we now rotate the coordinate system about the *x*-axis through the angle φ. The dashed line near the positive *z*-axis in Figure 5.7 indicates the new *y*-axis after this rotation. A rotation about the *x*-axis is said to be *positive* if the *y*-axis goes towards the *z*-axis (through an

angle of 90°). It corresponds to the turning of a normal, right-handed screw which moves forward in the direction of the positive *x*-axis. However, since we are performing a coordinate transformation instead of rotating points, we have to use $-\varphi$ instead of φ as the angle of rotation, so that we obtain the following rotation matrix:

$$R_x = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & \cos(-\varphi) & \sin(-\varphi) & 0 \\ 0 & -\sin(-\varphi) & \cos(-\varphi) & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix} = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & \cos\varphi & -\sin\varphi & 0 \\ 0 & \sin\varphi & \cos\varphi & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix} \tag{5.5}$$

After this final rotation, we have obtained the eye-coordinate

system with x_e-, y_e-and z_e-axes, which we have already seen in Figure 5.4. Multiplying the above matrices T, R_z and R_x, we obtain the desired viewing matrix:

$$V = TR_zR_x = \begin{bmatrix} -\sin\theta & -\cos\varphi\cos\theta & \sin\varphi\cos\theta & 0 \\ \cos\theta & -\cos\varphi\sin\theta & \sin\varphi\sin\theta & 0 \\ 0 & \sin\varphi & \cos\varphi & 0 \\ 0 & 0 & -\rho & 1 \end{bmatrix} \quad (5.6)$$

Recall that we use this matrix in Equation (5.2), to compute the eye coordinates x_e, y_e and z_e from the given world coordinates x_w, y_w and z_w.

The viewing transformation described above is to be

followed by the perspective transformation to be discussed in the next section. However, we could also use the eye coordinates x_e and y_e, simply ignoring z_e. In that case we have a so-called *orthographic projection*. Every point P of the object is then projected into a point P′ by drawing a line from P, perpendicular to the plane through the *x*-axis and the *y*-axis. It can also be regarded as the perspective image we obtain if the viewpoint is infinitely far away. An example of such a picture is the cube in Figure

5.2(b). Parallel lines remain parallel in pictures obtained by orthographic projection. Such pictures are very often used in practice because with conventional methods they are easier to draw than real perspective images.

On the other hand, bringing some perspective into the picture will make it much more realistic. Our viewing transformation will therefore be followed by the perspective transformation, which will involve surprisingly little computation.

5.3 THE PERSPECTIVE TRANSFORMATION

You might have the impression that we are only half-way, and that in this section we will need as much mathematics as in Section 5.2. However, most of the work has already been done. Since we will not use world coordinates in this section, there will be no confusion if we denote eye coordinates simply by (x, y, z) instead of (x_e, y_e, z_e).

In Figure 5.8 we have chosen a point Q, whose eye coordinates

are (0, 0, $-d$) for some positive value d.



Figure 5.8: Screen and eye coordinates

Our screen will be the plane z =

$-d$, that is, the plane through Q and perpendicular to the z-axis. Then the screen-coordinate system has Q as its origin, and its X-and Y-axes are parallel to the x-and y-axes. For every object point P, the image point P′ is the intersection of line PE and the screen. To keep Figure 5.8 simple, we consider a point P whose y-coordinate is zero. However, the following equations to compute its screen coordinate X are also valid for other y-coordinates. In Figure 5.8 the triangles EPR and EP′Q are similar. Hence

$$\frac{P'Q}{EQ} = \frac{PR}{ER}$$

so we have

$$\frac{X}{d} = \frac{x}{-z}$$

(Recall that z-coordinates of object points are negative, so that $-z$ is a positive value.) In other words,

$$X = -d \cdot \frac{x}{z} \tag{5.7}$$

In the same way we can derive

$$Y = -d \cdot \frac{y}{z} \tag{5.8}$$

At the beginning of Section 5.2 we chose the origin O of the world-coordinate system to be a central point of the object. The origin Q of the screen-coordinate system will be central in the image because the *z*-axis of the eye-coordinate system is a line through E and O, which intersects the screen at Q. We must bear in mind that Equations (5.7) and (5.8) can be used in this form only if the origin Q of the screen coordinate system (with *X*-and *Y*-axes) lies in the center of the screen. If this origin lies instead in the lower-left

corner of the screen and the screen has width w and height h, we have to add $w/2$ and $h/2$ to the Equations (5.7) and (5.8), respectively.

We still have to specify the distance d between viewpoint E and the screen. Roughly speaking, we have

$$\frac{d}{\rho} = \frac{\text{image size}}{\text{object size}}$$

which follows from the similarity of the triangles $EP'_1P'_2$ and EP_1P_2 in Figure 5.9. Thus we have

$$d = \rho \cdot \frac{\text{image size}}{\text{object size}} \qquad (5.9)$$



Figure 5.9: Image size and object size

This equation should be applied to both the horizontal and the vertical directions. It should be interpreted only as a means to obtain an indication about an

appropriate value for *d*, for the three-dimensional object may have a complicated shape, and it may not be clear how its size is to be measured. We then use a rough estimation of the object size, such as the maximum of its length, width and height. The image size in Equation (5.9) should be taken somewhat smaller than the screen.

5.4 A CUBE IN PERSPECTIVE

We will now discuss a complete Java program, which draws a perspective representation of a cube, as shown in Figure 5.10. Such representations, with all edges visible, are called *wire-frame* models.



Figure 5.10: Output of program *CubePers.java*

To specify this cube in a program, we assign numbers to its vertices, as shown in Figure

5.11. The center of the cube coincides with the origin O and its edges have length 2, which implies that the x-, y- and z-coordinates of its eight vertices are equal to +1or -1.



Figure 5.11: Vertex numbers and coordinate axes

The following program produces the wire-frame model of Figure 5.10. We store the world, eye and screen coordinates for each of the eight vertices of the cube in the class *Obj*:

```
// CubePers.java: A cube i
// Uses: Point2D (Section
import java.awt.*;
import java.awt.event.*;

public class CubePers exte
{   public static void mai

        CubePers()
        {   super("A cube in
        addWindowListener(ne
            {public void winc
```

```
        setLayout(new Border
        add("Center", new Cv
        Dimension dim = getT
        setSize(dim.width/2,
        setLocation(dim.widt
        show();
    }
}

class CvCubePers extends C
{   int centerX, centerY;
    Obj obj = new Obj();

    int iX(float x){return
    int iY(float y){return

    void line(Graphics g,
    {  Point2D p = obj.vSc
       g.drawLine(iX(p.x),
```

```
    }

    public void paint(Grap
    {   Dimension dim = get
        int maxX = dim.widt
            minMaxXY = Math
        centerX = maxX/2; c
        obj.d = obj.rho * m
        obj.eyeAndScreen();
        // Horizontal edges
        line(g, 0, 1); line
        // Horizontal edges
        line(g, 4, 5); line
        // Vertical edges:
        line(g, 0, 4); line
    }
}

class Obj // Contains 3D c
```

```
{   float rho, theta=0.3F,
          v11, v12, v13, v2
                        // Ele
    Point3D[] w;        // Wor
    Point2D[] vScr;      // Sc
    Obj()
    {   w = new Point3D[8];
        vScr = new Point2D[8
        // Bottom surface:
        w[0] = new Point3D(
        w[1] = new Point3D(
        w[2] = new Point3D(-
        w[3] = new Point3D(-
        // Top surface:
        w[4] = new Point3D(
        w[5] = new Point3D(
        w[6] = new Point3D(-
        w[7] = new Point3D(-
        objSize = (float)Mat
```

```
        // = sqrt(2  * 2
        // = distance bet
    rho = 5 *  objSize;
}

void initPersp()
{  float costh = (float
          sinth = (float
          cosph = (float
          sinph = (float
    v11 = -sinth; v12 =
    v21 = costh;  v22 =
                  v32 =

    }

    void eyeAndScreen()
    {  initPersp();
       for (int i=0; i<8
```

```
            {   Point3D p = w[i];
                float x = v11 * p
                      y = v12 * p
                      z = v13 * p
                vScr[i] = new Poi
            }
        }
    }
```

As discussed in Section 5.3 (see point Q in Figure 5.8), the perspective transformation is simplest if we use a coordinate system with the origin in the center of the screen and with a *y*-axis pointing upward. To convert such (floating-point) coordinates to device

coordinates of type *int*, we again use the methods *iX* and *iY*. As usual, these are based on the values of the fields *centerX*, *centerY* and *maxY*, which are computed in the *paint* method before this method uses *iX* and *iY*.

The *paint* method also computes the screen distance *d* (stored in *obj*), using Equation (5.9). After calling the *Obj* method *eyeAndScreen* to compute eye and screen coordinates, we use our method *line* to draw all 12 cube edges.

In the class *Obj*, the arrays *w* and *vScr* contain the world and the screen coordinates, respectively, of the cube vertices. Recall that we use the matrix multiplication of Equation (5.2) to compute the eye coordinates from the given world coordinates stored in *w*. We then use these eye coordinates to compute the screen coordinates for the array *vScr*. Figure 5.11 is helpful in specifying the coordinate values in the array *w* and the vertex numbers in calls to the *line* method.

5.5 SOME USEFUL CLASSES

To avoid duplication of code, we now present some classes (*Input*, *Obj3D*, *Tria*, *Polygon3D*, *Canvas3D* and *Fr3D*) that we will frequently use later.

5.5.1 Input: A Class for File Input Operations

The first class we will discuss is *Input*. It is not really specific for computer graphics, but useful for any programming task that

involves reading data from a textfile in a simple way. We will use it to read data for 3D objects, specified in a particular format. There is an *Input* constructor that accepts the name of an input file as an argument, as well as a constructor without any arguments to read data from the keyboard. To demonstrate how easy it is to use this class, let us suppose we are given a textfile containing only numbers and we want to write a program to read this file and compute the sum of these numbers. For example, this

textfile, say, *example.txt*, may have the following contents:

```
2.5     6
200     100
```

Then the desired program is shown below:

```
// Sum.java: Demonstrating
//    of all numbers in the
//    only numbers and whit
public class Sum
{  public static void main
   {  float x, s=0;
      Input inp = new Inpu
      for (;;)
      { x = inp.readFloat(
        if (inp.fails())
           break;
```

```
            s + = x;
        }
        System.out.println("
    }
}
```

After compiling and executing this program in a directory that also contains the files *Input.java* and *example.txt*, the following output line is displayed:

```
The computed sum is 308.5
```

This example demonstrates the use of the *Input* constructor and of the methods *readFloat* and *fails*. The complete class *Input*, listed below, shows that it

contains some other useful methods as well:

```
// Input.java: A class to
// Methods of this class,
//    Input(fileName) (cons
//    Input()         (cons
//    readInt()       (read
//    readFloat()     (read
//    readChar()      (read
//    readString()    (read
//    skipRest()      (skip
//    fails()         (inpu
//    eof()           (fail
//    clear()         (rese
//    close()         (clos
//    pushBack(ch)    (push
import java.io.*;

class Input
```

```
{   private PushbackInputSt
    private boolean ok = tr
    private boolean eoFile

    Input(){pbis = new Push

    Input(String fileName)
    {   try
        {    InputStream is =
             pbis = new Pushb
        }
        catch(IOException ic
    }

    int readInt()
    {   boolean neg = false;
        char ch;
        do {ch = readChar();
        if (ch == '-'){neg =
```

```
        if (!Character.isDig
        {  pushBack(ch);
           ok = false;
           return 0;
        }
        int x = ch - '0';
        for (;;)
        {  ch = readChar();
           if (!Character.is
           x = 10 * x + (ch
        }
        return (neg ? -x : x
     }
float readFloat()
{  char ch;
   int nDec = -1;
   boolean neg = false;
   do
   {  ch = readChar();
```

```
}   while (Character.is
if (ch == '-'){neg = tr
if (ch == '.'){nDec = 1
if (!Character.isDigit(
float x = ch - '0';
for (;;)
{   ch = readChar();
    if (Character.isDigi
    {   x = 10 * x + (ch
        if (nDec >= 0) nD
    }
    else
    if (ch == '.' && nDe
    else break;
}
while (nDec > 0){x *= 0
if (ch == 'e'  ||   ch
{   int exp = readInt();
    if (!fails())
```

```
        {   while (exp < 0){
            while (exp > 0){
        }
    }
    else pushBack(ch);
    return (neg ? -x : x);
}

char readChar()
{   int ch=0;
    try
    {   ch = pbis.read();
        if (ch == -1) {eoFi
    }
    catch(IOException ioe){
    return (char)ch;
}

    String readString()
```

```
{   String str = " ";
    char ch;
    do ch = readChar();

    for (;;)
    {    ch = readChar();
       if (eof()  ||   c
          break;
       str += ch;
    }
    return str;
}

void skipRest()   // Sk
{   char ch;
    do ch = readChar();
}

boolean fails(){return
```

```
    boolean eof(){return ec
    void clear(){ok = true;

    void close()
    {   if (pbis != null)
        try {pbis.close();}c
    }

    void pushBack(char ch)
    {   try {pbis.unread(ch)
    }
}
```

Using a call to *readChar* immediately after *readInt* or *readFloat* causes the character immediately after the number to be read. To realize this, we use the standard Java class

PushbackInputStream, which enables us to push back, or ‘unread’ the last character that we have read and that does not belong to the number we are reading.

After an attempt to read a number by using *readInt* or *readFloat*,wecancall the *fails* method to check whether that attempt was successful. If *fails* returns *true*, a non-numeric character, such as a period in the second part of our input files, may have been read. It is then still possible to read that

character by using *readChar*.The *clear* method resets the error flag, so that we can resume input, using *fails* again. The method *fails* also returns *true* if an input operation fails because the end of the file is encountered during a call to one of the methods *readInt*, *readFloat* and *readChar*. In that case, the *eof* method also returns *true*. We can use the method *readString* to read a string surrounded by double quotes (”), as we will do in Chapter 8. To skip all remaining characters of the current input line, we use the

method *skipRest*.

5.5.2 Obj3D: A Class to Store 3D Objects

Let us now discuss the way the above class *Input* is used in the method *readObject* of the class *Obj3D*. Suppose we have an input file such as the one shown below:

```
1     0     0     0
2     0   100.5   0
3     0     0   1.5e2
Faces:
1 2 3.
3 2 1.
```

We will often use files of this type, which will be described in more detail in the next chapter. This example defines a 3D object that has only three vertices, with numbers 1, 2 and 3. The *x*-, *y*- and *z*-coordinates are given after each of these vertex numbers. The object has two faces, which are the two sides of the triangle with these three vertices. The first line following the word *Faces* indicates the side where we view the vertices 1, 2 and 3, in that order, counter-clockwise, while the last line denotes the other side. Obviously, which of these

two triangle sides we can see depends on the point of view.

A simplified version of the *Obj3D* method *readObject* is shown below. It shows how the class *Input* can be used to read data files such as the one shown above. In this fragment three dots (...) denote code that is not relevant in this discussion because it does not perform any input operations:

```
private boolean readObject
{  for (;;)
   { int i = inp.readInt()
     if (inp.fails()){inp.
     ...
```

```
    float x = inp.readFlo
          y = inp.readFlo
          z = inp.readFlo
    addVertex(i, x, y, z)
  }
  ...
  do   // Skip the line "
  {  ch = inp.readChar();
  }  while (!inp.eof() &&
  ...
  // Build polygon list:
  for (;;)
  {  Vector vnrs = new Ve
     for (;;)
     {  int i = inp.readI
        if (inp.fails()){
        ...
        vnrs.addElement(n
     }
```

```
            ch = inp.readChar();
            if (ch != '.') break
            // Ignore input line
            if (vnrs.size() >= 2
               polyList.addEleme
        }
        inp.close();
        return true;
    }
```

The above fragment is a simplified version of the method *readObject* of the class *Obj3D*, which we will now discuss in more detail. We will use this class to store all data of 3D objects, along with their 2D representations, in such a way

that this data is easy to use in our programs. We store three representations of vertices:

'Vector' *w* of *Point3D* elements:	world coordinates
Array *e* of *Point3D* elements:	eye coordinates
Array *vScr* of *Point2D* elements:	screen coordinates

Recall the classes *Point2D* and *Point3D* discussed in Sections

1.5 and 3.9. Since we read the world coordinates from an input file without knowing in advance how many vertices there will be, we use a Java *Vector* for them. This is different with the eye and screen coordinates. Since we compute these ourselves after we have read the world coordinates of all vertices, we know the size of the arrays *e* and *vScr*, so that we can allocate memory for them. We use the vertex numbers to indicate the positions in *w*, *e*,and *vScr*. In other words, with an input line of the form

we can find these world coordinates *x*, *y* and *z* of vertex *i* in the *Point3D* object

```
(Point3D)w.elementAt(i)
```

We use the *Obj3D* method *eyeAndScreen* to compute the corresponding eye coordinates and store them in the *Point3D* object

```
e[i]
```

This method also computes the corresponding screen coordinates and stores them in

the *Point2D* object

`vScr[i]`

It follows that *w.size*(), *e.length* and *vScr.length* will be one higher than the highest vertex number that is in use.

We will use the accessor methods *getE*() and *getVScr*() for access to the arrays *e* and *vScr*. The *Vector* object *w* will not be used at all outside the class *Obj3D*.

Another useful method of *Obj3D* is *planeCoeff*. For each face (or polygon) of the object, it

computes the coefficients *a*, *b*, *c* and *h* of the equation

$$ax + by + cz = h \qquad (5.10)$$

which describes the plane where this face lies. Using the first three vertices A, B and C of a polygon, we compute the normal vector **n** = (*a*, *b*, *c*) of the plane as the vector product **AB** × **AC** (see Section 2.4), scaled such that

$$a^2 + b^2 + c^2 = 1$$

Using the inner product (see Section 2.2) of **n** and a vector **x** = **EP** for any point P in the plane,

we can write (5.10) as

$$\mathbf{n} \cdot \mathbf{x} = h$$

in which *h* is positive if the sequence A, B and C is clockwise, that is, if ABC is a back face. On the other hand, if ABC is not a back face, *h* is negative and the sequence A, B and C is counter-clockwise. Recall that the positive *z*-axis (in the eye-coordinate system) points towards us, as is more or less the case with the normal vector **n** of a visible face. However, the vector **x** points away from us, which implies that

the inner product $\mathbf{n} \cdot \mathbf{x} = h$ will be negative for a visible face and positive for a back face. The absolute value of h is the distance between the eye E and the plane in question (see Exercise 7.1). We will use the coefficients a, b, c and h on several occasions. In the class *Obj3D*, the method *planeCoeff* computes these coefficients, after which they are stored in *Polygon3D* objects, as we will see shortly. This method *planeCoeff* also computes the maximum and minimum values of an inner product used to

determine which color is to be assigned to each face, as we will discuss in Section 7.2.

Since the file *Obj3D.java* is considerably larger than the program files we have seen so far, it is not listed here but you can find it in Appendix C. Here is a summary of all methods of this class that we can use outside it:

```
boolean read(String fName)
Vector getPolyList()
String getFName()
Point3D[] getE()
Point2D[] getVScr()
Point2D getImgCenter()
float getRho()
```

```
float getD()
float eyeAndScreen

void planeCoeff()

boolean vp(Canvas cv, floa

int colorCode(double a, dc
```

We will discuss the method *colorCode* in detail in Section 7.2. The public *Obj3D* method *read* calls the private method *readObject*, discussed above, as the following fragment shows:

```
boolean read(String fName)
{  Input inp = new Input(f
```

```
    ...
    return readObject(inp);
}
```

As we have seen in the simplified version of *readObject*, this method starts by repeatedly reading four numbers, *i*, *x*, *y* and *z*, and calls the method *addVertex*, which keeps track of the minimum and maximum values of *x*, *y* and *z*. The loop in which the four numbers are read terminates when an attempt to read a vertex number *i* fails because of the word *Faces*. The minimum and maximum coordinate values just mentioned

are required for a call to the private method *shiftToOrigin*, which reduces all world coordinates such that the origin of the coordinate center will coincide with the center of the bounding box of the object.

After skipping the rest of the line on which we encounter the word *Faces*,we enter a loop to read vertex-number sequences representing polygons. Vertex numbers in these sequences may be preceded by a minus sign, as we will discuss in Chapter 6, so that the vertex numbers are actually the absolute values of

the integers that we read.

Since we will often refer to the class *Obj3D*, let us have a look at a simplified version of it:

```
// Obj3D.java: A 3D object
// Uses: Point2D (Section
//       Polygon3D, Input
...
class Obj3D
{  ...
   private Vector w = new
   private Point3D[] e;
   private Point2D[] vScr;
   private Vector polyList
   ...
   private void addVertex(
   {  ...
```

```
        }
        . . .
}
```

Recall that the complete version is listed in Appendix C.

5.5.3 Tria: A Class to Store Triangles by Their Vertex Numbers

We will often store large sets of triangles, the vertices of which have numbers in the same way as letters normally used in geometry. Since several triangles may share some vertices, it

would not be efficient to store the coordinates of each vertex separately for every triangle. For example, suppose in 3D space we have a triangle with vertices 1, 2 and 3 and another with vertices 1, 4 and 2. It will then be efficient to set up a table with the *x*-, *y*- and *z*-coordinates of the four vertices 1, 2, 3 and 4, and denote the triangles only by their vertex numbers. The following class represents triangles in this way:

```
// Tria.java: Triangle rep
class Tria
{  int iA, iB, iC;
```

```
    Tria(int i, int j, int
}
```

If there had been no 3D programs in this book other than that for wireframe models, as discussed in Section 5.6, it would not have been necessary to store polygons, let alone triangles. We could then have restricted ourselves to the edges of 3D objects, that is, to line segments. We will nevertheless store the polygonal faces of the objects even in this chapter, to prepare for some more interesting programs where hidden lines or faces are not displayed.

5.5.4 Polygon3D: A Class to Store 3D Polygons

Almost at the end of the *Obj3D* method *readObject* you may have noticed the following statement:

```
polyList.addElement(new Pc
```

Here a new *Polygon3D* object is created to store the vertex numbers of a polygon. This object is then added to the *Vector* object *polyList*, a private variable of the class

Obj3D.Theclass *Polygon3D* contains a number of methods that we will not use in this chapter. These are related to triangles resulting from polygons and will be useful in the next two chapters, in which we will be dealing with algorithms to eliminate hidden lines and faces. Thanks to the above class *Tria*, the coordinates of the vertices of each triangle are not duplicated. Since they are stored in arrays that are data members of the *Obj3D* class, we only need to store the numbers *iA*, *iB* and *iC* of the vertices here. Although, in

Section 2.13, we have already used a method *triangulate* to divide a polygon into triangles, we will need a slightly different one that represents vertices by numbers referring to the *Obj3D* class. This special method for triangulation is part of the class *Polygon3D*, listed below:

```
// Polygon3D.java: Polygon
//                 referri
import java.util.*;
class Polygon3D
{  private int[] nrs;
   private double a, b, c,
   private Tria[] t;
   Polygon3D(Vector vnrs)
   {  int n = vnrs.size();
```

```
    nrs = new int[n];
    for (int i=0; i<n; i
       nrs[i] = ((Intege
}

int[] getNrs(){return n
double getA(){return a;
double getB(){return b;
double getC(){return c;
double getH(){return h;
void setAbch(double a,
{  this.a = a; this.b =
}
Tria[] getT(){return t;

void triangulate(Obj3D
// Successive vertex nu
// Resulting triangles
{ int n = nrs.length;
```

```
int[] next = new int[
t = new Tria[n - 2];
Point2D[] vScr = obj.
int iA=0, iB, iC; int
for (int i=0; i<n; i+
for (int k=0; k<n-2;
{   // Find a suitabl
    // and an internal
    Point2D a, b, c;
    boolean found = fa
    int count = 0, nA
    while (!found && +
    {  iB = next[iA];
       nA = Math.abs(n
       nB = Math.abs(n
       nC = Math.abs(n
       if (Tools2D.are
       {  // Edges AB
          // Test to s
```

```
                // B, C) lie
                j = next[iC]
                while (j !=
                       (nj ==
                       !Tools
                    {  j = ne
                    }
                if (j == iA)
                {   // Trian
                  t[k] = new
                  next[iA] =
                  found = tr
                }
              }
              iA = next[iA];
            }
            if (count == n)
            {   // Degenerated
              // vertices on
```

```
                    if (nA >= 0) t
                    else
                    { System.out.p
                      System.exit(
                    }
                }
            }
        }
    }
```

The vertex numbers of the given polygon are available in the array *nrs*, while those of each resulting triangle are stored in an element of the array *t*.Themost difficult part of this class is the method *triangulate*, which is the 3D equivalent of the *Tools2D* method

with the same name, discussed in Section 2.13 and not used in this chapter.

5.5.5 Canvas3D: An Abstract Class to Adapt the Java Class Canvas

The canvas classes we will be using will contain the methods *getObj* and *setObj*, to retrieve and store a reference to an *Obj3D* object. In view of a separate frame class, *Fr3D*, we need to define the following abstract class:

```
// Canvas3D.java: Abstract
import java.awt.*;

abstract class Canvas3D ex
{  abstract Obj3D getObj()
   abstract void setObj(Ob
}
```

Remember, abstract classes are only useful to create subclasses, not to define objects. Any (non-abstract) subclass of *Canvas3D* is simply a subclass of the standard class *Canvas*, except that it is guaranteed to define the methods *getObj* and *setObj*. For example, in the next section we

will discuss a class *CvWireframe* of which the first line reads

```
class CvWireframe extends
```

By writing here *Canvas*3*D* instead of *Canvas*, we are obliged to define the methods *getObj* and *setObj* in this *CvWireframe* class, and in return we are allowed to call these two methods for any object of class *CvWireframe*. We will clarify the use of the abstract class *Canvas*3*D* further at the end of this section.

5.5.6 Fr3D: A Frame

Class for 3D Programs

The class *Fr3D* will be used in four non-trivial 3D programs of this book, *Wireframe.java* (Section 5.6), *HLines.java* (Chapter 6), *Painter.java* (Section 7.3) and *ZBuf.java* (Section 7.4). Since these programs will have the same menus, it makes sense to let them share the file *Fr3D.java*, listed below, in which much of the code is related to these menus. The Java compiler accepts the calls *cv.getObj*() and *cv.setObj*(*obj*) in this file because,

as *Canvas3D* is an abstract class, the actual type of *cv* can only be a subclass of it. As we have just seen, this implies that this subclass will define the methods *getObj* and *setObj*:

```
// Fr3D.java: Frame class
//    user actions.
import java.awt.*;
import java.awt.event.*;
import java.util.*;

class Fr3D extends Frame i
{  protected MenuItem open
      incrDist, decrDist;
   protected String sDir;
protected Canvas3D cv;
protected Menu mF, mV;
```

```
Fr3D(String argFileName, C
{ super(textTitle);
  addWindowListener(new Wi
     {public void windowCl
  this.cv = cv;
  MenuBar mBar = new MenuB
  setMenuBar(mBar);
  mF = new Menu("File");
  mV = new Menu("View");
  mBar.add(mF); mBar.add(m

  open = new MenuItem("Ope
     new MenuShortcut(KeyE
  eyeDown = new MenuItem("
     new MenuShortcut(KeyE
  eyeUp = new MenuItem("Vi
     new MenuShortcut(KeyE
  eyeLeft = new MenuItem("
```

```
    new MenuShortcut(KeyE
eyeRight = new MenuItem(
    new MenuShortcut(KeyE

incrDist = new MenuItem(
    new MenuShortcut(KeyE
decrDist = new MenuItem(
    new MenuShortcut(KeyE
exit = new MenuItem("Exi
    new MenuShortcut(KeyE
mF.add(open); mF.add(exi
mV.add(eyeDown); mV.add(
mV.add(eyeLeft); mV.add(
mV.add(incrDist); mV.add
open.addActionListener(t
exit.addActionListener(t
eyeDown.addActionListene
eyeUp.addActionListener(
eyeLeft.addActionListene
```

```
    eyeRight.addActionListen
    incrDist.addActionListen
    decrDist.addActionListen
    add("Center", cv);
    Dimension dim = getToolk
    setSize(dim.width/2, dim
    setLocation(dim.width/4,
    if (argFileName != null)
    {  Obj3D obj = new Obj3D
       if (obj.read(argFileN
    }
    cv.setBackground(new Col
    show();
}

void vp(float dTheta, floa
{  Obj3D obj = cv.getObj()
    if (obj == null  ||   !
       Toolkit.getDefaultTo
```

```
}

public void actionPerforme
{  if (ae.getSource() inst
   {  MenuItem mi = (MenuI
      if (mi == open)
      {  FileDialog fDia =
         "Open", FileDialc
         fDia.setDirectory
         fDia.setFile("*.c
         fDia.show();
         String sDir1 = fD
         String sFile = fD
         String fName = sD
         Obj3D obj = new C
         if (obj.read(fNam
         {  sDir = sDir1;
            cv.setObj(obj)
            cv.repaint();
```

```
            }
        }
        else
        if (mi == exit) Syst
        if (mi == eyeDown) v
        if (mi == eyeUp) vp(
        if (mi == eyeLeft) v
        if (mi == eyeRight)
        if (mi == incrDist)
        if (mi == decrDist)
    }
  }
}
```

Notice the use of the abstract class *Canvas*3*D* in the line

```
Fr3D(String argFileName, C
```

almost at the beginning of class

Fr3D. We cannot replace *Canvas3D* with *Canvas* here because the compiler would not accept the statement

```
cv.setObj(obj);
```

in the if-statement near the end of the *Fr3D* constructor. After all, *setObj* is not a method of the standard Java class *Canvas*. Since, in the next section we will actually be using the class *CvWireframe*,ofwhich *setObj* is really a method, it is tempting to write *CvWireframe* instead of *Canvas3D*. This would indeed work, but then we would not be

able to use the class *Fr3D* also in programs with canvas classes other than *CvWireframe*, as we will do in Chapters 6 and 7. We now see that the abstract class *Canvas3D* is very useful. It is general enough to be used in several of our programs and yet less general than the standard *Canvas* class in that it 'promises' an implementation of the methods *setObj* and *getObj*. We will discuss some aspects of the class *Fr3D* in Chapter 7 when using it.

5.6 A GENERAL PROGRAM FOR WIRE-FRAME MODELS

It is now time to see the classes of the previous section in action. A relatively simple way of displaying 3D objects, bounded by polygons, is by drawing all the edges of these polygons, as we did for a cube in Section 5.4. The classes we have just seen enable us to write a general program *Wireframe.java*,which reads input files through a menu command *Open* and enables the user to view the object from any

reasonable viewpoint, by using either menu commands or the keyboard. The comment lists all classes that *Wireframe.java* directly or indirectly uses.

```
// Wireframe.java: Perspec
//     vertices and faces.
// Uses: Point2D (Section
//       Triangle, Tools2D
//       Point3D (Section
//       Input, Obj3D, Tri
//       CvWireframe (Sect
import java.awt.*;

public class Wireframe ext
{  public static void main
   {  new Fr3D(args.length
         "Wire-frame model"
```

```
        }
}
```

This rather simple program file accepts an optional program argument, which may be supplied to specify the name of the input file. This is what the first argument, a conditional expression, of the *Fr3D* constructor is about. The second argument of this constructor generates an object of class *CvWireframe*, which does almost all the work. Finally, the third argument specifies the text, *Wire-frame model*, that we want to appear in the title bar of the

window. The class *CvWireframe* is listed below:

```
// CvWireframe.java: Canva
import java.awt.*;
import java.util.*;

class CvWireframe extends
{  private int maxX, maxY,
   private Obj3D obj;
   private Point2D imgCent

   Obj3D getObj(){return c
   void setObj(Obj3D obj){
   int iX(float x){return
   int iY(float y){return

   public void paint(Graph
   {  if (obj == null) ret
```

```
Vector polyList = ob
if (polyList == null
int nFaces = polyLis
if (nFaces == 0) ret
Dimension dim = getS
maxX = dim.width - 1
centerX = maxX/2; ce
// ze-axis towards e
// object points are
// obj is a java obj
// - Vector w
// - Array e
// - Array vScr
// - Vector polyList

// Every Polygon3D v
// - Array 'nrs' for
// - Values a, b, c,
// (- Array t (with
```

```
obj.eyeAndScreen(dim
      // Computation

imgCenter = obj.getI
obj.planeCoeff();
Point3D[] e = obj.ge
Point2D[] vScr = obj

g.setColor(Color.bla

for (int j=0; j<nFac
{  Polygon3D pol = (
   int nrs[] = pol.g
   if (nrs.length <
      continue;
   for (int iA=0; iA
   {  int iB = (iA +
      int na = Math.
```

```
                    // abs in view
                    Point2D a = vS
                    g.drawLine(iX(
                }
            }
        }
    }
```

Thanks to the other classes discussed in the previous section, this program file is rather small. However, due to the object-oriented character of Java, the flow of control of the whole program may not be immediately clear. In particular, you may wonder how starting the program leads to reading a 3D object file

and displaying the desired image. Let us begin with the *main* method in the file *Wireframe.java*.Here an *Fr3D* object is created by calling its constructor, and a *CvWireframe* object is created at the same time in the second argument of this constructor call. As we have seen in the previous section, the first line of class *Fr3D* reads

```
class Fr3D extends Frame i
```

which indicates that this class contains a method *actionPerformed*. This method is called when a menu command is

given. In particular, the *Open* command in the *File* menu triggers the execution of a fragment that causes a standard dialog box for 'Open file' to appear, as you can see in the method *actionPerformed* at the end of Section 5.5. This fragment contains the following:

```
Obj3D obj = new Obj3D();
if (obj.read(fName))
{   sDir = sDir1;
    cv.setObj(obj);
    cv.repaint();
}
```

Here we see that the *Obj3D* method *read* is called, with the

file name supplied by the user as an argument, so that this method can read any 3D object provided by the user. We also find here a call to *setObj*, a method defined in the above class *CvWireframe* as

```
void setObj(Obj3D obj){thi
```

As a result, the *CvWireframe* class gets access to the *Obj3D* object that contains all data for the real 3D object. The above if-statement also contains a call to the standard Java *Canvas* method *repaint*, which calls the method *paint* of our

CvWireframe class. The actual computation and display of the image are done in this method *paint*, although much of the computation work is delegated to methods of other classes. An example of this is the statement

```
obj.eyeAndScreen(dim);
```

which calls the *Obj3D* method *eyeAndScreen* to compute the eye and screen coordinates of the object.

5.6.1 A Demonstration

It is now time to see the program

Wireframe.java in action. For example, let us use the object with vertices 1, 2, …, 6, shown in Figure 5.12.


z
6
5
O
4
3
y
X
1
2

Figure 5.12: Object and vertex numbers

With dimensions 1, 3 and 5 for the thickness, the width and the height, respectively, the following data file specifies this object:

```
1   1 0 0
2   1 3 0
3   0 3 0
4   0 0 0
5   1 0 5
6   0 0 5
Faces:
1 2 5.
3 4 6.
```

```
2 3 6 5.
1 5 6 4.
1 4 3 2.
```

When running program *Wireframe.java* and opening the above input file, a window as shown in Figure 5.13 appears.



Figure 5.13: Default view of object

By moving the point of view, using the *Viewpoint to Right* command from the *View* menu or

its shortcut *Ctrl+Arrow right* a number of times, we obtain a different view of the same object, as shown in Figure 5.14.



Figure 5.14: Same object viewed from the back

Note that the program chooses a default viewing distance which is quite reasonable. If desired we can increase or decrease this distance using two commands from the *View* menu.

EXERCISES

Modify program *CubePers.java* of Section 5.4 in such a way that, *with the*

given viewpoint, only the visible edges are drawn as solid black lines; draw the other, invisible lines in a different color, or, as usually in mechanical engineering, as dashed lines (see Exercise 1.5).

5.1 ?

Use a *fillPolygon* method to display only the top, right and front faces of Figure 5.10 as filled polygons of different colors.

5.2 ?

5.3 To prepare for Exercise 5.5, extend program *CubePers.java* of Section 5.4 so that two cubes beside each other are generated.

Use the class *Rota3D* of Section 3.9 to apply *animation with double buffering* to the cube of Section 5.4, using a rotation about some line, say,

0–6 (see Figure 5.11) through some small angle. If you are unfamiliar with animation in Java or with the Java class *Image*, required for double buffering, you will find the program *Anim.java* in Appendix F helpful.

5.4 ?

As Exercise 5.4, but the rotation is to be applied to the two cubes of Exercise 5.3. Use different

axes of rotation and increase the rotation angles for the two

5.5 cubes by different amounts, so that the cubes seem to rotate independently of each other, with different speeds. Figure 5.15 shows a snapshot of the two cubes, each rotating about one of its vertical edges.

?

Answers

As Figure 5.11 shows, nine c
method of program *CubePer*
fragment:

```
// Visible edges:
line(g, 0, 1); line(g
line(g, 1, 2); line(g
line(g, 5, 6);

// Invisible edges:
g.setColor(Color.blue
line(g, 0, 3); line(g
```

If you did Exercise 1.5 and h
available, you may be able to

```
dash(g, 0, 3); dash(g
```

while adding the following me

```
void dash(Graphics g,
```

```
5.1 {   Point2D P = obj.vS
        Lines.dashedLine(g
    }
```

Figure F.1 shows the result o



Figure F.1: Dashed lines r

There are two *fillPolygon* me
other taking two arrays *x* and
5.2 device coordinates, using the
before each of the three calls

To replace Figure 5.11, begir
plane, and by assigning the r
5.3 second cube. With this sketc
you can easily update the pro
objSize,which is used to com

The following program demo
a simple case: a line segmer
the canvas. Every 20 ms, the

origin O (in the center of the
that of a running clock with o

```
// Anim.java: Animati
import java.awt.*;
import java.awt.event
public class Anim ext
{  public static void

   Anim()
   {  super("Animatio
      addWindowListen
       {public void w
                {Syste
      add("Center", n
      Dimension dim =
      setSize(dim.wid
      setLocation(dim
      show();
```

```
        }
    }
    class CvAnim extends
        implements Runnabl
    {   float rWidth = 10.
        int centerX, cente
        Dimension d;
        Image image;
        Graphics gImage;

        float alpha = 0;
        Thread thr = new T

        public void run()
        {   try
            { for (;;)
              {   alpha += 0
                  repaint();
                  Thread.sle
```

5.4

```
        }
      }
      catch (Interrup
    }

    CvAnim(){thr.start

    void initgr()
    {  d = getSize();
       int maxX = d.wi
       pixelSize = Mat
       centerX = maxX/
       xC = rWidth/2;
    }

    int iX(float x){re
    int iY(float y){re
    public void update
    public void paint(
```

```
        {   initgr();
            if (w != d.widt
            {    w = d.width
                 image = cre
                 gImage = im
            }
            float r = 0.8F
                x = r * (flo
                y = r * (flo
            gImage.clearRec
            // Every 20 ms,
            // Each time, i
            // different po
                gImage.drawL
                g.drawImage(
        }
    }
```

The following program produ
Remember, this program wo
available in the current direct

```
// CubRot2.java: Two
//    Uses: Point2D (S
//          Point3D, R
import java.awt.*;
import java.awt.event

public class CubRot2
{  public static void

   CubRot2()
   {  super("Rotating
      addWindowListen
       {public void w
                {Syste
      add("Center", n
```

```
            Dimension dim =
            setSize(3 * dim
            setLocation(dim
            show();
        }
    }

    class CvCubRot2 exten
        implements Runnabl
    {   int centerX, cente
        Obj2 obj = new Obj
        Image image;
        Graphics gImage;

        double alpha = 0;
        Thread thr = new T

        public void run()
    {   try
```

```
    {   for (;;)
        {   alpha += 0.0
            repaint();
            Thread.sleep
        }
    }
    catch (Interrupted
}

CvCubRot2(){thr.start
public void update(Gr

int iX(float x){retur
int iY(float y){retur

void line(int i, int
{   Point2D P = obj.vS
    gImage.drawLine(iX
}
```

```
public void paint(Gra
{   Dimension dim = ge
    int maxX = dim.wid
    centerX = maxX/2;
    int minMaxXY = Mat
    obj.d = obj.rho *
    obj.rotateCube(alp
    obj.eyeAndScreen()
    if (w != dim.width
    {   w = dim.width;
        image = createI
        gImage = image.
    }
    gImage.clearRect (
    // Horizontal edge
    line (0, 1); line
    // Horizontal edge
    line (4, 5); line
    // Vertical edges:
```

5.5

```
        line (0, 4); line
        // Same for second
        line (8, 9); line
        // Horizontal edge
           line (12, 13);
           // Vertical edg
           line (8, 12); l
           g.drawImage(ima
        }
    }

    class Obj2 // Contain
    {    float rho, theta=
         Point3D[] s, w; /
         Point2D[] vScr; /
         float v11, v12, v
           v32, v33, v43,
           xe, ye, ze, obj
```

```
Obj2()
{   s = new Point3
    w = new Point3
    vScr = new Poi
    // Bottom surf
    s[0] = new Poi
    s[1] = new Poi
    s[2] = new Poi
    s[3] = new Poi
    // Top surface
    s[4] = new Poi
    s[5] = new Poi
    s[6] = new Poi
    s[7] = new Poi
    // Bottom surf
    s[8] = new Poi
    s[9] = new Poi
    s[10] = new Po
    s[11] = new Po
```

```
            // Top surface
            s[12] = new Po
            s[13] = new Po
            s[14] = new Po
            s[15] = new Po
            rho = 15; // F
        }

    void rotateCube(doubl
        {   Rota3D.initRot
            for (int i=0;
                w[i] = Rota
            Rota3D.initRot
            for (int i=8;
                w[i] = Rota
        }

        void initPersp()
        {  float costh = (
```

```
                sinth = (
                cosph = (
                sinph = (
        v11 = -sinth;
        v12 = -cosph *
        v13 = sinph * c
        v21 = costh;
        v22 = -cosph *
        v23 = sinph * s
        v32 = sinph;
        v33 = cosph;
        v43 = -rho;
    }

    void eyeAndScreen(
    {   initPersp();
        for (int i=0; i
        {   Point3D P =
            float x = v1
```

```
                    float y = v1
                    float z = v1
                    Point3D Pe =
                    vScr[i] = ne
                        Point2D(-
                }
            }
        }
```



Figure 5.15: Snapshot of two cubes rotating about vertical axes

Chapter 6: Hidden-Line Elimination

Traditionally, engineers who want to display three-dimensional objects use line drawings, with black lines on white paper. Although line drawings might look rather dull compared with colored representations of such objects, there are many technical applications for which they are desired. We will now produce exactly the set of line segments that appear in the

final result, so we will not put any pixels on the screen that we overwrite later, as we will do in Chapter 7. An advantage of this approach is that this set can also be used for output on a printer or a plotter. Since each of these line segments will be specified only by its endpoints, the possibly limited resolution of our computer screen does not affect the representation of the lines on the printer or plotter; in other words, these lines are of high quality. By using HP-GL (short for Hewlett-Packard Graphics

Language) as our file format, we will be able to import the files we produce in text processors such as Microsoft Word. Still better, we can use drawing programs such as CorelDraw to read these files and then enhance the graphics results, for example, by adding text and changing the line type and thickness, before we import them into our documents. In this book, most line drawings of 3D objects have been produced in this way.

6.1 LINE SEGMENTS AND TRIANGLES

Although the faces of the objects we are dealing with can be polygons with any number of vertices, we will triangulate these polygons and use the resulting triangles instead. Suppose we are given a set of line segments PQ and a set of triangles ABC in terms of the eye and screen coordinates of all points P, Q, A, B and C. It will then be our task to draw each line segment PQ as far as none of the triangles ABC obscures them. A line segment

(or *line*, for short) may be completely visible, completely invisible or partly visible. For example, in Figure 6.1, line 1 is completely visible because it lies in front of the triangle on the left and is unrelated to the other two triangles. In contrast, line 2 lies behind the triangle in the middle and is therefore completely invisible. Finally, lines 3 and 4 are not completely visible, but some parts of them are.



Figure 6.1: Triangles and line segments

There is another important case: since the edges of the triangles are also line segments, it will frequently occur that a line segment is an edge of the triangle under consideration. Such line segments are to be considered visible, as far as that triangle is concerned. For

example, consider the letter L in Figure 6.2. Here the only line segment that is partly visible and partly invisible is the line 7–8, which intersects the face 1-2-10-9-6-5, or rather one of the triangles (6-10-9, for example) of which this face consists. In the image, the line 7–8 intersects the edge 6–9 of that triangle in point I, which divides this line into the visible part 8-I and the invisible one I-7.



Figure 6.2: A non-convex polyhedron

6.2 TESTS FOR VISIBILITY

On the basis of the given faces of the object, we build a set of triangles and a set of line segments. Then for each line segment PQ, we call a method *lineSegment*, which has the task to draw any parts of PQ that are visible. This method is recursive and can be represented in the flowchart in Figure 6.3, where the numbered tests performed in different steps will be individually discussed in this section and the boxes with double edges denote

recursive calls.


lineSegment(PQ, a set of triangles)
More triangles?
No
Draw PQ
End
Yes
Take one triangle ABC
No
ABC obscures PQ?
Tests 1-6, and 8
Yes
Yes
Completely?
Test 7
No
Find intersection point I and take visible part PI
Test 9
LineSegment(PI, remaining triangles)
Find intersection point J and take visible part JQ
Test 9
LineSegment(JQ, remaining triangles)
End

Figure 6.3: Flowchart for *lineSegment* method

This flowchart is equivalent to the following pseudocode, in which I and J are points (between P and Q) of line segment PQ. On the screen we view I and J as intersecting points of PQ with edges of triangle ABC:

```
void lineSegment(line
{ In set s, try to fin
If no such triangle fc
    Draw PQ
Else
{ If triangle ABC leav
```

```
            lineSegment(PI, th
          If triangle ABC leav
            lineSegment(JQ, th
    }
  }
```

According to both the flowchart and this pseudocode, the loop that searches the set of triangles terminates as soon as a triangle ABC is found that obscures PQ.

If ABC obscures PQ completely, no other action is required. If ABC obscures PQ partly, the parts that are possibly visible are dealt with recursively, using the remaining triangles. Note that in

these cases the remaining triangles of the current loop are not applied to the whole line segment PQ anymore. The line PQ is drawn only if none of the triangles obscures it, that is, after the loop is completed.

To make the above algorithm as fast as we can, we should be careful with the order in which we perform several tests when we are looking for a triangle that obscures PQ. Tests that take little computing time and are likely to succeed are good candidates for being performed as soon as possible. Sometimes

these aspects are contradictory. For example, in the sequence of tests that we will be discussing, the second is not very likely to succeed but it nevertheless deserves its position in this sequence because it is very inexpensive. The inner part of the loop that searches the set of triangles is discussed in greater detail below. Since we have to be careful with small numerical errors due to the finite precision of floating-point computations, we sometimes use small positive real numbers $\varepsilon = eps$ as tolerances, as these examples

show:

Mathematical expression	Implementation in program
$x \leq a$	x<a+eps
$x < b$	x<b-eps
$y \geq c$	y>c-eps
$y > d$	y>d+eps

In the second column, it does not make any significant difference if we replace < with <=,and > with >=. We should take some care in choosing the value of *eps*, since this should preferably be related

to the magnitude of the numbers we are comparing. You can find details of such tolerance values ε in the program file *HLines.java*, but they are omitted in the discussion below for the sake of clarity.

6.2.1 Test 1 (2D; Figure 6.4)



Figure 6.4: Test 1: both P and Q on the left of A, B and C

If neither P nor Q lies to the right of the leftmost one of the three vertices A, B and C (of triangle *t*) the triangle does not obscure PQ. This type of test is known as

a *minimax* test: we compare the maximum of all *x*-coordinates of PQ with the minimum of all those of triangle *t*. Loosely speaking, we have now covered the case that PQ lies completely to the left of triangle *t*. In the same way, we deal with PQ lying completely to the right of *t*. Similar tests are performed for the minimum and maximum *y*-coordinates.

6.2.2 Test 2 (3D; Figure 6.5)



Figure 6.5: Test 2: PQ identical with AB

If PQ (in 3D space) is identical with one of the edges of triangle *t*, this triangle does not obscure PQ. This test is done very efficiently by using the vertex numbers of P, Q, A, B and C. As we will see in a moment, in

recursive calls, P or Q may be a computed point, which has no vertex number. It is therefore not always possible to perform this test.

6.2.3 Test 3 (3D; Figure 6.6)



Figure 6.6: Test 3: P and Q nearer than A, B and

C

If neither P nor Q is further away than the nearest of the three vertices A, B and C of triangle *t*, this triangle does not obscure PQ. This is a minimax test, like Test 1, but this time applied to the *z*-coordinates. Since the positive *z*-axis points to the left in Figure 6.6, the greater the *z*-coordinate of a point, the nearer this point is. Therefore, triangle ABC does not obscure PQ if the minimum of z_P and z_Q is greater than or equal to the maximum of z_A, z_B and z_C.

6.2.4 Test 4 (2D; Figure 6.7)



Figure 6.7: Test 4: P and Q on a side of AB different from that of C

If, on the screen, the points P and Q lie on one side of the line AB while the third triangle vertex C lies on the other, triangle ABC does not obscure PQ.

The lines BC and CA are dealt with similarly. This test is likely to succeed, but we perform it only after the previous three tests because it is rather expensive. Since the vertices A, B and C are counter-clockwise, the points P and C are on different sides of AB if and only if the point sequence ABP is clockwise. As we have seen in Section 2.5, this implies that we can use the static method *area2* of class *Tools2D*.With *Point2D* objects *AScr*, *BScr*, *CScr* for the points A, B and C, the left-hand side in the comparison

`Tools2D.area2(AScr, BScr,`

is equal to twice the area of triangle ABP, preceded by a minus sign if (and only if) the sequence ABP is clockwise. This value is negative if P and C lie on different sides of AB, and it is zero if A, B and P lie on a straight line. If this comparison succeeds and the same applies to

`Tools2D.area2(AScr, BScr,`

then the whole line PQ and point C lie on different sides of the line AB, so that triangle ABC does not obscure line segment PQ.

After this test for the triangle edge AB, we use similar tests for edges BC and CA.

Note that P and Q can both lie outside triangle ABC, while PQ intersects this triangle. This explains the above test, which at first may look quite complicated. Unfortunately, the current test does not cover all cases in which PQ lies outside triangle ABC, as you can see in Figure 6.8.



Figure 6.8: Test 5: triangle ABC on one side of PQ

6.2.5 Test 5 (2D; Figure 6.8)

Triangle ABC does not obscure PQ if the points A, B and C lie on the same side of the infinite line through P and Q. We determine if this is the case using a test that

is similar to the previous one:

$$(PQA \leq 0 \text{ and } PQB \leq 0 \text{ and } PQC \leq 0) \text{ or}$$
$$(PQA \geq 0 \text{ and } PQB \geq 0 \text{ and } PQC \geq 0)$$

where *PQA*, obtained as

```
double PQA = Tools2D.area2
```

denotes twice the area of triangle PQA, preceded by a minus sign if the point sequence P, Q, A is clockwise. The variables *PQB* and *PQC* have similar meanings.

6.2.6 Test 6 (3D; Figure 6.9)

If neither P nor Q lies behind the plane through A, B and C, triangle ABC does not obscure PQ. This test deals with those line segments PQ for which Test 3 failed because the further one of the points P and Q does *not* lie nearer than the nearest of A, B, C, while P and Q nevertheless lie on the same side of the (infinite) plane ABC as the viewpoint E. Figure 6.9 illustrates this situation.



Figure 6.9: Test 6: neither P nor Q behind plane ABC

We now benefit from the fact that we have stored the normal vector **n** = (*a*, *b*, *c*) of plane ABC and the distance *h* between E and this plane. The equation of this plane is

$$ax + by + cz = h$$

We compute

$$h_{\mathrm{P}} = \mathbf{n} \cdot \mathrm{EP}$$

$$h_{\mathrm{Q}} = \mathbf{n} \cdot \mathrm{EQ}$$

to perform the following test, illustrated by Figure 6.9:

$$|h_{\mathrm{P}}| \leq |h| \text{ and } |h_{\mathrm{Q}}| \leq |h|$$

Since **n**, when starting at E, points away from the plane, the values of h_P, h_Q, like that of h, are negative, so that this test is equivalent to the following:

$$h_{\mathrm{P}} \geq h \text{ and } h_{\mathrm{Q}} \geq h$$

6.2.7 Test 7 (2D; Figure 6.10)



Figure 6.10: Test 7: PQ behind triangle ABC

If (on the screen) neither P nor Q lies outside the triangle ABC, and the previous tests were

indecisive, PQ lies behind this triangle and is therefore completely invisible. The *Tools2D* method *insideTriangle*, discussed in Section 2.8, makes this test easy to program:

```
boolean pInside = Tools2D.
boolean qInside = Tools2D.
if (pInside && qInside) re
```

The partial results of this test, stored in the boolean variables *pInside* and *qInside*, will be useful in Tests 8 and 9 in the case that this test fails.

6.2.8 Test 8 (3D; Figure

6.11)



Figure 6.11: Test 8: P nearer than plane ABC

If P is nearer than the plane of triangle ABC and, on the screen, P lies inside triangle ABC, this triangle does not obscure PQ. The same is true for Q.

This test relies on the fact that no line segment PQ intersects any triangle. This test is easy to perform since the variables h_P and h_Q, computed in Test 6, and *pInside* and *qInside*, computed in Test 7, are now available. Using also the abbreviations *pNear* for $h_P > h$ and *qNear* for $h_Q > h$, we conclude that triangle ABC does not obscure PQ if the following is true:

```
pNear && pInside || qNear
```

6.2.9 Test 9 (3D; Figure 6.12)



Figure 6.12: Test 9: I and J in front of plane ABC

Although it might seem that, after Test 8, all cases with PQ not being obscured have been dealt with, this is not the case, as Figure 6.12 illustrates. In this example, Q lies behind the plane ABC, and, on the screen, PQ

intersects ABC in the points I and J, but PQ is nevertheless completely visible (as far as triangle ABC is concerned). This is because both points of intersection, I and J, lie in front of (that is, nearer than) triangle ABC. We take three steps to deal with this situation:

1. We compute (the 2D projections of) I and J on the screen.

2. We compute the *z*-values of I and J by linear interpolation of $1/z$ (see Section 7.4

and Appendix A).

3. To determine if I and J lie in front of the plane ABC, we compute how far I and J lie away in the direction towards this plane.

We will now discuss these three steps in more detail, starting with step 1, which we deal with as a 2D problem, writing, for example, P for what is actually the projection P′ of P on the screen.

Since we do not know in advance which of the three triangle edges

AB, BC and CA may intersect PQ, we try all three by rotating the points A, B and C. Here we deal only with AB. Suppose that, on the screen, the infinite line PQ intersects the infinite line AB in point I, where

$$\mathrm{PI} = \lambda \mathrm{PQ} \qquad (6.1)$$

$$\mathrm{AI} = \mu \mathrm{AB} \qquad (6.2)$$

Then point I belongs to the line *segments* PQ and AB if and only if

$$0 \leq \lambda \leq 1 \text{ and } 0 \leq \mu \leq 1$$

While rotating A, B and C, we

may find two points of intersection, with λ and μ satisfying these restrictions. We then denote the values λ of these points by λ_{min} and λ_{max}, and the corresponding points with I and J, so that we have

$$0 \leq \lambda_{\min} < \lambda_{\max} \leq 1$$

$$\mathbf{PI} = \lambda_{\min}\mathbf{PQ}$$

$$\mathbf{PJ} = \lambda_{\max}\mathbf{PQ}$$

As for the actual computation of λ and μ, let us use the vectors **u** = **PQ** and **v** = **AB**. It then follows from Equations (6.1) and (6.2) that we can express point I as

the left- and right-hand sides of the following equation:

$$\mathbf{P} + \lambda\mathbf{u} = \mathbf{A} + \mu\mathbf{v}$$

Writing **w** = **PA**(= **A** − **P**), we can replace this with

$$\lambda\mathbf{u} - \mu\mathbf{v} = \mathbf{w}$$

As usual, we write **u** = (u^1, u^2) and so on, which expands this vector equation to the following set of simultaneous linear equations:

$$u_1\lambda - v_1\mu = w_1$$

$$u_2\lambda - v_2\mu = w_2$$

Solving this system of equations, we obtain

$$\lambda = \frac{v_1 w_2 - v_2 w_1}{u_2 v_1 - u_1 v_2}$$

$$\mu = \frac{u_1 w_2 - u_2 w_1}{u_2 v_1 - u_1 v_2}$$

It goes without saying that this applies only if the denominators in these expressions are non-zero; otherwise PQ and AB are parallel, so that there are no points of intersection.

Having found the points I and J

on the screen, we turn to step 2, to compute their z-coordinates. We do this by linear interpolation of $1/z$ on the segment PQ. Using the values λ_{min} and λ_{max}, which we have just found, and referring to Equation (6.1), we can write

$$\frac{1}{z_I} = \frac{1}{z_P} + \lambda_{min}\left(\frac{1}{z_Q} - \frac{1}{z_P}\right) = \frac{\lambda_{min}}{z_Q} + \frac{1-\lambda_{min}}{z_P}$$

$$\frac{1}{z_I} = \frac{1}{z_P} + \lambda_{max}\left(\frac{1}{z_Q} - \frac{1}{z_P}\right) = \frac{\lambda_{max}}{z_Q} + \frac{1-\lambda_{max}}{z_P}$$

Refer to the discussion in Section 7.4 and Appendix A about the reason why we should use $1/z$ instead of simply z in this type of linear interpolation.

Finally, we proceed to step 3, to determine whether or not the points I and J lie in front of the plane through the points A, B and C. Recall that the equation of this plane is

$$ax + by + cz = h$$

where h is negative, and that its normal vector (with length 1) is

$$\mathbf{n} = (a, b, c)$$

We compute the value h_I, which is similar to h_P, discussed in Test 6 and illustrated by Figure 6.9, as

$$h_{\mathrm{I}} = \mathrm{EI} \cdot \mathbf{n} = ax_{\mathrm{I}} + by_{\mathrm{I}} + cz_{\mathrm{I}}$$

After computing h_{J} similarly, we can now test if I and J lie in front of the plane ABC (so that triangle ABC does not obscure PQ) in the following way:

$$h_{\mathrm{I}} > h \text{ and } h_{\mathrm{J}} > h$$

In the above discussion, we considered two distinct points I and J in which, on the screen, PQ intersects edges of triangle ABC. As we have seen, PI and JQ were visible, as far as triangle ABC is concerned, but IJ may be obscured by triangle

ABC. Actually, there may be only one point, I or J, to deal with. If, again on the screen, P lies outside triangle ABC and Q inside it, there is only point I to consider. In this case triangle ABC may obscure part IQ of line segment PQ. If it does, the remaining triangles are only to be applied to PI. Similarly, if, on the screen, P lies inside and Q outside triangle ABC, this triangle may obscure part PJ of PQ, and, if so, the remaining triangles are only to be applied to JQ.

6.2.10 Recursive Calls

If all the above tests fail, the most interesting (and time consuming) case applies: PQ is neither completely visible nor completely hidden. Fortunately, we have just computed the points of intersection I and J, and we know that triangle ABC obscures the segment IJ, while the other two segments, PI and QJ are visible, as far as triangle ABC is concerned. We therefore apply the method *lineSegment* recursively to the latter two segments. Actually, the recursive call for PI applies only to the case that, on the screen, P lies

outside triangle ABC and λ_{min} (see Test 9) is greater than zero. Analogously, the recursive call for QJ applies only if Q lies outside that triangle and λ_{max} is less than 1.

6.2.11 The Arguments of the lineSegment Method

In the *paint* method of the class *CvHLines*, we may be inclined to write the call to the method *lineSegment* in a very simple form, such as

```
lineSegment(g, iP, iQ);
```

where *g* is the graphics context and *iP* and *iQ* are the vertex numbers of the vertices P and Q. However, in the recursive calls just discussed, we have two new points I and J, for which there are no vertex numbers, so that this does not work. On the other hand, omitting the vertex numbers altogether would deprive us of Test 2 in its current efficient form, in which we determine if PQ is one of the edges of triangle ABC. We therefore decide to supply P and Q both as *Point*3*D* objects

(containing the eye coordinates of P and Q) and as vertex numbers if this is possible; if it is not, we use −1 instead of a vertex number. When we recursively call *lineSegment*, the screen coordinates of P and Q are available. If we did not supply these as arguments, it would be necessary to compute them inside *lineSegment* once again. To avoid such superfluous actions, we also supply the screen coordinates of P and Q as arguments as *Point2D* objects. Finally, it would be a waste of time if the recursive

calls would again be applied to all triangles. After all, we know that PI and PJ are not obscured by the triangles that we have already dealt with. We therefore also use the parameter *iStart*, indicating the start position in the array of triangles that is to be used. This explains that the method *lineSegment* has as many as eight parameters, as its heading shows:

```
void lineSegment(Graphics
    Point2D PScr, Point2D Ç
```

The complete method

lineSegment can be found in class *CvHLines*, listed in Appendix D.

6.3 SPECIFICATION AND REPRESENTATION OF 3D OBJECTS

From now on, we will no longer restrict ourselves to cubes, as we did in the previous chapter, but rather accept input files that define objects bounded by polygons (which may contain holes, as we will see in Section 6.4). These input files consist of two parts: a list of vertices, each in the form of a positive vertex number followed by three real numbers, the world coordinates

of that vertex. The second part consists of an input line of the form

`Faces:`

followed by sequences of vertex numbers, each sequence followed by a period (.). Each such sequence denotes a polygon of the object. For each polygon, when viewed from outside the object, the vertex sequence must be counter-clockwise. This orientation must also apply to the first three vertices of each sequence; in other words, the second number

of each sequence must denote a convex vertex. For example, the following input file, say, *letterL.dat*, describes the solid letter *L* of Figure 6.2:

```
1   20   0   0
2   20  50   0
3    0  50   0
4    0   0   0
5   20   0  10
6   20  40  10
7    0  40  10
8    0   0  10
9   20  40  80
10  20  50  80
11   0  50  80
12   0  40  80
Faces:
```

```
1 2 10 9 6  5.
3 4 8  7 12 11.
2 3 11 10.
7 6 9 12.
4 1 5 8.
9 10 11 12.
5 6 7  8.
1 4 3  2.
```

The first line after *Faces* specifies the front face. We might have used a different vertex-number sequence for this face, such as

```
10 9 6 5 1 2.
```

However, the following sequences would be incorrect:

```
2 1 5 6 9 10. (invalid: cl
9 6 5 1 2 10. (invalid: 6
```

Although the sequence

```
3 4 8 7 12 11.
```

seems to be clockwise, it is really counter-clockwise when the face in question is viewed from outside the object, that is, from the back. As we will see in Section 7.1, we use this phenomenon in our programs to detect back faces.

In the first part of the input file, it is not required that the vertex numbers are consecutive and in

ascending order. For example, the following input file (defining a pyramid similar to those in Egypt) is also acceptable. It also shows that the vertex coordinates need not be integers:

```
10   -1.5 -1.5 0
30    1.5 -1.5 0
20    1.5  1.5 0
12   -1.5  1.5 0
5     0    0   3
Faces:
30 20 5.
20 12 5.
12 10 5.
10 30 5.
30 10 12 20.
```

We will use the extension .*dat* for these input files.

6.4 HOLES AND INVISIBLE LINE SEGMENTS

The above way of specifying the boundary faces of objects does not work for polygons that contain holes. For example, consider the solid letter A of Figure 6.13, the front face of which is not a proper polygon because there is a triangular hole in it. The same applies to the (identical) face on the back. Each vertex i of the front face is connected with vertex $i + 10$ of the back face ($1 \leq i \leq 10$).



Figure 6.13: Solid letter A

We can turn the front face into a polygon by introducing a very narrow gap, say, between the

vertices 7 and 10, as shown in Figure 6.14. After doing this, we could try to specify this new polygon as

```
1 2 3 4 5 6 7 10 9 8 10 7.
```

Note that this requires the gap (7, 10) to have width zero, so that there is only one vertex (7) at the top. On the other hand, only a real gap makes it clear that the vertex numbers (10, 9, 8) occur in that order in the above input line: just follow the vertices in Figure 6.14, starting at vertex 1.



Figure 6.14: A polygon

If we really specified the front

face in the above way, the line (7, 10) would be regarded as a polygon edge and therefore appear in our result. This is clearly undesirable. To prevent this from happening, we adopt the convention of writing a minus sign in front of the second vertex of a pair, indicating that this pair denotes a line segment that is not to be drawn. We do this with the ordered pairs (7, 10) and (10, 7) in the above input line, writing (7, −10) and (10, −7), so that we use the following input line instead of the above one:

```
1 2 3 4 5 6 7 -10 9 8 10 -
```

The solid letter A of Figure 6.13 is therefore obtained by using the following input file, in which the extra minus signs occur in the first two lines after the word *Faces*:

```
1      0  -30   0
2      0  -20   0
3      0  -16   8
4      0   16   8
5      0   20   0
6      0   30   0
7      0    0  60
8      0  -12  16
9      0   12  16
10     0    0  40
11   -10  -30   0
12   -10  -20   0
```

```
13 -10 -16   8
14 -10  16   8
15 -10  20   0
16 -10  30   0
17 -10   0 60
18 -10 -12 16
19 -10  12 16
20 -10   0 40
Faces:
1 2 3 4 5 6 7 -10 9 8 10 -
11 17 -20 18 19 20 -17 16
2 12 13 3.
3 13 14 4.
15 5 4 14.
8 9 19 18.
8 18 20 10.
19 9 10 20.
6 16 17 7.
11 1 7 17.
```

```
11 12 2 1.
15 16 6 5.
```

(Note that this use of minus signs applies only to vertex numbers in the second part of an input file. In the first part, minus signs can only occur in coordinate values, where they have their usual meaning.)

Implementing this idea is very simple. For example, because of the minus sign that precedes vertex number 10 in

```
... 7 -10 ...
```

we do not store line segment (7, 10) in the data structure that will be discussed in Section 6.5. In other respects, we simply ignore these minus signs. Therefore the set of triangles resulting from the above complete set of input data (for the solid letter A) is the same as when there had been no minus signs in front of any vertex numbers.

Besides for holes, we can also use these minus signs for the approximation for curved surfaces, as discussed in Section E.5 of Appendix E.

6.5 INDIVIDUAL FACES AND LINE SEGMENTS

Although we usually draw polygons that are boundary faces of solid objects, we sometimes want to draw very thin (finite) planes, here also called *faces*.

Examples are sheets of paper and a cube made of very thin material, of which the top face is removed, as shown in Figure 6.15.



Figure 6.15: A hollow

cube

Since such faces have two visible sides, we specify each face twice: counterclockwise for the side we are currently viewing and clockwise for the side that is currently invisible but may become visible when we change the viewpoint. For example, the front face of the cube of Figure 6.15 is specified twice in the input file:

```
1 2 3 4.
4 3 2 1.
```

Although the user supplies polygons in input files as object

faces, we deal primarily with line segments, referred to as PQ in the previous section. Besides the polygons and the triangles resulting from them, we also store the edges of the polygons as line segments. It is also desirable to be able to draw line segments that are not edges of polygons.

Examples of such ‘loose’, individual line segments are the axes of a 3D coordinate system. Sometimes we want to define the edges of polygons as individual line segments, to prevent such polygons from obscuring other

line segments, displaying objects as wire-frame models. An example of this is shown in Figure 6.16. Here we have a solid pyramid fitting into a cube. Obviously, the pyramid would not be visible if the cube was solid; we therefore prefer the latter to be displayed as a wire-frame model. To provide an input file for this pyramid, we begin by assigning vertex numbers, as shown in Figure 6.17.



Figure 6.16: Solid pyramid in wire-frame
cube



Figure 6.17: Vertex numbers of pyramid and

cube

These vertex numbers occur in the following input file:

```
1  0  0  0
2  2  0  0
3  2  2  0
4  0  2  0
5  0  0  2
6  2  0  2
7  2  2  2
8  0  2  2
9  1  1  2
Faces:
1  4  3  2.
1  2  9.
2  3  9.
3  4  9.
4  1  9.
```

```
1 5.
2 6.
3 7.
4 8.
5 6.
6 7.
7 8.
8 5.
```

After the word *Faces*, we begin with the square bottom face and the four triangular faces of the pyramid. After this, four vertical and four horizontal cube edges follow, each specified by its two endpoints. It follows that the word *Faces* in our input files should not be taken too literally:

this *Faces* section may include pairs of vertex numbers, which are not faces at all but line segments not necessarily belonging to faces.

Since line segments can occur not only as edges of faces but also individually, we have to design and implement a special data structure to store them in our program. This also provides us with the opportunity to store them only once. For example, the edge 3–9 of the pyramid of Figure 6.17 is part of the faces 2-3-9 and 3-4-9, but it would be inefficient to draw it twice. By

using a special data structure for line segments, we can ensure that this edge is stored only once.

Our data structure for line segments will be based on an array of arrays, as shown on the left in Figure 6.18.



Figure 6.18: Internal representation of line segments

An array element *connect*[*i*]

referring to an array containing the integer *j* implies that there is a line segment (*i*, *j*) to be drawn. By requiring that *i* is less than *j*, we ensure that each line segment is stored only once. For example, *connect*[1] refers to the array containing the integers 2, 4, 9 and 5. This indicates that the following line segments start at vertex 1 (each ending at a vertex that has a number higher than 1): 1–2, 1–4, 1–9 and 1–5, which is in accordance with Figure 6.17. The next element, *connect*[2] refers to three vertex numbers, 3, 9 and 6. Although, besides 2–

3, 2–9 and 2–6, there is also a line segment 2-1 (see Figure 6.17), this is not included here because 2 is greater than 1 and this segment has already been stored as line segment 1–2. You may wonder why in Figure 6.18 there are only boxes that give room for at most four vertex numbers. Actually, the sizes of these boxes will always be a multiple of some *chunk size*, here arbitrarily chosen as 4. In other words, if there are five line segments (*i*, *j*) with the same *i* and all with *i* less than *j*, the box size would be increased from 4

to 8 and so on. Since increasing the box size requires memory reallocation and copying, we should not choose the chunk size too small. On the other hand, the larger the chunk size, the more memory will be wasted, since they will normally not be completely filled. To indicate how many vertex numbers are actually stored in each box, we use another array, *nConnect*, as shown in Figure 6.18 on the right. For example, *nConnect*[1]= 4 because *connect*[1] refers to four vertex numbers.

6.6 AUTOMATIC GENERATION OF OBJECT SPECIFICATION

As long as 3D objects do not have too many vertices and the vertex coordinates are easily available, it is not difficult to create 3D specifications as input files by entering all data manually, using a text editor. This is the case, for example, with the solid letter A, discussed in Section 6.4. If there are many vertices, which is normally the case if we approximate curved surfaces, we

had better generate 3D data files by special programs. This section explains how to automatically generate 3D specifications through an example. The generated specification files are accepted by the programs *Painter.java*, *ZBuf.java* (for hidden-face elimination, described in Chapter 7) and *HLines.java* (for hiddenline elimination, described in the next two sections). Most illustrations in this chapter have been obtained by using *HLines.java* for this purpose.

Many 3D objects are bounded by

curved surfaces. We can approximate these by a set of polygons. An example is a hollow cylinder as shown in Figure 6.19 on the right. Both representations of hollow cylinders (or rather, hollow prisms) of Figure 6.19 were obtained by running the program *Cylinder.java*, which we will be discussing, followed by the execution of program *HLines.java*.HP-GL files exported by the latter program were combined by CorelDraw, after which the result was imported into this book. Although the object shown on the left in Figure

6.19 is a (hollow) *prism*, not a cylinder, we will consistently use the term *cylinder* in this discussion.



Figure 6.19: Hollow cylinders with $n = 6$ (left) and $n = 60$ (right)

The user will be able to enter the diameters of both the (outer) cylinder and the (inner) cylindrical

hole. If the latter, smaller diameter is zero, our program will produce a solid cylinder instead of a hollow one. For simplicity, we will ignore this special case, with only half the number of vertices, in our discussion below, but simply implement it in the program.

For some sufficiently large integer *n* (not less than 3), we choose *n* equidistant points on the outer circle (with radius *R*) of the top face, and we choose *n* similar points on the bottom face. Then we approximate the outer cylinder by a prism whose

vertices are these $2n$ points. The inner circle (of the cylindrical hole) has radius r ($< R$). The hollow cylinder has height h. Let us use the z-axis of our coordinate system as the cylinder axis. The cylindrical hole is approximated by rectangles in the same way as the outer cylinder. The bottom face lies in the plane $z = 0$ and the top face in the plane $z = h$. A vertex of the bottom face lies on the positive x-axis. Let us set $h = 1$. Then for given values n, R and r, the object to be drawn and its position are then completely

determined. We shall first deal with the case $n = 6$ and generalize this later for arbitrary n.We number the vertices as shown in Figure 6.20.



Figure 6.20: Vertex numbering

For each vertex i of the top face there is a vertical edge that connects it with vertex *i* + 6. We can specify the top face by the following sequence:

```
1 2 3 4 5 6 -18 17 16 15 1
```

Here the pairs (6, − 18) and (18, − 6) denote an arti.cial edge, as discussed in Section 6.4. The bottom face on the right is viewed here from the positive *z*-axis, but in reality only the other side is visible. The orientation of this bottom face is therefore opposite to what we see in Figure 6.20 on the right, so that

we can specify this face as

```
12  11  10  9  8  7  -19  20  21  2
```

Since $n = 6$, we have $12 = 2n$, $18 = 3n$ and $24 = 4n$, so the above sequences are special cases of

$$1 \quad 2 \ldots n \quad -3n \quad 3n-1 \quad 3n-2 \quad \ldots \quad 2n+1 \quad 3n \quad -n.$$

and

$$2n \quad 2n-1 \quad \ldots \quad n+1 \quad -(3n+1) \quad 3n+2 \quad 3n+3 \quad \ldots \quad 4n$$
$$3n+1 \quad -(n+1).$$

Let us define

$$\delta = \frac{2\pi}{n}$$

Since, in Figure 6.20, on the left,

vertex 6 lies on the positive *x*-axis and according to geometry in Figure 6.21 (outer circle), the Cartesian coordinates of the vertices on the top face are as follows:

$$
\begin{aligned}
x_i &= R\cos i\delta \\
y_i &= R\sin i\delta \qquad (i = 1, \ldots, n;\ \text{outer circle}) \\
z_i &= h \\
x_i &= r\cos(i - 2n)\delta \\
y_i &= r\sin(i - 2n)\delta \qquad (i = 2n + 1, \ldots, 3n;\ \text{inner circle}) \\
z_i &= h
\end{aligned}
$$



Figure 6.21: Calculating vertex coordinates

For the bottom face we have

$$x_i = x_{i-n}$$
$$y_i = y_{i-n} \qquad (i = n+1, \ldots, 2n, 3n+1, \ldots, 4n)$$
$$z_i = 0$$

A program based on the above analysis can be written in any programming language. Using Java for this purpose, we can choose between an old-fashioned, text-line oriented solution and a graphical user interface with, for example, a dialog box with text fields and a button as shown in Figure 6.22.



Figure 6.22: Dialog box for (possibly hollow) cylinder

This dialog box contains a title bar, and seven so-called *components*:three *labels* (that is, static text in the gray area), three text fields in which the user can enter data, and an OK button. Programming the layout of a dialog box in Java can be done in several ways, none of which is particularly simple. Here we do

this by using three *panels*:

- Panel *p*1 at the top, or *North*, for both the label *Number of vertices on outer circle* and a text field in which this number is to be entered.

- Panel *p*2 in the middle, or *Center*, for the label *Diameters D and d (cylinder is hollow if d* > 0*)* and two text fields for these diameters.

- Panel *p*3 at the bottom, or *South*, for the label

Generate 3D object file?
and an OK button.

Since there are only a few components in each panel, we can use the default *FlowLayout* layout manager for the placements of these components in the panels. By contrast, the panels are placed above one another by using *Border-Layout*, as the above words *North*, *Center* and *South*, used in the program as character strings, indicate. As in many other graphics programs in this book, we use two classes in this

program, but this time there is a dialog class instead of a canvas class. Another difference is that we do not display the frame, but restrict the graphical output to the dialog box. (We cannot omit the frame class altogether because the *Dialog* constructor requires a ‘parent frame’ as an argument.) Recall that we previously used calls to *setSize*, *setLocation* and *show* in the constructor of the frame class. We simply omit these calls to prevent the frame from appearing on the screen. Obviously, we must not omit such calls in the

constructor of our dialog class, called *DlgCylinder* in the program. As for the generation of the hollow cylinder itself, as discussed above, this can be found in the method *genCylinder*, which follows this constructor:

```
// Cylinder.java: Generati
//                    (possibl
import java.awt.*;
import java.awt.event.*;
import java.io.*;

public class Cylinder exte
{ public static void main(
  Cylinder(){new DlgCylinc
}
```

```
class DlgCylinder extends
{  TextField tfN = new Tex
   TextField tfOuterDiam =
   TextField tfInnerDiam =
   Button button = new But
   FileWriter fw;

   DlgCylinder(Frame fr)
   { super(fr, "Cylinder (
     addWindowListener(new
     {  public void window
        { dispose();
          System.exit(0);
        }
     });
     Panel p1 = new Panel(
     p1.add(new Label("Num
     p1.add(tfN);
     p2.add(new Label(
```

```
    "Diameters D and d
p2.add(tfOuterDiam);
p3.add(new Label("Gen
p3.add(button);
setLayout(new BorderL
add("North", p1);
add("Center", p2);
add("South", p3);

button.addActionListe
{ public void actionP
  {  int n=0;
     float dOuter=0,
     try
     { n = Integer.va
       dOuter =
          Float.value
       dInner =
          Float.value
```

```
            if (dInner < 0
            if (n < 3 || d
               Toolkit.get
            else
            {  try
               { genCylind
               }
               catch (IOEx
               dispose();
               System.exit
            }
         }
         catch (NumberFor
         { Toolkit.getDef
         }
      }
   });
   Dimension dim = getTo
   setSize(3 * dim.width
```

```
        setLocation(dim.width
        show();
}

void genCylinder(int n, fl
    throws IOException
{   int n2 = 2 * n, n3 = 3
    fw = new FileWriter("Cy
    double delta=2* Math.PI
    for (int i=1; i<=n; i++
    { double alpha=i* delta
          cosa = Math.cos(al
      for (int inner=0; inn
      { double r = (inner =
        if (r > 0)
        for (int bottom=0;
        {   int k = (2 * inn
            // Vertex number
            // Top:      1 (
```

```
            // Bottom: n+1 (
            wi(k); // w = wr
            wr(r * cosa); wr
            wi(1 - bottom);
            fw.write("\r\n")
        }
        }
    }
    fw.write("Faces:\r\n"
    // Top boundary face:
    for (int i=1; i<=n; i
    if (rInner > 0)
    { wi(-n3); // Invisib
      for (int i=n3-1; i>
      wi(n3); wi(-n); //
    }
    fw.write(".\r\n");

// Bottom boundary fac
```

```
for (int i=n2; i>=n+1;
if (rInner > 0)
{ wi(-(n3+1));
  for (int i=n3+2; i<=
  wi(n3+1); wi(-(n+1))
}
fw.write(".\r\n");
// Vertical, rectangul
for (int i=1; i<=n; i+
{ int j = i % n + 1;
  // Outer rectangle:
  wi(j); wi(i); wi(i +
  if (rInner > 0)
  { // Inner rectangle
    wi(i + n2); wi(j +
    fw.write(".\r\n");
  }
}
fw.close();
```

```
}
void wi(int x)
   throws IOException
{  fw.write(" " + String.v
}

void wr(double x)
   throws IOException
{ if (Math.abs(x) < 1e-9)
  fw.write(" " + String.va
    // float instead of dc
  }
}
```

The number 60 entered in the top text field of Figure 6.22 refers to the hollow cylinder shown in Figure 6.19 on the right. The hollow prism shown on the left in

this figure is obtained by replacing 60 with 6. In that case the following file is generated:

```
1 0.75 1.299038 1
7 0.75 1.299038 0
13 0.5 0.8660254 1
19 0.5 0.8660254 0
2 -0.75 1.299038 1
8 -0.75 1.299038 0
14 -0.5 0.8660254 1
20 -0.5 0.8660254 0
3 -1.5 0.0 1
9 -1.5 0.0 0
15 -1.0 0.0 1
21 -1.0 0.0 0
4 -0.75 -1.299038 1
10 -0.75 -1.299038 0
16 -0.5 -0.8660254 1
```

```
22 -0.5 -0.8660254 0
5 0.75 -1.299038 1
11 0.75 -1.299038 0
17 0.5 -0.8660254 1
23 0.5 -0.8660254 0
6 1.5 0.0 1
12 1.5 0.0 0
18 1.0 0.0 1
24 1.0 0.0 0
Faces:
1 2 3 4 5 6 -18 17 16 15 1
12 11 10 9 8 7 -19 20 21 2
2 1 7 8.
13 14 20 19.
3 2 8 9.
14 15 21 20.
4 3 9 10.
15 16 22 21.
5 4 10 11.
```

```
16 17 23 22.
6 5 11 12.
17 18 24 23.
1 6 12 7.
18 13 19 24.
```

Recall that we have already discussed the first two lines that follow the word *Faces*. More interesting examples on generating input files for different 3D objects can be found in Appendix E.

6.7 HIDDEN-LINE ELIMINATION WITH HP-GL OUTPUT

Besides graphics output on the screen, it is sometimes desired to produce output files containing the same results. An easy way to realize this for line drawings is by using the file format known as HP-GL, which stands for Hewlett-Packard Graphics Language. We will use only a very limited number of HP-GL commands:

IN: Initialize

SP: Set pen

PU: Pen up

PD: Pen down

PA: Plot absolute

We think of drawing by moving a pen, which can be either on or above a sheet of paper. These two cases are distinguished by the commands *PD* and *PU*.The *PA* command is followed by a coordinate pair *x*, *y*, each as a four-digit integer in the range 0000–9999. This coordinate pair indicates a point that the pen will move to. The origin (0000, 0000)

lies in the bottom-left corner. For example, the following HP-GL file draws a capital letter *X* in italic, shown in Figure 6.23:



Figure 6.23: Letter X in

italic

```
IN;SP1;
PU;PA5000,2000;PD;PA5000,8
PU;PA3000,2000;PD;PA7000,8
```

This file format is easy to understand and it is accepted by many well-known packages, such as Microsoft Word and CorelDraw. The latter enables us to enhance the drawing after importing the HP-GL file, as was done to add text, resulting in Figure 6.23.

We will see how to implement this in the next section.

The program *HLines.java* is listed in Appendix D. First, *HLines.java* can generate HP-GL files (Figure 6.24 illustrates a menu item for exporting HP-GL files); second, it can display individual lines, and third, printing and photocopying the resulting images can be done in black and white without loss of quality. On the contrary, these line drawings, obtained via HP-GL files and produced by a printer, look better than those on the screen.



Figure 6.24: The Export HP-GL menu item

This example also shows the use of individual line segments, as discussed in Section 6.5. The

solid inside the wire-frame cube is a dodecahedron, which is discussed in greater detail in Section E.1 of Appendix E.

The statement

```
cv.setHPGL(new HPGL(obj));
```

in the class *MenuCommands* (at the end of the file *HLines.java*) creates an object of class *HPGL*, and the variable *hpgl* of the class *CvHLines* is made to refer to it. The fact that *hpgl* is no longer equal to *null* will be interpreted as an indication that an HP-GL file is to be written. The class

HPGL can be found at the end of Appendix D. The *write* method of this class is used in the *drawLine* method of the class *CvHLines*, that is, if the variable *hpgl* is unequal to *null*,as discussed above. After we have written an HP-GL file, we set *hpgl* equal to *null* again (at the end of the *paint* method) to avoid that every call to *paint* should automatically produce HP-GL output. If this is again desired, the user must use the *Export HP-GL* command of the *File* menu once again. The class *CvHLines* is defined in the file *HLines.java* (see Appendix

D).

Figure 6.25 shows that our hidden-line algorithm can correctly render the three beams that we will use to demonstrate the Z-buffer algorithm for hidden-face elimination. As we will see in Section 7.3, the painter's algorithm fails in this case.



Figure 6.25: Three beams

6.8 IMPLEMENTATION

The program *HLines.java* has much in common with *Wireframe.java*, discussed at the end of Chapter 5. We will therefore benefit as much as possible from the code that we have already developed in Section 5.5. Unfortunately, since we now have an extra menu item, *Export HPGL*,inthe *File* menu, we cannot use the existing frame class *Fr3D* directly, but we will use an extended version, that is, a subclass of it. The name of this subclass, *Fr3DH*, occurs in the

main method of the following file:

```
// HLines.java: Perspectiv
// When you compile this p
// following classes shoul
//        CvHLines, Fr3D, F
//        Point3D, Point2D,
import java.awt.*;
import java.awt.event.*;
import java.util.*;

public class HLines extend
{  public static void main
   {  new Fr3DH(args.lengt
         "Hidden-lines alg
   }
}
```

Notice the title *Hidden-lines*

algorithm, which is used here as the third argument of the *Fr3DH* constructor, and consequently appears in the title bar of the window shown in Figure 6.25. The implementation of the hidden-lines algorithm discussed in this chapter can be found in the class *CvHLines*, of which an object is created in the second argument of the above constructor call. In view of the extent of this class, it is not listed here but rather as the file *CvHLines.java* in Appendix D. In this section we will only discuss some other aspects of the

program, especially some classes occurring in the above comment lines, as far as these have not been dealt with in Section 5.5.

The subclass *Fr3DH*, just mentioned, of *Fr3D* is defined in the following file:

```
// Fr3DH.java: Frame class
// This class extends Fr3D
import java.awt.*;
import java.awt.event.*;
import java.util.*;

class Fr3DH extends Fr3D
{  private MenuItem export
   CvHLines cv;
```

```
Fr3DH(String argFileNam
{  super(argFileName, c
   exportHPGL = new Men
   mF.add(exportHPGL);
   exportHPGL.addAction
   this.cv = cv;
}

public void actionPerfc
{  if (ae.getSource() i
   {  MenuItem mi = (Me
      if (mi == exportH
      {  Obj3D obj = cv
      if (obj != null)
      {  cv.setHPGL(new
         cv.repaint();
      }
      else
         Toolkit.getDef
```

```
            }
            else
                super.actionPe
        }
    }
}
```

At the start of the class, the variable *exportHPGL* is declared to implement the additional menu item that we need. The method *actionPerformed* overrides the method with the same name of the super class *Fr3D*. When any menu command is used, a test is executed to see if this command is *Export HPGL*. If this is not the case, the method

actionPerformed of the super class is called to deal with other menu commands. If it is the case, the statement

```
cv.setHPGL(new HPGL(obj));
```

is executed, which makes a variable *hpgl* of the class *CvHlines* point to an *HPGL* object, generated here as an argument of *setHPGL*. By making this variable *hpgl* unequal to *null*, any call of the *CvHLines* method *drawLine* will perform the desired HP-GL output, as you can see in the following lines, copied from Appendix D.

```
private void drawLine(Grap
  float x2, float y2)
{ if (x1 != x2 || y1 != y2
  { g.drawLine(iX(x1), iY(
    if (hpgl != null)
    { hpgl.write("PU;PA" +
      hpgl.write("PD;PA" +
    }
  }
}
```

To clarify both the use of the *HPGL* constructor in the above call of *setHPGL* and this method *drawLine*, we will also have a look at the way the class *HPGL* is defined:

```
// HPGL.java: Class for ex
```

```
import java.io.*;

class HPGL
{  FileWriter fw;
   HPGL(Obj3D obj)
   {  String plotFileName
      for (int i=0; i<fNam
      {  char ch = fName.c
         if (ch == '.') br
         plotFileName += c
      }
      plotFileName += ".pl
      try
      {  fw = new FileWrit
         fw.write("IN;SP1;
      }
      catch (IOException i
   }
  void write(String s)
```

```
    {   try {fw.write(s); fw.
    }
}
```

Apart from the extra code to generate HP-GL output and the obvious greater complexity of the canvas class due to hidden-line elimination, the structure of program *HLines.java* is very similar to *Wireframe.java* discussed at the end of the previous chapter.

EXERCISES

Use a normal editor or text

data file, to be used with pr
for the object consisting of l
square and a vertical line th
shown twice in Figure 6.26.
viewpoint is above the squa
default), while the situation
viewpoint below the square
by using the *Viewpoint Dow*
View menu (or by pressing

6.1



Figure 6.26: Line passin
of a square

Hidden-line elimination work
problem in Exercise 6.1 bec
passes through edges of th
by triangulation of the squar

6.2 horizontal square to a horizo
HLines.java to display the c

vertical line through the triar
not be displayed properly lik
6.26. Explain why and find a

The same as Exercise 6.1 f
shows two very thin square
object is shown twice to de
are four potentially visible fa

6.3



Figure 6.27: Two thin sq

rings

Write a program *HLinesDas*
HLines.java but instead of d
draw them as dashed lines.
applied to the file *letterL.da*
produces the result of Figur
changing the viewpoint). An
this is by letting the method
class *CvHLines- Dashed* fir
PQ as a dashed line, so the
parts of them, will later be d
normally drawn lines if the li
question happen to be visibl
should happen only for calls
the *paint* method, not for re

use a method *dashedLine* s
Exercise 1.5. This call to *da*
followed by a fragment of th

6.4



Figure 6.28: Hidden lines
dashed lines

```
if (hpgl != null)
{  hpgl.write("LT4 1
   ...
   hpgl.write("LT;\n
}
```

where ... denotes two lines
HP-GL output in the method
make dashed lines also app
when the user uses the *Exp*
The two HP-GL commands
switch from normally drawn
back to normal lines.

For each of Exercises 6.5–6
a program that generates a
format discussed in Section
refer to Appendix E for mor

The files generated by your
by not only the program *HL*
programs *Painter.java* and *
in Chapter 7.

Write a program *BookView.*
generate a data file for an o
user to supply the number o
width and height, and the na
as program arguments. For
*bookv*4*.dat* and *bookv*150*.d*
shown in Figure 6.29 were
the following commands:

```
java BookView 4 15 2
java BookView 150 15
```

Apply the program *HLines.j*

6.5 HP-GL files. Import these fi
processor or drawing progr
twice for Figure 6.29.



Figure 6.29: Two open b
sheets: 4 on the left and
right

6.6 Write a program to generat
sphere, as shown in Figure
Enable the user to supply *n*

a program argument.

Write a program to generat
shown in Figure 6.30.

6.7



Figure 6.30: A semi-sph

Generate a great many cub

beside, behind and above e
6.31).

6.8



Figure 6.31: A cube of cubes

Generate a data file for two
torus), as shown in Figure 6

6.9



Figure 6.32: Two tori

Write a program to generat
as shown in Figure 6.33.

6.10



Figure 6.33: A spiral staircase

Answers

6.1

The desired input file is liste

```
1    1-1   0
2    1 1   0
3   -1 1   0
4   -1-1   0
5   0 0    -2
6   0 0    2
Faces:
1 2 3 4.
4 3 2 1.
```

5 6.

Use the vertices 1, 2 and 3
lies inside the triangle. Let v
endpoints as in the above s
6.2 use the invisible lines 1–4, 2
6.14. In other words, define
polygon, specified as a seq
1, 2, 4, 2, 3, 4, and so on, i

See Section 6.4 for holes in
the same structure as the a
faces. Based on Figure F.2,

1 2 3 -7 6 5 8 7 -3 4.

6.3



Figure F.2: One of the fo

6.27

A simple solution to this pro
edges (visible as well as inv
are drawn as solid lines wit
words, every visible edge is

effect of a solid line. Althou
dashed lines, we obtain bet
required for screen output a
and ends with a dash of the
modify the program file *HLi*

1. Disable back-face
   buildLineSet.

```
if (n>2&& pol
```

2. Insert the followin

6.4

```
void dashedLi
        float x
{  float u1 =
      L = (fl
   int n = Ma
   float h1 =
   for (int i
   {  float x
```

```
                x
            drawLin
        }
    }
```

3. Just before the ca
   the program file, i

```
dashedLine(g,
```

A program to generate an c
4and *n* = 150) to produce th
Exercise 6.6 below for the v

```
// BookView.java: Ge
import java.io.*;
```

```
public class BookVie
{  public static voi
      throws IOExcep
   {  if (args.lengt
      {  System.out.
         "Supply nr
         "as program
         System.exit
       }
       int n;
       float w, h;
       FileWriter fw
       n = Integer.v
       w = Float.val
       h = Float.val
       fw = new File
       int spineTop
       float theta =
       float xTop =
```

6.5

```
fw.write(spin
fw.write(spin
for (int i=0;
{  float phi=
      y = w *
      z = w *
   outerTop =
   fw.write(o
      y + " "
   fw.write(o
      y + " "
}
fw.write("Fac
for (int i=0;
{  outerTop =
   fw.write(s
      + outer
   fw.write(s
      + outer
```

```
            }
            fw.close();
        }
    }
```

Before writing the program
mathematical expressions f
discuss how this can be dor
program that generates 3D

The model of a sphere in qu
north pole. Since it is given
horizontal planes between t
latitude, on the sphere. The
vertex (other than the two p
horizontal and a vertical circ
poles. There are $n - 2$ rem

faces is equal to $(n-2)\cdot($
horizontal edges. Altogethe
below, $2(n^2-n+1)$ vertice
5.3. Using a sphere radius
their z-coordinate

$$z = \cos\varphi$$

Writing $\delta = \pi/n$, we will onl
angles:

$$\varphi = i\cdot\delta\ (i = 1,2,\ldots,n-1)$$

6.6

On each of these circles we

$$\theta = j\cdot\delta\ (j = 0,1,\ldots,2n-1)$$

Thus, each pair (i, j) is assc

associating a vertex numbe
with vertex number 2 on circ
vertex number available for
2, and so on. In general, on
each circle there are $2n$ ver

$$\text{number for vertex } (i,j) = (i-1)\cdot 2n + 2 + j$$

As we have seen in Section
computed as $x = \sin\varphi \cos$
upon i and j as shown abov

Finally, we have to assign a
$1 + (n - 1) \cdot 2n$ vertex num

$$1 + (n-1)\cdot 2n + 1 = 2(n^2 - n + 1)$$

which is also the total numb

6.7

Analyze this problem in the
(at the south pole) and eac
and clockwise, since either
Exercise 6.6, we had bette
sphere in this problem, so t
circle that we use, giving al

6.8

Use program arguments for
and *z*. Remember, the wor
specify the vertices of *all* c

Let us start with a torus su
as its center, and let the se
x-axis. We will make the siz
their positions are different.
completely determined by t

must be wide enough for th
≥ 2.

For each vertex of the first
have seen in Section E.3 th
numbers i and $i + n^2$ for ea
torus, we have to shift the f
we turn it through the x-axis

6.9

computations are required f
*Rota*3D of Section 3.9 in thi
corresponding vertex $i + n^2$,

Although, in the first part of
order of the vertex numbers
lines of the following form ir

$$\begin{array}{llll} i & x & y & z \\ i+n^2 & x' & y' & z' \end{array}$$

Similarly, in the second part
in the second face of each
the desired program for two
statements.

If necessary, you might refe
Section 6.6 for the cylindric
that the situation here is sim
Cylinder.java with *rInner* =

6.10 You can use program *Beam*
constructed, or you can use
you also perform a translati
step. As for the railing, reca
segments specified as two
Section 6.5.

Chapter 7: Hidden-Face Elimination

In the previous two chapters we have discussed the wireframe model and how to remove hidden-lines of 3D objects. For example, a realistic looking cube is displayed by simply drawing all the visible edges of the cube. Instead, we can construct a polygon for each of the six faces. If we display only the visible faces, we obtain a more realistic image

of a cube. In Exercise 5.2 this was done by displaying only the top, right and front faces, taking the chosen viewpoint into account. Recall that we used $\theta = 0.3$ and $\varphi = 1.3$ (both in radians) at the beginning of class *Obj* in program *CubePers.java*. The solution of Exercise 5.2 will fail, for example, if we use $\theta = -0.3$ because then the left instead of the right face of the cube (see Figure 5.10) should be displayed as a filled polygon. In this chapter, the viewpoint will be taken care of

automatically, so that the invisible faces of a cube, also known as *back faces*, are omitted regardless of the chosen viewpoint. Besides, a face may be only partly visible, which is the case, for example, if we have two cubes, with the nearer one partly hiding the farther one. The problem of displaying only the visible portions of faces will also be solved in this chapter. Finally, instead of taking just some colors, we will assume that there is a source of light, such as the

sun, to determine the brightness or darkness of a face. Except for Section 7.1, we will display all faces of 3D objects in shades of yellow, against a blue background.

7.1 BACK-FACE CULLING

It is not difficult to determine which faces of a cube are invisible because they are at the back. Such faces, known as *back faces*, can be detected by investigating the orientation of their vertices. To begin with, we specify each face counterclockwise, when viewed from outside the object. For example, we denote the top face of the cube of Figure 5.11 as the counter-clockwise vertex sequence 4, 5, 6, 7, or, for

example, 6, 7, 4, 5, but not 6, 5, 4, 7, for that would be clockwise. In contrast, we can specify the bottom face of the cube as the sequence 0, 3, 2, 1, which is counter-clockwise when this face is viewed from the outside but clockwise in our perspective image. Here we see that the orientation of the bottom face in the image is different from that in 3D space, when the object is viewed from the outside (that is, from below). This is because this bottom face is a back face. We use this principle to tell back faces from visible faces. The

method *area2*, discussed in Section 2.7, will now be very useful, so that we will again use the class *Tools2D*, in which this method occurs. Recall that the complete version of class *Tools2D* can be found in Section 2.13.

Note that we should use screen coordinates in the test we have just been discussing. If we used the x_e-and y_e-coordinates instead (ignoring the z_e- coordinate; see Figure 5.4), this test about the orientation of the vertices would be equivalent to testing whether

the normal vector, perpendicular to the face in question and pointing outward, would point more or less towards us or away from us, that is, whether that vector would have a positive or a negative z_e- component. This test would be correct with orthographic (or parallel) projection but not necessarily with central projection, which we are using. Exercise 7.1 deals with this subject in greater detail.

This time we will use the *Graphics* methods *setColor* and *fillPolygon*, to display each face,

if it is visible, in a color that is unique for that face. Just before we do this (in the *paint* method) we test whether the face we are dealing with is visible; if it is not, it is a back face so that we can ignore it. To demonstrate that this really works, we will modify the viewpoint (by altering the angles θ and φ) each time the user presses a mouse button:

```
// Backface.java: A cube i
// Uses: Point2D (Section
//       Tools2D (Section

import java.awt.*;
import java.awt.event.*;
```

```
public class Backface exte
{  public static void main

   Backface()
   {  super("Press mouse b
      addWindowListener(ne
         {public void winc
      add("Center", new Cv
      Dimension dim = getT
      setSize(dim.width/2,
      setLocation(dim.widt
      show();
   }
}

class CvBackface extends C
{  int centerX, centerY;
   ObjFaces obj = new ObjF
   Color[] color = {Color.
```

```
                              Color.
float dPhi = 0.1F;
CvBackface()
{  addMouseListener(new
   {  public void mouse
      {  obj.theta += 0
         obj.phi += dPh
         if (obj.phi >
         repaint();
      }
   });
}

int iX(float x){return
int iY(float y){return

public void paint(Graph
{   Dimension dim = get
 int maxX = dim.width -
```

```
        minMaxXY = Math.mi
    centerX = maxX/2;
    centerY = maxY/2;
    obj.d = obj.rho * minM
    obj.eyeAndScreen();
    Point2D[] p = new Poin
    for (int j=0; j<6; j++
    {   Polygon pol = new P
        Square sq = obj.f[j
        for (int i=0; i<4;
        {   int vertexNr = s
            p[i] = obj.vScr[
            pol.addPoint(iX(
        }
        g.setColor(color[j]
        if (Tools2D.area2(p
            g.fillPolygon(pc
    }
}
```

```
}

class ObjFaces // Contains
{  float rho, theta=0.3F,
   Point3D[] w;     // Worl
   Point3D[] e;     // Eye
                    // (e =
   Point2D[] vScr; // Scre
   Square[] f;      // The
   float v11, v12, v13, v2
      v32, v33, v43, // El
      xe, ye, ze, objSize;
ObjFaces()
{  w = new Point3D[8];
   e = new Point3D[8];
   vScr = new Point2D[8];
   f = new Square[6];
   // Bottom surface:
   w[0] = new Point3D( 1,
```

```
    w[1] = new Point3D( 1,
    w[2] = new Point3D(-1,
    w[3] = new Point3D(-1,
    // Top surface:
    w[4] = new Point3D( 1,
    w[5] = new Point3D( 1,
    w[6] = new Point3D(-1,
    w[7] = new Point3D(-1,
    f[0] = new Square (0, 1
    f[1] = new Square (1, 2
    f[2] = new Square (2, 3
    f[3] = new Square (3, 0
    f[4] = new Square (4, 5
    f[5] = new Square (0, 3
    objSize = (float)Math.s
       // distance between
    rho = 3 *  objSize; //
}
```

```
void initPersp()
{  float
   costh = (float)Math.cos
   cosph = (float)Math.cos
   v11 = -sinth;      v12 =
   v21 = costh;       v22 =
                      v32 =

}

void eyeAndScreen()
{  initPersp();
   for (int i=0; i<8; i++)
   {  Point3D p = w[i];
      float x = v11 * p.x
      float y = v12 * p.x
      float z = v13 * p.x

         Point3D Pe = e[i]
```

```
            vScr[i] = new Poi
        }
    }
}

class Square
{   int nr[];
    Square(int iA, int iB,
    {   nr = new int[4];
        nr[0] = iA; nr[1] =
    }
}
```

If you do not use the Java *classpath* variable, you should make sure that the files *Point2D.class*, *Point3D.class* and *Tools2D.class* (or the corresponding *.java* files) are in

the same directory as this program. We now obtain images of a cube in bright colors, so the result on the screen looks much better than Figure 7.1. Initially, the top face of the cube is visible, but after we have clicked the mouse button several times the cube shows its bottom face, as is the case in this illustration.



Figure 7.1: Result of back-face culling

We will use back-face culling in the programs that follow. This technique is worthwhile because it drastically reduces the number

of polygons that may be visible and it is inexpensive compared with some more time-consuming algorithms to be discussed later in this chapter. However, using only backface culling is not sufficient, since it does not work for non-convex solids. As Figure 6.12 illustrates, the solid letter *L* is not convex, since the line that connects, for example, vertices 1 and 11 does not lie completely inside the object. In that example, the rectangle 5-6-7-8 is not a back face, but it is only partly visible.

7.2 COLORING INDIVIDUAL FACES

Let us now decide on the color to be used for each polygon (and for all triangles of which it consists) based on its orientation in relation to the light source. For a polygon in a plane with equation

$$ax + by + cz = h,$$

we can obtain a color code by calling the method *colorCode* of the class *Obj3D* as follows:

```
int cCode = obj.colorCode(
```

(Note that we use the name *colorCode* both for an array and for a method.) This color code, stored in the variable *cCode*, will later be used as follows:

```
g.setColor(new Color(cCode
```

Using integers in the range 0–255 for *cCode*, we obtain shades of yellow in this way. For a given polygon, we will associate the values in this range with the inner product (see Section 2.2) between the following two vectors:

vector directed

s = $(1/\sqrt{3})(-1, 1, 1)$:	from the object to the sun; normal vector, perpendicular to
n = (a, b, c):	the polygon and pointing away from the object (more or less towards the viewpoint E).

Note that these vectors have length 1 and are expressed in eye coordinates x_e, y_e and z_e. The signs of the triple elements $-1, 1, 1$ imply that the light comes from the left, from above and from the front, as Figure 7.2

illustrates.



Figure 7.2: Vector s, pointing to the sun, and normal vector n of a face

Since we know the range of the color codes, we can convert

inner-product values to color codes, if we also know the range of all possible inner products that can occur. This range

$$inprodRange = inprodMax - inprodMin$$

is found in the method *planeCoeff* of the class *Obj3D* simply by computing all those inner products, as soon as *a*, *b* and *c* are computed.

The following method of *Obj3D.java* shows how an inner product **n** · **s**, discussed above, is computed and how the above values *inprodMin* and *inpro-*

dRange are used to derive a color code in the range 0–255:

```
int colorCode(double a, dc
{  double inprod = a * sun
   return (int)Math.round(
}
```

The method *colorCode* needs to be called for every polygon, or face, to be colored. It is usually placed in the method *paint*, along with its color code and its distance, as demonstrated in the example program of the next section.

7.3 PAINTER'S ALGORITHM

It is an attractive idea to solve the hidden-face problem by displaying all polygons in a specific order, namely first the most distant one, then the second furthest, and so on, finishing with the one that is closest to the viewpoint. Painters sometimes follow the same principle, particularly when working with oil paintings. They typically start with the background and paint a new layer for objects on the

foreground later, so that the overlapped parts of objects in the background, painted previously, are covered by the current layer and thus become invisible. This algorithm is therefore known as the *painter's algorithm*. It is based on the assumption that each triangle can be assigned a z_e-coordinate, which we can use to sort all triangles. One way of obtaining such a z_e-coordinate for a triangle ABC is by computing the average of the three z_e-coordinates of A, B and C. However, there is a problem, which is clarified by Figure 7.3.

For each of the three beams, a large rectangle is partly obscured by another, so we cannot satisfactorily place them (or the triangles in which these rectangles are divided) in the desired order, that is, from back to front (see also Figures 7.8 and 7.9). Consequently, the naïve approach just suggested will fail in this case. Surprisingly enough, it gives good results in many other cases, such as the solid letter *L* in Figure 6.2 and the sphere and cone in Figure 7.5. It is also very fast.



Figure 7.3: Beams, each of which partly obscures

another



Figure 7.4: Program *Painter.java* applied to file *letterL.dat*



Figure 7.5: Sphere and cone

The program *Painter.java* is listed below. If you compile and run this program, all classes defined in the program files

Point2D.java, Point3D.java, Obj3D.java, etc., must be available, as the comment below indicates. Recall our discussion of this subject at the end of Chapter 1.

```
// Painter.java: Perspecti
//    vertices and faces.
// Uses: Fr3D (Section 5.5
//       Point2D (Section
//       Obj3D, Polygon3D,
import java.awt.*;

public class Painter exten
{ public static void main(
  {  new Fr3D(args.length>
       "Painter");
  }
```

```
}
```

In the above *Fr3D* constructor call, the first argument is a conditional expression to check if the user has used the option of specifying an input file as a program argument in the command line. (This is not required, since the user can also use the *File* menu to open input files). Recall that this is similar to what we did in Sections 5.6 and 6.8. The second argument of the constructor call just mentioned creates an object of class *CvPainter*, which is listed below in the separate file

CvPainter.java. The third argument specifies the window title *Painter* that will appear.

```
// CvPainter.java: Used in
import java.awt.*;
import java.util.*;

class CvPainter extends Ca
{  private int maxX, maxY,
   private Obj3D obj;
   private Point2D imgCent

   Obj3D getObj(){return c
   void setObj(Obj3D obj){
   int iX(float x){return
   int iY(float y){return

   void sort(Tria[] tr, in
```

```
    {   int i = l, j = r,  w
        float x = zTr[(i + j
        Tria wTria;
        do
        {   while (zTr[i] < x
            while (zTr[j] > x
            if (i < j)
            {   w = zTr[i]; zT
                wTria = tr[i];
                wInt = colorCo
                colorCode[j] =
                i++; j--;
            } else
        if (i == j) {i++; j-
    } while (i <= j);
    if (l < j) sort(tr, col
    if (i < r) sort(tr, col
}
```

```
public void paint(Graphics
{   if (obj == null) return
    Vector polyList = obj.g
    if (polyList == null) r
    int nFaces = polyList.s
    if (nFaces == 0) return

    Dimension dim = getSize
    maxX = dim.width - 1; m
    centerX = maxX/2; cente
    // ze-axis towards eye,
    // object points are al
    // obj is a java object
    // - Vector w          (wc
    // - Array e           (ey
    // - Array vScr        (sc
    // - Vector polyList (P

    // Every Polygon3D valu
```

```
// - Array 'nrs' for ve
// - Values a, b, c, h
// - Array t (with nrs.

// Every Tria value con
// numbers iA, iB and i
obj.eyeAndScreen(dim);
      // Computation of

imgCenter = obj.getImgC
obj.planeCoeff();    //

// Construct an array c
// each polygon and cou
// of triangles:
int nTria = 0;
for (int j=0; j<nFaces;
{   Polygon3D pol = (Pc
      if (pol.getNrs().
```

```
            continue;
         pol.triangulate(c
         nTria += pol.getT
      }
      Tria[] tr = new Tria
      int[] colorCode = ne
      float[] zTr = new fl
      int iTria = 0;
      Point3D[] e = obj.ge
      Point2D[] vScr = obj

      for (int j=0; j<nFac
      {  Polygon3D pol = (
         if (pol.getNrs().
         int cCode =
            obj.colorCode(
         Tria[] t = pol.ge
         for (int i=0; i<
         {  Tria tri = t[i
```

```
            tr[iTria] = tr
            colorCode[iTri
            float zA = e[t
                zC = e[tri.
            zTr[iTria++] =
        }
    }

    sort(tr, colorCode,

    for (iTria=0; iTria<
    {  Tria tri = tr[iTr
        Point2D a = vScr[
                b = vScr[
                c = vScr[
        int cCode = color
        g.setColor(new Cc
        int[] x = {iX(a.x
        int[] y = {iY(a.y
```

```
                g.fillPolygon(x,
            }
        }
    }
```

We use a special method, *sort*, to sort the triangles; it is based on the well-known and efficient quicksort algorithm, discussed in detail in Ammeraal (1996). Before calling *sort*, we build three arrays:

Open table as spreadsheet

Array element	Type	Conta
tr[*iTria*]	*Tria*	the th vertex

		numbe the tri
colorCode[*iTria*]	*int*	value betwe and 2
zTr[*iTria*]	*float*	value repres z_e- coord of tria

For a given subscript value *iTria*, the three array elements in the first column of this table belong to the same triangle. We may regard them as members of the

same record, of which *zTr* is the key. During sorting, whenever two elements *zTr*[*i*]and *zTr*[*j*] are swapped, we swap *tr*[*i*]and *tr*[*j*] as well as *colorCode*[*i*] and *colorCode*[*j*] at the same time. It seems reasonable to use the average of the three z_e-coordinates of a triangle's vertices as the z_e-coordinate of that triangle, but we may as well simply use the sum instead of the average. Recall that the positive z_e-axis points towards us, so that all z_e values that we use are negative: the more negative it is, the further away the triangle is. It

follows that we have to paint the triangles in increasing order of their z_e-coordinates, or, equivalently, in decreasing order of their absolute values.

As the class *CvPainter* in the program *Painter.java* shows, there is a call to *colorCode* in the method *paint* for every polygon just before entering the loop. Within the loop, all the triangles of that polygon, their color code, and each triangle's distance, are stored in the three arrays *tr*, *colorCode* and *zTr*, discussed above. After this has been done

for all polygons, the triangles are sorted on the basis of their distances stored in *zTr*, and then displayed in order of decreasing distance.

Next, we demonstrate the application of the painter's algorithm to some simple 3D objects, with the implementation of user operations. As Figure 7.4 shows, we will enable the user to change the viewpoint E, characterized by its spherical coordinates. Immediately after an input file has been opened, these coordinates have the following (default) values:

$\rho = 3 \times$ the distance between two opposite vertices of a box in which the objects fits

$\theta = 0.3$ radians ($\approx 17^\circ$)

$\varphi = 1.3$ radians ($\approx 74^\circ$)

If the user gives the menu command *Viewpoint Down* the value of φ is increased by 0.1 radians (≈6°). Similarly, *Viewpoint Up* decreases φ by 0.1 radians, while *Viewpoint Left* and *Viewpoint Right* decrease and increase θ by 0.1 radians, respectively. The same effects can be achieved by using one of the four arrow keys, ↓, ↑, ← and →, together with the Ctrl-key, as indicated in the menu. Figure 7.4

shows the screen when the input file *letterL.dat*, discussed in Section 6.3, has been read by program *Painter.java* and the user has used the *Viewpoint Up* command four times, so that we view the object from a higher viewpoint than in the initial situation.

The *File* menu, not shown in Figure 7.4, consists of the following commands:

```
Open    Ctrl+O
Exit    Ctrl+Q
```

If several input files are available, the user can switch to another

object by using the *Open* command (or Ctrl+O), as usual. The simplicity of our file format makes it easy to generate such files by other programs, as we will discuss in the next two sections. In particular, mathematically well-defined solids, such as the sphere and the cone of Figure 7.5, are very suitable for this. Incidentally, this example demonstrates that what we call a ‘three-dimensional object’ may consist of several solids. Note, however, that the input-file format requires that all vertices, in this example of both

the sphere and the cone, must be defined in the first part of the file and all faces in the second. In other words, the line with the word *Faces* must occur only once in the file. This example also shows that curved surfaces can be approximated by a great many flat faces. In this example, there are altogether 1804 vertices and 1920 faces. Here the command *Viewpoint Down* has been used four times and the command *Viewpoint Right* twice.

An object will normally appear with a reasonable perspective effect, but the user will be able to

increase or decrease the viewing distance by using menu commands or their shortcuts, Ctrl+Insert and Ctrl+Delete, as Figure 7.4 shows.

Although we can see only shades of gray in Figures 7.4 and 7.5, the situation looks much more interesting on the screen: the background is light blue like the sky and all faces of the object are yellow. The source of light is far away, at the top left, so that the upper and the left faces are bright yellow, while those on the right and on the bottom are much darker.

To start the program, we can supply the (initial) input file as a program argument, if we like. For example, if the first 3D object to be displayed is given by the file *letterL.dat*, we can start the program by entering

```
java Painter letterL.dat
```

Alternatively, we can enter

```
java Painter
```

and use the *Open* command in the *File* menu (or Ctrl+O) to specify the input file *letterL.dat*. With both ways of starting the program, we can switch to

another object by using this *Open* command.

As discussed at the beginning of this section, the painter's algorithm will fail in some cases, such as the three beams of Figure 7.3. We will therefore discuss another algorithm for hidden-face elimination in the next section.

7.4 Z-BUFFER ALGORITHM

If the images of two faces F_1 and F_2 overlap, we may consider two questions with regard to the correct representation of these faces:

1. Which pixels would be used for both F_1 and F_2 if each face were completely visible?

2. For each of these pixels, which of the corresponding points in

F_1 and F_2 is nearer?

The Z-buffer algorithm deals with these questions in a general and elegant way. Recall that we are using an eye-coordinate system, with *z*-coordinates denoting the distance we are interested in. We consider points P in 3D space and their corresponding projections P′ in 2D space, where we use central projection with the viewpoint E as the center of projection. In other words, each line PE is a ray of light, intersecting the screen in P ′. We are especially interested in

such points P′ that are the centers of pixels.

The Z-buffer algorithm is based on a large two-dimensional array in which we store numbers that represent *z*-coordinates. Using the variable *dim* as the current canvas dimension, we define the following array, also known as a *Z-buffer*,for this purpose:

```
private float buf[][];
buf = new float[dim.width]
```

We initialize array *buf* with values corresponding to points that are very far away. As before, we ignore back faces. For each of

the remaining faces we compute all pixels and the *z*-values that correspond with these. For each pixel P′(*ix*, *iy*), we test whether the corresponding point P in 3D space is nearer than *buf* [*ix*][*iy*] indicates. If it is, we put this pixel on the screen, using the color for the face in question, computed as in the previous section, while, at the same time, updating *buf* [*ix*][*iy*]:

```
For each face F (and i
  For each pixel P'(ix
    If P is nearer tha
    {    set pixel P'
         update buf [i
```

}

In this discussion, the words *distance* and *near* refer to the *z*-coordinates in the eye-coordinate system. (Since we use no other 3D coordinates here, we simply write *z* instead of z_e here.) There are two aspects that make the implementation of the above algorithm a bit tricky:

1. Since the *z*-axis points towards us, the larger *z* is, the shorter the distance.

2. It is necessary to use

1/z instead of z for linear interpolation.

Let us take a look at this rather surprising point 2. Suppose we are given the z_e-coordinates of two points A and B in 3D space and the central projections A′ and B′ of these points on the screen. Besides, some point P′ on the screen, lying on A′B′, is given and we have

$$x_{P'} = x_{A'} + \lambda(x_{B'} - x_{A'})$$

$$y_{P'} = y_{A'} + \lambda(y_{B'} - y_{A'})$$

where x_P', and so on, are screen coordinates. We are then interested in the point P (in 3D space) of which P′ is the central projection. Since we want to know how far away P is, our goal is to compute z_P. (After this, we can also compute the 3D coordinates $x_P = -x_P' z_P/d$ and $y_P = -y_P' z_P/d$, using Equations (5.7) and (5.8) of Section 5.3, where we wrote X and Y instead of x' and y'.) Curiously enough, to compute this eye coordinate z_P by interpolation, we need to use the inverse values of the z-

coordinates:

$$\frac{1}{z_P} = \frac{1}{z_A} + \lambda\left(\frac{1}{z_B} - \frac{1}{z_A}\right)$$

We will simply use this result here; it is discussed in more detail in Appendix A. Let us write

$$z_{Pi} = \frac{1}{z_P}$$

which we write as *zPi* (equal to 1/*zP*) in the program. Using the same convention (z_{Ai} = 1/*zA*, etc.) for other variables and writing *xA*, *yA* etc. for screen coordinates, we compute the

centroid D(x_D, y_D) along with its inverse z-value z_{Di} for each triangle ABC as follows:

```
xD = (xA + xB + xC)/3;
yD = (yA + yB + yC)/3;
zDi = (zAi + zBi + zCi)/3;
```

This centroid will be the basis for computing z_i-values for other points of the triangle by linear interpolation. To do this, we are interested in how much z_{Pi} increases if P moves one pixel to the right. This quantity, which we may write as $\partial z_i/\partial x$ or simply as *dzdx* in the program, is constant for the whole triangle.

We will use this value, as well as its counterpart $dzdy = \partial z_i/\partial y$ indicating how much z_{Pi} increases if P moves one pixel upward, that is, if the screen coordinate y_P is increased by 1. It is useful to think of the triples x, y and z_i (where x and y are screen coordinates and $z_i = 1/z$) as points in a plane of an imaginary 3D space. We can then denote this plane as

$$ax + by + cz_i = k \qquad (7.1)$$

Writing this in the form $z_i = (k - ax - by)/c$ and applying partial

differentiation to z_i, we obtain

$$\frac{\partial z_i}{\partial x} = -\frac{a}{c} \tag{7.2}$$

$$\frac{\partial z_i}{\partial y} = -\frac{b}{c} \tag{7.3}$$

To find *a*, *b* and *c*, remember that (*a*, *b*, *c*) in Equation (7.1) is the normal vector of the plane of triangle ABC (in the imaginary space we are dealing with). We define the vectors

$$\mathbf{u} = \mathbf{AB} = (u_1, u_2, u_3)$$

$$\mathbf{v} = \mathbf{AC} = (v_1, v_2, v_3)$$

where

$$u_1 = x_B - x_A \qquad v_1 = x_C - x_A$$

$$u_2 = y_B - y_A \qquad v_2 = y_C - y_A$$

$$u_3 = z_{Bi} - z_{Ai} \qquad v_3 = z_{Ci} - z_{Ai}$$

Then the vector product

$$\mathbf{u} \times \mathbf{v} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \end{vmatrix}$$

(see Section 2.4) is also perpendicular to triangle ABC, so that we can compute the desired values *a*, *b* and *c* of (7.1), (7.2) and (7.3) as the coefficients of **i**,**j**

and **k**, respectively, finding

$$a = u_2 v_3 - u_3 v_2$$

$$b = u_3 v_1 - u_1 v_3$$

$$c = u_1 v_2 - u_2 v_1$$

So much for the computation of $dzdx = \partial z_i / \partial x$ and $dzdy = \partial z_i / \partial y$, which we will use to compute z_{Pi} for each point P of triangle ABC, as we will see below.

To prepare for traversing all relevant *scan lines* for triangle ABC, such as LR in Figure 7.6, we compute the *y*-coordinates

yTop and *yBottom* of the vertices at the top and the bottom of this triangle. For all pixels that comprise triangle ABC on the screen, we have to compute the *z*-coordinate of the corresponding point in 3D space. In view of the enormous number of those pixels, we should do this as efficiently as possible. Working from the bottom of the triangle to the top, when dealing with a scan line, we traverse all its pixels from left to right. Figure 7.6 shows a situation in which all pixels of triangle ABC below the scan line LR have already been

dealt with.



Figure 7.6: Triangle ABC and scan line LR

For each scan line at level *y*

($yBottom \leq y \leq yTop$), we find the points of intersection L and R with triangle ABC as follows. We introduce the points I, J and K, which are associated with the triangle edges BC, CA and AB, respectively. Initially, we set the program variables *xI*, *xJ* and *xK* to 10^{30}, and *xI*1, *xJ*1 and *xK*1 to -10^{30}. Then, if *y* lies between *yB* and *yC* or is equal to one of these values, we compute the point of intersection of the scan line with BC, and we assign the *x*-coordinate of this point to both *xI* and *xI*1. In the same way we possibly update *xJ*, *xJ* 1 for C A

and *xK* and *xK*1 for AB. After this, each of the variables *xI*, *xJ* and *xK* is equal either to its original value 10^{30} or to the *x*-coordinate of the scan line in question with BC, CA and AB, respectively. The same applies to the other three variables, except that these may still have a different original value, -10^{30}. We can now easily find *xL* and *xR*:

$$xL = \min(xI, xJ, xK)$$
$$xR = \max(xI1, xJ1, xK1)$$

So far, we have been using floating-point, logical coordinates

y, *xL* and *xR*. Since we have to deal with pixels, we convert these to the (integer) device coordinates *iY*, *iXL* and *iXR* as follows:

```
int iy = iY(y), iXL = iX(x
```

By adding 0.5 to *xL* and subtracting 0.5 from *xR*, we avoid clashes between neighboring triangles of different colors: the pixel (*iXR*, *y*) belonging to triangle ABC should preferably not also occur as a pixel (*iXL*, *y*) of the right-hand neighbor of this triangle, because it would then not be clear which

color to use for this pixel. Before entering the loop for all pixels *iXL*, *iXL* + 1, …, *iXR* for the scan line on level *y*, we compute the inverse *z* value *zi* = z_{Li} for the pixel (*iXL*, *y*). Theoretically, this value is

$$z_{\mathrm{Li}} = z_{\mathrm{Di}} + (y - y_{\mathrm{D}})\frac{\partial z}{\partial y} + (x_{\mathrm{L}} - x_{\mathrm{D}})\frac{\partial z}{\partial x}$$

In the program we modify this a little, giving a little more weight to the centroid D of the triangle:

```
double zi = 1.01 * zDi + (
```

This modification is useful in some special cases of which we

will give an example at the end of this section.

Starting at the left end (*iXL*, *y*) of a scan line with the above *z* value $zi = z^{Li}$,we could now write the loop for this scan line as follows:

```
for (int x=iXL; x<=iXR; x+
{   if (zi < buf[x][iy]) //
    {   g.drawLine(x, iy, x,
        buf[x][iy] = (float)
    }
    zi += dzdx;
}
```

Along a horizontal line LR, shown in Figure 7.6, we compute the inverse *z*- coordinate, *zi*. If this is

less than the contents of the array element *buf* [*x*][*y*], we put a pixel on the screen and update that array element.

The above test *zi* < *buf*[*x*][*y*] may at first look confusing. Since the positive *z*-axis of the eye-coordinate system points towards us, we have:

- the *larger* the *z*-coordinate of a point, the nearer this point is to the eye.

However, we are using inverse values *zi* = 1/*z*, so that the above

is equivalent to

- the *smaller* the *zi*-value of a point, the nearer it is to the eye.

A complicating factor is that we are using negative *z*-coordinates, but the above also applies to negative numbers. The following example for two points P and Q will make the situation clear:

P nearby		Q far away
$z_P = -10$	$>$	$z_Q = -20$
$zi_P = 1/z_P = -0.1$	$<$	$zi_Q = 1/z_Q = -0.05$

Another curious aspect of the above fragment is that putting a

pixel on the screen is done here by drawing a line of only one pixel. It is strange that Java does not supply a more elementary routine, say, *putPixel*, for this purpose. However, we can do much better by delaying this '*putPixel*' operation until we know for how many adjacent pixels it is to be used; in other words, we build horizontal line segments in memory, storing their leftmost *x* values and displaying these segments if we can no longer extend it on the right. This implies that even if there were a *putPixel* method, we would not use it, but

rather draw horizontal line segments, consisting of some pixels we have recently been dealing with. Instead of the above for-loop we will actually use an ‘optimized’ fragment which is equivalent to it, as we will discuss in a moment. The program *ZBuf.java* is listed below.

```
// ZBuf.java: Perspective
//     lists vertices and f
//     Z-buffer algorithm u
// Uses: Point2D (Section
//       Obj3D, Polygon3D,
import java.awt.*;

public class ZBuf extends
```

```
{  public static void main
   {  new Fr3D(args.length
         "ZBuf");
   }
}
```

The class *CvZBuf* is defined in the following separate file:

```
// CvZBuf.java: Canvas cla
import java.awt.*;
import java.util.*;

class CvZBuf extends Canva
{  private int maxX, maxY,
   private float buf[][];
   private Obj3D obj;
   private Point2D imgCent

   int iX(float x){return
```

```
int iY(float y){return

Obj3D getObj(){return c
void setObj(Obj3D obj){

public void paint(Graph
{  if (obj == null) ret
   Vector polyList = ob
   if (polyList == null
   int nFaces = polyLis
   if (nFaces == 0) ret
   float xe, ye, ze;

   Dimension dim = getS
   maxX = dim.width - 1
   centerX = maxX/2; ce
   // ze-axis towards e
   // object points are
   // coordinates x and
```

```
        // the z-direction,
        // of z. With negati
        // a small value of
        // fore begin with l
        if (maxX != maxX0 ||
        {  buf = new float[d
           maxX0 = maxX; max
        }
        for (int iy=0; iy<di
           for (int ix=0; ix

        obj.eyeAndScreen(dim
        imgCenter = obj.getI
        obj.planeCoeff(); //
        Point3D[] e = obj.ge
        Point2D[] vScr = obj

        for (int j=0; j<nFac
{   Polygon3D pol = (Polygc
```

```
if (pol.getNrs().length
   continue;
int cCode =
    obj.colorCode(pol.g
g.setColor(new Color(cC

pol.triangulate(obj);

Tria[] t = pol.getT();
for (int i=0; i<t.lengt
{  Tria tri = t[i];
   int iA = tri.iA, iB
   Point2D a = vScr[iA]
   double zAi = 1/e[tri
       zCi = 1/e[tri.iC
   // We now compute th
   // (written here as
   // of the imaginary
   // where zi is 1/z (
```

```
// eye coordinates.
// the partial deriv
double u1 = b.x - a.
       u2 = b.y - a.
       cc=u1*v2-u2*v
if (cc <= 0) continu
double xA = a.x, yA
       xB = b.x, yB
       xC = c.x, yC
       xD = (xA + xB
       yD = (yA + yB
       zDi = (zAi +
       u3 = zBi - zA
       aa=u2*v3-u3*v
       bb=u3*v1-u1*v
       dzdx = -aa/cc
       yBottomR = Ma
       yTopR = Math.
int yBottom = (int)M
```

```
            yTop = (int)M

        for (int y=yBottom;
        {  // Compute horizc
           // for coordinate
           double xI, xJ, xK
           xI = xJ = xK = 1e
           xI1 = xJ1 = xK1 =
           if((y-yB)*(y-yC)<
             xI = xI1 = xC +
           if((y-yC)*(y-yA)<
             xJ = xJ1 = xA +
           if((y-yA)*(y-yB)<
             xK = xK1 = xB +
           // xL = xR = xI;
           xL = Math.min(xI,
           xR = Math.max(xI1
           int iy = iY((floa
              iXR = iX((floa
```

```
        double zi = 1.01

    /*
        for (int x=iXL; x
        {  if (zi < buf[x
           {  g.drawLine(
              buf[x][iy]
           }
           zi += dzdx;
        }
    /*
//  The above comment
//  ---
        boolean leftmostV
        int xLeftmost = 0
        for (int ix=iXL;
        {  if (zi < buf[i
           {  if (!leftmc
              {  xLeftmos
```

```
                    leftmost
                }
                buf[ix][iy]
            }
            else
            if (leftmostVa
            {   g.drawLine(
                leftmostVal
            }
                zi += dzdx;
            }
            if (leftmostVa
                g.drawLine(
        // ---
            }
        }
    }
}
```

Almost at the end of this program, the fragment between the two lines // - is a more efficient version than the for-loop in the comment that precedes it. In that for-loop, each line LR is drawn pixel by pixel. In the more efficient version that follows, however, the line LR is drawn by one or more line segments depending on how much the line LR is blocked by the triangles that are nearer. In the best case, where no triangle is in front of the line, the line is drawn by a simple call to the *drawLine* method. Scanning through each horizontal

line from left to right, we use a Boolean variable *leftmostValid* to record if we have found a leftmost point that is not blocked by any other triangle. If so, we keep scanning and updating the Z-buffer until we encounter the first point that is further away than the corresponding Z-buffer value, such as *I* in Figure 7.7. We then draw the line up to the point just before that blocked point (*I*). We meanwhile set *leftmostValid* to false, entering the line segment, such as *IJ* in Figure 7.7. Continuing scanning through until the first visible point, such as

J, is found, we record *J* as the new leftmost point and set *leftmostValid* to true. This process continues to reach R, and the last line segment, such as *JR*, is drawn if it is not blocked.



Figure 7.7: Illustration of more efficient version

Figure 7.8 demonstrates that the Z-buffer algorithm can also be used in cases in which the

painter's algorithm fails. The latter is illustrated by Figure 7.9. (We have also seen these three beams in Figures 6.25 and 7.3.)



Figure 7.8: Z-buffer algorithm

applied to three beams



Figure 7.9: Painter's algorithm failing

In Appendix E (Section E.5) we will develop a program that enables us to display the surfaces of functions of two variables. Files generated by this program are also accepted by the program *ZBuf.java*, as Figure 7.10 demonstrates.



Figure 7.10: Function of two variables

Here we are using faces with two sides, as discussed in Section 6.5. The way these are used here requires a correction in the

computation of *zi*. Recall that we have introduced the factor 1.01 in the following statement:

```
double zi = 1.01 * zDi + (
```

Without this factor, some incorrect dark pixels would appear on the boundary, also referred to as the *silhouette*, of the (yellow) object and the (light blue) background. To understand this, we note that in Figure 7.11 point P lies on the boundary of the triangles T_1 and T_2.



Figure 7.11: Point P belonging to triangles of very different colors

The nearer triangle, T_1, is visible and its color is bright yellow because it lies on the upper side of the surface. Triangle T_2 lies on the lower side and would appear almost black on the screen if it were not obscured by T_1. Point

P, belonging to both triangles, is used twice to determine the color of the corresponding pixel on the basis of the *zi* value of P. In both cases, this value is the same or almost the same, so that it is not clear which color will be used for this pixel. To solve this problem, we use the factor 1.01 instead of 1 in the above computation of *zi*. Because of this, the *zi* value for P when taken as a point of T_1 will now be slightly less than when P is regarded as a point of T_2. As a result, the light yellow color will be used for the pixel in question.

EXERCISES

The problem of back-face culling cannot generally be solved by testing whether the z_e-component of the normal vector of a face in question is positive or negative. Recall that we are using the equation

$$ax + by + cz = b$$

for the plane of each face, in which **n** = (*a*, *b*, *c*) is the normal vector of that face,

pointing outward. Using also the vector $\mathbf{x} = (x, y, z)$, we can write the above equation as

$$\mathbf{n} \cdot \mathbf{x} = h$$

Figure 7.12 shows the geometrical interpretation of **n**, **x** and *h*. For a visible face, the inner product *h* is negative because **n** and **x** point in opposite directions. By contrast, *h* is positive for a back face.



Figure 7.12: Geometrical interpretation of x, n and *h*, where *h* is negative

Although in most cases *c*, the

third component of the vecto
n, is positive for a visible face and negative for a back face, there are situations in which this is not true. Give a
example of such a situation, with a detailed explanation. How does back-face culling based on the signs of *h* and (incorrectly) of *c* relate to that based on the orientation of point sequences?

7.2 Apply animation with double buffering to a cube, as in Exercise 5.4, but use colore
faces.

Apply animation to two colored cubes (see Exercises 5.5 and 7.2), but use colored faces. Even if they partly hide each other, this problem can be solved by back-face culling, provided the farther cube is drawn before the nearer one This is demonstrated in Figure 7.13; here the *Graphics* methods *fillPolygon* and *drawPolygon* are applied to each visible face. By drawing the edges of such faces in black, we make sure that we can

7.3 clearly distinguish the colored faces if shades of gray are used in black-and-white reproductions, such as Figure 7.13.



Figure 7.13: Two rotating cubes, generated by back-face

culling

7.4 In the program file *Obj3D.java*, the direction of the light vector (*sunX*, *sunY*, *sunZ*) pointing to the source of light was arbitrarily chosen. Even without moving the object (by rotating it, for example), we can obtain an exciting effect by using animation to change this vector, so that the source of light rotates. Extend the program *Painter.java* to realize this. An easy way of

doing this is by using spherical coordinates *sunTheta* and *sunPhi* and radius 1 for a light vector of unit length, similar to the spherical coordinates θ, φ and ρ, shown in Figure 5.1, and increasing, say, *sunTheta* by 0.02 radians every 50 ms.

Write a 3D data file (using a text editor) for the steps shown in Figure 7.14. Apply the programs *Painter.java* and *ZBuf.java* to it. Can you

write a program to generate such data files? In such a program, the number of steps and the dimensions should preferably be variables.

7.5



Figure 7.14:
Steps

Answers

In Figure F.3, the two outer fa
but the corresponding inner fa
and 19 indicate. The latter fa
invisible if we view the object
shows.



Figure F.3: Object nearby
visible



Figure F.4: The same obje
invisible

7.1 Recall that, with eye coordina
the *y*-axis upwards and the *z*
inner face that is visible in Fig
Figure F.4. Estimating the no
value *h*, as specified in the ex

for this face, we find:

a is almost equal to -
the negative *x*-axis;

b is almost zero, but
slightly from above;

c is almost zero, but
the back.

These values, and in particula
distance. By contrast, the inr
vector from the viewpoint E t
depends on the viewing dista
drawing a sketch similar to F
example. As a result, you wil
but positive in Figure F.4. Thi
determine if a face is a back

not that of *c*. The correct pra
equivalent to back-face cullin
points: if this orientation on th
object is viewed from outside
of *h* would be equivalent to u
instead of the screen coordir
image points. This would wo
may result in wrongly decidin
if the object is viewed from n
Recall that we also briefly dis

7.2 We can use back-face culling
are visible. Refer to the solut
implementation of animation

In the previous exercise we c
rotation about a vertical axis

7.3

the cube unchanged. This is
now want to use two rotatior
rotating each cube about one
rotation speeds, the latter sir
angles in each step. As in the
to supply only one method *ru*
occurs.

Change the class *CvPaint* (in
follows:

1. At the beginning of
   line

   ```
   implements Run
   ```

2. After {, add the follo

   ```
   Image image;
   Graphics gImag
   ```

```
double sunThet
Thread thr = n
```

3. Insert the method *r*
Exercise 5.4, but c
spherical coordinat
variables *obj.sunX*
value for *sunPhi*, w
constant. By using
= 1, the light vector

7.4

4. Insert the program

```
int w, h;
CvPainter(){th
public void up
```

5. Modify the *paint* m
glmage as well as

done in program *Ar*
Exercise 5.4.

7.5 For the format of the desired
for the program to generate
and Appendix E, if necessary

Chapter 8: Fractals

8.1 INTRODUCTION

There are many aspects in nature that are repeating and many cases of patterns similar at different scales. For example, when observing a pine tree, one may notice that the shape of a branch is very similar to that of the entire tree, and the shapes of sub-branches and the main branch are also similar. Such kind of self-similar structure that occurs at different levels of magnification can be modeled by a branch of mathematics called *Fractal geometry*. The term

fractal was coined by Benît Mandelbrot in 1975, and means *fractus* or *broken* in Latin. Fractal geometry studies the properties and behavior of fractals. It describes many situations which cannot be explained easily by classical geometry. Fractals can be used to model plants, weather, fluid flow, geologic activity, planetary orbits, human body rhythms, socioeconomic patterns, and music, just to name a few. They have been applied in science, technology, and computer generated art. For example, engineers use fractals

to control fluid dynamics in order to reduce process size and energy use.

A fractal, typically expressed as curves, can be generated by a computer recursively or iteratively with a repeating pattern. Compared with human beings, computers are much better in processing long and repetitive information without complaint. Fractals are therefore particularly suitable for computer processing. This chapter introduces the basic concepts and program implementation of fractals. It starts with a simple type of

fractal curves, then focuses on a grammar-based generic approach for generating different types of fractal images, and finally discusses the well-known Mandelbrot set.

8.2 KOCH CURVES

A simple example of self-similar curves is the Koch curve, discovered by the Swedish mathematician Helge von Koch in 1904. It serves a useful introduction to the concepts of fractal curves.

In Figure 8.1, K_0, K_1, and K_2 denote successive generations of the Koch curve. A straight line segment is called the zero-th generation. We can construct Koch curve as follows:

- Begin with a straight line

and call it K_0;

- Divide each segment of K_n into three equal parts; and

- Replace the middle part by the two sides of an equilateral triangle of the same length as the part being removed.



Figure 8.1: Three generations of the Koch curve

The last step ensures that every straight line segment of K_n becomes the shape of K_1 in a

smaller scale in K_{n+1}.

Koch curves have the following interesting characteristics:

- Each segment is increased in length by a factor of 4/3. Therefore, K_{n+1} is 4/3 as long as K_n, and K_i has the total length of $(4/3)^i$.
- When n is getting large, the curve still appears to have the same shape and roughness.
- When n becomes infinite,

the curve has an infinite length, while occupying a finite region in the plane.

The Koch curve can be easily implemented using the turtle graphics method. Originated in the Logo programming language, turtle graphics is a means of computer drawing using the concept of a turtle crawling over the drawing space with a pen attached to its underside. The drawing is always relative to the current position and direction of the turtle. Considering each straight line of K_{n-1} to be drawn

as a K^1 in K^n in the next generation, we can write a recursive program to draw Koch curves as in the following pseudocode:

To draw K_n we proceed as follows:

```
If (n == 0) Draw a straigh
Else
{   Draw K_{n-1};
    Turn left by 60°;
    Draw K_{n-1};
    Turn right by 120°;
    Draw K_{n-1};
    Turn left by 60°;
    Draw K_{n-1};
```

```
}
```

To implement the above pseudocode in a Java program, we need to keep track of the turtle's current position and direction. The following program draws the Koch curve at the zero-th generation K_0. With each mouse click, it draws a higher generation replacing the previous generation. The program defines the origin of the coordinate system at the center of the screen. The turtle starts pointing to the right, and locating at half of the initial length to the left of the origin, that is, $(-200, 0)$ for the

initial length of 400. The turtle moves from the current position at (*x*, *y*) to the next position at (*x*1, *y*1) while changing its direction accordingly.

```
// Koch.java: Koch curves.
import java.awt.*;
import java.awt.event.*;
public class Koch extends
{  public static void main
   Koch()
   {  super("Koch. Click t
      addWindowListener(ne
         {public void winc
                  WindowEve
      setSize (600, 500);
      add("Center", new Cv
      show();
```

```
    }
}

class CvKoch extends Canva
{  public float x, y;
   double dir;
   int midX, midY, level =

   int iX(float x){return
   int iY(float y){return

   CvKoch()
   {  addMouseListener(new
      {  public void mouse
         {  level++; // ea
            repaint();
         }
      });
   }
```

```
public void paint(Graph
{  Dimension d = getSiz
   int maxX = d.width -
       length=3* maxX /
   midX = maxX/2; midY
   x = (float)(-length/
   y = 0;
   dir = 0;
   drawKoch(g, length,
}

public void drawKoch(Gr
{  if (n==0)
   {  double dirRad, xI
      dirRad = dir * Ma
      xInc = len * Math
      yInc = len * Math
      float x1=x+ (floa
            y1=y+ (floa
```

```
                g.drawLine(iX(x),
                x = x1;
                y = y1;
                }
                else
                {   drawKoch(g, le
                    dir += 60;
                    drawKoch(g, le
                    dir-=120;
                    drawKoch(g, le
                    dir += 60;
                    drawKoch(g, le
        }
    }
}
```

Joining three Koch curves together, we obtain the interesting Koch snowflake as

shown in Figure 8.2. The length of a Koch snowflake is $3*(4/3)^i$ for the *i*th generation since the length of K_i is $(4/3)^i$. It increases infinitely as does *i*. The area of the Koch snowflake grows slowly and is indeed bounded. In fact, as *i* becomes very large, its shape and roughness appear to remain the same. Koch snowflakes can be easily drawn by connecting three Koch curves using a modified version of the program above (see Exercise 8.2).



Figure 8.2: Koch snowflakes of generations 3, 5 and 7

8.3 STRING GRAMMARS

As discussed above, Koch curves are drawn through a set of commands specifically defined for Koch curves. Many interesting curves could be drawn in a similar fashion but they would require a complete program for each different kind of curve. The approach in the above section is apparently not general for generating different kinds of curves.

Consider again the Koch curve.

The pattern of the first generation repeats itself in smaller scales at higher generations.

Such a common pattern distinguishes Koch curves from other curves. Therefore, an approach that can encode the common pattern in a simple string of characters would be general enough to specify a variety of curves. Formally, the specification of a common pattern is called a *grammar*, and the grammar-based systems for drawing fractal curves are called *L-Systems* (invented by the Hungarian biologist Aristid

Lindenmayer in 1968).

The string of characters defining a common pattern instructs the turtle to draw the pattern. Each character in the string serves as a command to perform an atomic operation. Given the distance *D* and turning angle α through which the turtle is supposed to move, let us now introduce the three most common commands:

- F - move forward the distance *D* while drawing in the current direction.
- + - turn right through the

angle α.

- − - turn left through the angle α.

For example, given a string *F* −*F*++*F*−*F* and angle 60°, the turtle would draw the first generation of Koch curve K_1 as shown in Figure 8.1. It would however be tedious and error-prone to manually provide long strings for different curves. Fortunately, computers are best at performing repeated, long and tedious tasks without making mistakes. Using the same Koch curve example, to draw more

generations, we define a *string production rule*

$$F \rightarrow F-F++F-F$$

The rule means that every occurrence of *F* (that is, the left-hand side of '→') should be replaced by *F*−*F*++*F*−*F* (that is, the right-hand side). Starting from an initial string *F* which is called the *axiom*, recursively applying this production rule would produce strings of increasing lengths. Interpreting any of the strings, the turtle would draw a corresponding generation of the Koch curve. Let

us make the axiom the zero-th generation $K_0 = F$ and the first generation $K_1 = F - F ++ F - F$, then K_2 can be obtained by substituting every F character in K_1 by $F-F++F-F$, so that

$$K_2 = F-F++F-F-F-F++F-F++F-F++F-F-F-F++F-F$$

By interpreting this string, the turtle would draw a curve exactly the same as K_2 in Figure 8.1. This process can continue to generate the Koch curve at any higher generation.

In summary, to draw a fractal curve, such as the Koch curve, at

any generation, we need to know at least the following three parameters:

1. The axiom from which the turtle starts.

2. The production rule for producing strings from the *F* character. We will call the right-hand side of this rule the *F-string*, which is sufficient to represent the rule.

3. The angle at which the turtle should turn.

Denoting these parameters in a

template form (axiom, F-string, angle), we call this the *grammar* of the curve, and we can specify the Koch curve as (*F*, *F*−*F*++*F*−*F*, 60).

To define more complex and interesting curves, we introduce three more production rules, obtaining grammars of six elements instead of three as above. We introduce an *X-string*, to be used to replace every occurrence of *X* when producing the next generation string. Similarly, there will be a *Y-string*, used to replace every occurrence

of *Y*. Their replacement process is performed in the same fashion as for the F-string. In other words, all the three string types are treated equally during the string-production process. The *X* and *Y* characters are, however, different from the *F* character as they are simply ignored by the turtle when drawing the curve. The third new production rule, named *f-string*, will be discussed shortly. In the meantime, we reserve its position, but substitute *nil* for it to indicate that we do not use it. It follows that there are six parameters in the

extended grammar template

(axiom, F-string, f-string, X-string, Y-string, angle).

The following grammars produce some more interesting curves:

Dragon curve: $(X, F, nil, X+YF+, -FX-Y, 90)$.

Hilbert curve: $(X, F, nil, -YF+XFX+FY-, +XF-YFY-FX+, 90)$.

Sierpinski: arrowhead$(YF, F, nil, YF+XF+Y, XF-YF-X, 60)$.

Figures 8.3, 8.4 and 8.5 illustrate some selected generations of the Dragon, Hilbert and Sierpinski curves that are generated based on their string grammars as defined above.



Figure 8.3: Dragon curves: 1st, 2nd, 3rd, 4th, 5th and 11th generations



Figure 8.4: Dragon curve of 8th generation, rounded corners





Figure 8.5: Hilbert curve (5th generation) and Sierpinski arrowhead (7th generation)

It is remarkable that no Dragon

curve intersects itself. There seems to be one such intersection in the 4th generation Dragon curve of Figure 8.3 and many more in those of higher generations. However, that is not really the case, as demonstrated by using rounded instead of sharp corners. Figure 8.4 illustrates this for an 8th generation Dragon curve.

It is interesting to note that all the curves we have seen so far share one common characteristic, that is, each curve reflects the exact trace of the turtle's movement and is drawn

essentially as one long and curved line. This is because the turtle always moves forward and draws by executing the *F* character command.

8.3.1 Moving without drawing and f-strings

Sometimes, it is desirable to keep some of the curve components at proper distances from each other. This implies that such a curve is not connected. We therefore need to define a forward moving action for the turtle without drawing:

- *f* - move forward the distance *D* without drawing a line.

The f-string, for which we have already reserved a position (just after the F-string) indicates how each lower-case *f* is to be expanded. By using an f-string other than *nil*, we are able to generate an image with a combination of islands and lakes as shown in Figure 8.6, based on the following grammar:

$$(F+F+F+F, F+f-FF+F+FF+Ff+FF-f+FF-F-FF-Ff-FFF, ffffff, nil, nil, 90)$$



Figure 8.6: Second generation islands

Note that here the parameters X-string and Y-string are unused and therefore written as *nil*.

To summarize, we have introduced the following six parameters into our string grammar:

1. The axiom from which the turtle starts;

2. The F-string for producing strings from *F* that instructs the turtle to move forward while drawing;

3. The f-string for

producing strings from *f*, that instructs the turtle to move forward without drawing;

4. The *X*-string for producing strings from *X*, that does not affect the turtle;

5. The *Y*-string for producing strings from *Y*, that does not affect the turtle; and

6. The angle at which the turtle should turn.

In principle, more parameters may be introduced if the above six parameters cannot express new types of curves. On the other hand, a grammar does not have to use all the introduced parameters since, as we have seen, a *nil* can be used to represent an unused parameter.

8.3.2 Branching

With all the curves we have seen so far, one may observe the following phenomenon. The turtle is always moving forward along a curved line. It sometimes draws

(seeing an *F* character) and sometimes does not draw (seeing an *f* character). The turtle never turns back to where it has visited before, since it cannot remember its previous positions. This implies that the turtle is unable to branch off from any of the previous curve positions and draw branching lines.

To make the turtle remember places that it has visited, we need to introduce the concept of the turtle's *state*. Let us call the turtle's current position together with its direction the *state* of the turtle. In other words, a state is

defined by the values of a location in the drawing space and the angle at the location. To enhance the drawing power of string-production rules, we allow the turtle to keep its states and return to any of them later by introducing two more character commands:

- [- store the current state of the turtle
-] - restore the turtle's previously stored state

These two characters, however, do not form strings of their own

and thus do not require new production rules. They merely participate in the F-, f-, X-, and Y-strings to instruct how the turtle should behave.

The most appropriate data structure to implement the store and restore operations is a stack. Upon meeting a [character, the turtle pushes its current state onto the stack. When encountering a] character, the turtle pops its previous state from the stack and starts from the previous position and direction to continues its journey. Having empowered the turtle with

the capability of returning and restarting from its previous states, we are able to draw curves with branches, such as trees defined in the following string grammars:

$$\text{Tree1: } (F, F[+F]F[-F]F, nil, nil, nil, 25.7)$$

$$\text{Tree2: } (X, FF, nil, F[+X]F[-X]+X, nil, 20.0)$$

$$\text{Tree3: } (F, FF-[-F+F+F]+[+F-F-F], nil, nil, nil, 22.5)$$

These grammars were used to obtain the trees shown in Figure 8.7.



Figure 8.7: Examples of fractal trees: Tree1 (4th generation), Tree2 (5th generation) and Tree3 (4th generation)

If the line thickness of each branch is set in proportion to its distance from the root, and also a small fraction of randomness is applied to the turning angle, more

realistic looking trees would be produced.

Most of the figures in this section were produced by the program below, with input files to be discussed after this program:

```
// FractalGrammars.java
import java.awt.*;
import java.awt.event.*;

public class FractalGramma
{  public static void main
   {  if (args.length == 0
         System.out.printl
      else
         new FractalGramma
   }
```

```
    FractalGrammars(String
    {  super("Click left or
       addWindowListener(ne
          {public void winc
                WindowEve
       setSize (800, 600);
       add("Center", new Cv
       show();
    }
}

class CvFractalGrammars ex
{  String fileName, axiom,
    int maxX, maxY, level =
    double xLast, yLast, di
       lengthFract, reductF

    void error(String str)
    {  System.out.println(s
```

```
    System.exit(1);
}

CvFractalGrammars(Strin
{   Input inp = new Inpu
    if (inp.fails())
       error("Cannot ope
    axiom = inp.readStri
    strF = inp.readStrin
    strf = inp.readStrin
    strX = inp.readStrin
    strY = inp.readStrin
    rotation = inp.readF
    dirStart = inp.readF
    fxStart = inp.readFl
    fyStart = inp.readFl
    lengthFract = inp.re
    reductFact = inp.rea
    if (inp.fails())
```

```
            error("Input file

        addMouseListener(new
        {  public void mouse
           {  if ((evt.getMo
              {  level--;
                 if (level <
                    level =
              }
              else
                 level++;
              repaint();
           }
        });

}

Graphics g;
int iX(double x){return (i
```

```
int iY(double y){return (i

void drawTo(Graphics g, dc
{  g.drawLine(iX(xLast), i
   xLast = x;
   yLast = y;
}

void moveTo(Graphics g, dc
{  xLast = x;
   yLast = y;
}
public void paint(Graphics
{  Dimension d = getSize()
   maxX = d.width - 1;
   maxY = d.height - 1;
   xLast = fxStart * maxX;
   yLast = fyStart * maxY;
   dir = dirStart; // Init
```

```
    turtleGraphics(g, axiom
}

public void turtleGraphics
    int depth, double len)
{   double xMark=0, yMark=0
    for (int i=0;i<instruct
    {   char ch = instructic
        switch(ch)
        {
        case 'F': // Step fc
            // Start: (xLast,
            if (depth == 0)
            {   double rad = M
                    dx = len *
                drawTo(g, xLas
            }
            else
                turtleGraphics
```

```
            break;
        case 'f': // Step fo
            // Start: (xLast,
            if (depth == 0)
            {  double rad = M
                  dx = len *
               moveTo(g, xLas
            }
            else
               turtleGraphics
            break;
        case 'X':
            if (depth > 0)
               turtleGraphics
            break;
        case 'Y':
            if (depth > 0)
               turtleGraphics
            break;
```

```
            case '+': // Turn ri
               dir -= rotation;
            case '-': // Turn le
               dir += rotation;
            case '[': // Save pc
               xMark = xLast; yM
            case ']': // Back tc
               xLast = xMark; yL
            }
         }
      }
   }
```

The most essential input data consist of the grammar, for example,

$$(X, F, nil, X+YF+, -FX-Y, 90)$$

for the Dragon curve. In addition, the following five values would help in obtaining desirable results:

- The direction in which the turtle starts, specified as the angle, in degrees, relative to the positive *x*-axis.
- The distance between the left window boundary and the start point, expressed as a fraction of the window width.
- The distance between

the lower window boundary and the start point, expressed as a fraction of the window height.

- The length of a single line segment in the first generation, expressed as a fraction of the window height.

- A factor to reduce the length in each next generation, to prevent the image from growing outside the window boundaries.

Setting the last two values can be regarded as tuning, so they were found experimentally. We supply all these data, that is, five strings and six real numbers, in a file, the name of which is supplied as a program argument. For example, to produce the Dragon curve, we can enter this command to start the program:

```
java FractalGrammars Dragc
```

where the file *Dragon.txt* is listed below, showing the grammar (*X*, *F*, *X*+*YF* +, −*FX*−*Y*, 90) followed by the five values just discussed:

```
"X"          // Axiom
```

```
"F"          // strF
""           // strf
"X+YF+"      // strX
"-FX-Y"      // strY
90           // Angle of rotat
0            // Initial direct
0.5          // Start at x = 0
0.5          // Start at y = 0
0.6          // Initial line l
0.6          // Reduction fact
```

As you can see, strings are supplied between a pair of quotation marks, and comment is allowed at the end of each line. Instead of *nil*, we write the empty string "". Although the initial direction of the turtle is

specified as east, the first line is drawn in the direction south. This is because of the axiom "*X*",which causes initially *strX* = "*X*+*YF*+" to be used, where *X* and *Y* are ignored. So actually "+*F*+" is executed by the turtle. As we know, the initial + causes the turtle to turn right before the first line is drawn due to *F*, so this line is drawn downward instead of from left to right.

The other curves were produced in a similar way. Both the grammars and the five additional parameter values, as discussed

above, for these curves are listed in the following table:

Dragon	(*X*, *F*, *nil*, *X*+*YF*+, −*FX*
Hilbert	(*X*, *F*, *nil*, −*YF*+*XFX*+*FY* −*FX*+, 90)
Sier-pinski	(*YF*, *F*, *nil*, *YF*+*XF*+*Y*, *X* 60).
Islands	(*F*+*F*+*F*+*F*, *F*+*f* −*FF*+*F* − *f* + *FF*−F−*FF*−*Ff* −*F* *nil*, 90)
Tree1	(*F*, *F*[+*F*]*F*[-*F*]*F*, *nil*, *nil*,
Tree2	(*X*, *FF*, *nil*, *F*[+*X*]*F*[−*X*]
Tree3	(*F*, *FF*−[−*F*+*F*+*F*]+[+*F*

nil, *nil*, 22.5)

Open table as spreadsheet

When discussing the Tree examples with branches, we suggested that a stack would be used to push and pop states, while there seemed to be no stack structure in the program. However, there is a local variable *xMark* in the recursive method *turtleGraphics*, and for each recursive call a version of this variable is stored on a system stack. In other words, the use of a stack is implicit in this program.

8.4 MANDELBROT AND JULIA SETS

The *Mandelbrot set*, named after Polish-born French mathematician Benît Mandelbrot, is a fractal. Recall that a fractal curve reveals small-scale details similar to the large-scale characteristics. Although the Mandelbrot set is self- similar at different scales, the small-scale details are not *identical* to the whole. Also, the Mandelbrot set is infinitely complex. Yet the process of generating it is based on an extremely simple equation

involving complex numbers. The left part of Figure 8.8 shows a view of the Mandelbrot set. The outline is a fractal curve that can be zoomed in for ever on any part for a close-up view, as the right part of Figure 8.8 illustrates. Even parts of the image that appear quite smooth show a jagged outline consisting of many tiny copies of the Mandelbrot set. For example, as displayed in Figure 8.8, there is a large black region like a cardioid near the center with a circle joining its left-hand side. The region where the cardioid and the circle are joined

together appears smooth. When the region is magnified, however, the detailed structure becomes apparent and shows many fascinating details that were not visible in the original picture. In theory, the zooming can be repeated for ever, since the border is ‘infinitely complex’.



Figure 8.8: Mandelbrot set and magnified detail

The Mandelbrot set is a set *M* of complex numbers defined in the following way:

$$M = \{c \in \mathbb{C} | \lim_{n \to \infty} z_n \neq \infty\}$$

where *C* is the set of all complex numbers and, for some constant *c*, the sequence z_0, z_1, … is defined as follows:

$$z_0 = 0$$

$$z_{n+1} = z_n^2 + c$$

That is, the Mandelbrot set is the set of all complex numbers which

fulfill the condition described above. In other words, if the sequence z_0, z_1, z_2, … does not approach infinity, then c belongs to the set. Given a value c, the system generates a sequence of values called the *orbit* of the start value 0:

$$
\begin{aligned}
z_0 &= 0 \\
z_1 &= z_0^2 + c = c \\
z_2 &= z_1^2 + c = c^2 + c \\
z_3 &= z_2^2 + c = (c^2 + c)^2 + c \\
z_4 &= z_3^2 + c = ((c^2 + c)^2 + c)^2 + c \\
&\ldots
\end{aligned}
$$

As soon as an element of the

sequence $\{z_n\}$ is at a distance greater than 2 from the origin, it is certain that the sequence tends to infinity. A proof of this goes beyond the scope of this book. If the sequence does not approach infinity and therefore remains at a distance of at most 2 from the origin for ever, then the point c is in the Mandelbrot set. If any z_n is farther than 2 from the origin, then the point c is not in the set.

Now let us consider how to generate a Mandelbrot image. Since the Mandelbrot set is a set

of complex numbers, first we have to find these numbers that are part of the set. To do this we need a test that will determine if a given number is inside the set or outside. The test is applied to complex numbers z_n computed as $z_{n+1} = z^2_n + c$. The constant c does not change during the testing process. As the number being tested, c is the point on the complex plane that will be plotted when the testing is complete. This plotting will be done in a color that depends on the test result. For some value n_{Max}, say 30, we start computing z_1, z_2, …

until either we have computed z_n for $n = n_{\text{Max}}$, or we have found a point $z^n (n \leq n_{\text{Max}})$ whose distance from the origin O is greater than 2. In the former case, having computed n_{Max} elements of the sequence, none of which is farther than a distance 2 away from O, we give up, consider the point c belonging to the Mandelbrot set, and plot it in black. In the latter case, the point z_n going beyond the distance 2, we plot the point c in a color that depends on the value of n.

Let us now briefly discuss complex arithmetic, as far as we need it here, for those who are unfamiliar with this subject. Complex numbers are two-dimensional by nature. We may regard the complex number

$$z = x + yi$$

as the real number pair (x, y). It is customary to refer to x as the *real part* and to y as the *imaginary part* of z. We display z in the usual way, with x drawn along the horizontal axis and y along the vertical axis. Addition of

two complex numbers is the same as that for vectors:

$$(x_1 + y_1 i) + (x_2 + y_2 i) = (x_1 + x_2) + (y_1 + y_2)i$$

By contrast, multiplication of complex numbers is rather complicated:

$$(x_1 + y_1 i)(x_2 + y_2 i) = (x_1 x_2 - y_1 y_2) + (x_1 y_2 + x_2 y_1)i$$

It follows that for

$$z = x + yi$$

we have

$$z^2 = (x^2 - y^2) + 2xyi$$

Although we do not need this for

our purpose, we may as well note that by setting $x = 0$ and $y = 1$, giving $0 + 1 \times i = i$, we find

$$i^2 = (0^2 - 1^2) + 2 \times 0 \times 1 \times i = -1$$

which explains why the symbol i is often referred to as the square root of −1:

$$i = \sqrt{-1}$$

The distance of the complex number $z = x + yi$ from the origin O is called the *absolute value* or *modulus* of z and is denoted as $|z|$. It follows that

$$|z| = \sqrt{x^2 + y^2}$$

Remember, $|z|^2 = x^2 + y^2$, while $z^2 = (x^2 - y^2) + 2xyi$ so, in general, $|z|^2$ is unequal to z^2. This very brief introduction to complex numbers cannot replace a thorough treatment as found in mathematics textbooks, but it will be sufficient for our Mandelbrot subject.

In the algorithm for Mandelbrot fractals, when computing each successive value of z, we want to know if its distance from the

origin exceeds 2. To calculate this distance, usually denoted as $|z|$, we add the square of its distance from the *x*-axis (the horizontal real axis) to the square of its distance from the *y*-axis (the vertical imaginary axis) and then take the square root of the result. The computation of the square root operation can be saved by just checking whether the sum of these squares is greater than 4. In other words, for

$$z = x + yi$$

we perform the test

$$|z|^2 > 4$$

which is expressed in terms of real numbers as

$$x^2 + y^2 > 4$$

Now to compute each new value of z using $z_{n+1} = z^2_n + c$, let us write $Re(c)$ and $Im(c)$ for the real and imaginary parts of c. It then follows from

$$z^2 = (x + yi)^2 = (x^2 - y^2) + (2xy)i$$

that the real and imaginary parts of each element $z_{n+}{}^1$ are found as follows:

$$\text{real part:} \quad x_{n+1} = x_n^2 - y_n^2 + Re(c)$$

$$\text{imaginary part:} \quad y_{n+1} = 2x_n y_n + Im(c)$$

As we increment n, the value of $|z_n|^2$ will either stay equal to or below 4 for ever, or eventually surpass 4. Once $|z_n|^2$ surpasses 4, it will increase for ever. In ^{2} stays small, the number c being tested is part of the Mandelbrot set. In the latter case, when $|z^n|$ number c is not part of the Mandelbrot set.

8.4.1 Implementation in Java

To display the whole Mandelbrot set image properly, we need some mapping

$$x_{\mathrm{Pix}} \rightarrow x$$

$$y_{\mathrm{Pix}} \rightarrow y$$

to convert the device coordinates (x_{Pix}, y_{Pix}) to the real and imaginary parts x and y of the complex number $c = x + yi$. In the program, the variables x_{Pix} and y_{Pix} are of type *int*, while x and y are of type *double*. We will use the following ranges for the device coordinates:

$$0 \leq x_{Pix} < w$$

$$0 \leq y_{Pix} < h$$

where we obtain the width *w* and height *h* of the drawing rectangle in the usual way:

```
w = getSize().width;
h = getSize().height;
```

For *x* and *y* we have

$$minRe \leq x \leq maxRe$$

$$minIm \leq y \leq maxIm$$

The user will be able to change these boundary variables *minRe*, *maxRe*, *minIm* and *maxIm* by dragging the left mouse button.

Their default values are *minRe*0 = −2, *maxRe*0 = +1, *minIm*0 = −1, *maxIm*0 = +1, which will at any time be restored when the user clicks the right mouse button. Using the variable *factor*, computed in Java as

```
factor = Math.max((maxRe -
```

we can perform the above mapping from (x_{Pix}, y_{Pix}) to (x, y) by computing

$$x = minRe + factor \times x_{Pix}$$

$$y = minIm + factor \times y_{Pix}$$

For every device coordinate pair (x_{Pix}, y_{Pix}) of the window, the

associated point $c = x + iy$ in the complex plane is computed in this way. Then, in up to n_{Max} iterations, we determine whether this point belongs to the Mandelbrot set. If it does, we display the original pixel (x_{Pix}, y_{Pix}) in black; otherwise, we plot this pixel in a shade of red that depends on n, the number of iterations required to decide that the point is outside the Mandelbrot set. The expression $100 + 155 * n/n_{Max}$ ensures that this color value will not exceed its maximum value 255. If n_{Max} is set larger than that in the program,

program execution will take more time but the quality of the image would improve. The implementation of this can by found in the *paint* method at the bottom of the following program, after which we will discuss the implementation of cropping and zooming.

```
// MandelbrotZoom.java: Ma
import java.awt.*;
import java.awt.event.*;

public class MandelbrotZoo
{  public static void main
   MandelbrotZoom()
   {  super("Drag left mou
            "Click right m
```

```
        addWindowListener(ne
           {public void winc
                    WindowEve
        setSize (800, 600);
        add("Center", new Cv
        show();
    }
}
class CvMandelbrotZoom ext
{   final double minRe0 = -
                  minIm0 = -
    double minRe = minRe0,
                     minIm =
    int n, xs, ys, xe, ye,

    void drawWhiteRectangle
    { g.drawRect(Math.min(x

}
```

```
boolean isLeftMouseButton(
{  return (e.getModifiers(
}

CvMandelbrotZoom()
{  addMouseListener(new Mc
   {  public void mousePres
      {  if (isLeftMouseBu
         { xs = xe = e.get
           ys = ye = e.get
         }
         else
         { minRe = minRe0;
           maxRe = maxRe0;
           minIm = minIm0;
           maxIm = maxIm0;
           repaint();
         }
```

```
    }

    public void mouseRe
    {  if (isLeftMouseB
       {  xe = e.getX()
          ye = e.getY()
          if (xe != xs
          { int xS = Ma
                yS = Ma
                w1 = xE
                h2 = (i
                dx = (w
             xS -= dx; x
             yS -= dy; y
             maxRe = min
             maxIm = min
             minRe += fa
             minIm += fa
             repaint();
```

```
            }
        }
    }
        });

        addMouseMotionList
        {  public void mou
            {  if (isLeftMc
                {  Graphics
                    g.setXORM
                    g.setColc
                    if (xe !=
                        drawWh
                    xe = e.ge
                    ye = e.ge
                    drawWhite
                }
            }
        });
```

```
    }

    public void paint(Gr
    {  w = getSize().wid
       h = getSize().hei
       r = w/h; // Aspec
       factor = Math.max
       for(int yPix=0; y
       {  double cIm = m
          for(int xPix=0
          {  double cRe
             int nMax =
             for (n=0; n
             {  double x
                if (x2 +
                   break
                y = 2 *
                x = x2 -
             }
```

```
                                g.setColor(
                                    : new C
                                g.drawLine(
                            }
                        }
                    }
                }
```

As indicated in the title bar (implemented by a call to *super* at the beginning of the *MandelbrotZoom* constructor), the user can zoom in by using the left mouse button. By dragging the mouse with the left button pressed down, a rectangle appears, as shown in Figure 8.9, with one of its corners at the

point first clicked and the opposite one denoting the current mouse position. This process is sometimes referred to as *rubber banding*.



Figure 8.9: Cropping and

zooming in

When the user releases the mouse button, the picture is cropped so that everything outside the rectangle is removed and the contents inside are enlarged and displayed in the full window. This cropping is therefore combined with zooming in, as Figure 8.10 illustrates. The user can continue zooming in by cropping in the same way for ever. It would be awkward if there were no way of either zooming out or returning to the original image. In program *MandelbrotZoom.java* the latter

is possible by clicking the right mouse button.



Figure 8.10: Result of cropping and zooming in

To implement this cropping rectangle, we use two opposite corner points of it. The start point (*xs*, *ys*) is where the user clicks the mouse to start dragging, while the opposite corner is the endpoint (*xe*, *ye*). Three Java methods are involved:

mousePressed:	to define both the start point (*xs*, *ys*) and initial position of the endpoint

	(*xe*, *ye*);
mouseDragged:	to update the endpoint (*xe*, *ye*), removing the old rectangle and drawing the new one;
	to compute the logical boundary values

mouseReleased:	*minRe*, *maxRe*, *minIm* and *maxIm* on the basis of (*xs*, *ys*)and(*xe*, *ye*).

In *mouseDragged*, drawing and removing the cropping rectangle is done using the XOR mode which was briefly discussed at the end of Section 4.3. Here we use two calls

```
g.setXORMode(Color.black);
```

```
g.setColor(Color.white);
```

after which we draw both the old and the new rectangles. In *mouseReleased*, some actions applied to the cropping rectangle require explanation. As we want the zooming to be isotropic, we have to pay attention to the cropping rectangle having an aspect ratio

$$r_1 = w_1 : h_1$$

different from the aspect ratio

$$r = w : h$$

of the (large) drawing rectangle.

For example, the cropping rectangle may be in ‘portrait’ format (with $w_1 < h_1$), while the drawing rectangle has the ‘landscape’ characteristic (with $w > h$). The simplest way to deal with this case would be to cut off a portion of the cropping rectangle at the top or the bottom. However, that would lead to a result that may be unexpected and undesirable for the user. We will therefore replace the cropping rectangle with one that has the same center and the same area $a = w_1 h_1$, but an aspect ratio of r

(mentioned above) instead of r_1. The dimensions of this new rectangle will be $w_2 \times h_2$ instead of $w_1 \times h_1$. To find w_2 and h_2 we solve

$$w_2 h_2 = a \quad (= \text{area of cropping rectangle defined by the user})$$
$$w_2 : h_2 = r \quad (= \text{aspect ratio } w/h \text{ of drawing rectangle})$$

giving

$$h_2 = \sqrt{\frac{a}{r}}$$
$$w_2 = r h_2$$

Then we add the correction term $\Delta x = 1/2(w_2 - w_1)$to the x-coordinate xE of the right

cropping-rectangle edge and subtract it from the *x*-coordinate *xS* of the corresponding left edge. After performing similar operations on *yS* and *yE*, the resulting new rectangle with top-left corner point (*xS*, *yS*) and bottom-right corner point (*xE*, *yE*) is about as large as the user-defined rectangle but in shape similar to the large drawing rectangle. We then have to compute the corresponding coordinates in the complex plane, using the mapping discussed earlier. Since the new logical right boundary values *maxRe* and

maxIm should correspond to *xE* and *yE*, we compute

```
maxRe = minRe + factor * x
maxIm = minIm + factor * y
```

Similarly, to obtain the new left boundary values, we have to add *factor* × *xS* and *factor* × *yS* to the old values *minRe* and *minIm*, respectively, giving the slightly more cryptic statements

```
minRe += factor * xS;
minIm += factor * yS;
```

8.4.2 Julia sets

Associated with every point in the complex plane is a set somewhat similar to the Mandelbrot set called a *Julia set*, named after the French mathematician Gaston Julia. To produce an image of a Julia set, we use the same iteration $z_{n+1} = z^2_n + c$, this time with a constant value of c but with a starting value z_0 derived from the coordinates (x_{Pix}, y_{Pix}) of the pixel displayed on the screen. We obtain interesting Julia sets if we choose points near the boundaries of the Mandelbrot set as starting values z_0. For

example, we obtained Figure 8.11 by taking $c = -0.76 + 0.084i$, which in the Mandelbrot set (Figure 8.8) is the point near the top of the circle on the left.



Figure 8.11: Julia set, obtained by using $c = -0.76 + 0.084i$

Since the Mandelbrot set can be used to select *c* for the Julia set, it is said to form an index into the Julia set. Such an interesting relationship is also evidenced by the following fact. A Julia set is either connected or disconnected. For values of z_0 chosen from within the Mandelbrot set, we obtain connected Julia sets. That is, all the black regions are connected. Conversely, those values of z_0 outside the Mandelbrot set give disconnected Julia sets. The disconnected sets are often called *dust*, consisting of

individual points no matter what resolution they are viewed at. If, in the program *MandelbrotZoom.java*,we replace the *paint* method with the one below (preferably also replacing the name *Mandelbrot* with *Julia* throughout the program), and specify the dimensions $w = 900$ and $h = 500$ in the call to *setSize*, we obtain a program which initially produces Figure 8.11. Again, we can display all kinds of fascinating details by cropping and zooming. Note, in this program, c is a constant and the starting value z

of the sequence is derived from the device coordinates (x_{Pix}, y_{Pix}).

```
public void paint(Graphics
{  Dimension d = getSize()
   w = getSize().width;
   h = getSize().height;
   r = w/h;
   double cRe = -0.76, cIm
   factor = Math.max((maxR
   for(int yPix=0; yPix<h;
   {  for(int xPix=0; xPix
      {  double x = minRe
                y = minIm
         int nMax = 100, n
         for (n=0; n<nMax;
         {  double x2=x*x,
```

```
                if (x2 + y2 >
                    break;
                y = 2 * x * y
                x = x2 - y2 +
            }
            g.setColor(n == n
                : new Color(
            g.drawLine(xPix,
        }
    }
}
```

EXERCISES

8.1 Write a program to produce Dragon curves with rounded corners, as shown ?

in Figure 8.4.

8.2 Write a program to connect Koch curves, as shown in Figure 8.2. ?

8.3 To make bush curves (trees) appear more natural and pleasing, add randomness to the angles and lengths of the lines, and also draw lines with thickness. For example, the lower ?

part of a tree is thicker than its upper part.

8.4 Further to Exercise 8.3, add green leaves to the branches and make the leaves oriented toward the same directions as the branches. ?

Apply the method of cropping and

zooming used in

8.5 *Mandel-brotZoom.java* to some other (non-trivial) graphics program of your own choice. ?

Write a program to draw the Mandelbrot set, and when clicked on the Mandelbrot image, a Julia set corresponding to the clicked point is

8.6 drawn in a window ?

beside the Mandelbrot window. The clicked point in the form of $z = x + yi$ should also be displayed in the side window.

Answers

In the program *FractalGram* draws a line from the current *yLast* + *dy*), which, after the (*xLast*, *yLast*).

```
case 'F': // Step for
```

```
// Start: (xLast,
if (depth == 0)
{   double rad = Ma
    dx = len * Math
    drawTo(g, xLast
}
```

8.1 Besides *xLast* and *yLast*, intr
the cornerpoints that we will
time, instead of drawing a lin
one from the current point (*x*
approximate the rounded cor
automatically stored as the r
again. Then update the varia
and *dy*, respectively, so they
second line, from the current
dy/4). Note that this last line
fragment, since a quarter of

now replaced with the appro

8.2 In the *paint* method of the pr
to *drawKoch* preceded by se
calls, each preceded by assi
starts in the right direction.

8.3 You can generate a rand
random(), and derive the
branch in the tree. A line
method *fillPolygon*.

This hint is based on the
string grammar *Tree2* of

$$strX = "F[+X]F[-X]+X"$$

Each time the second *F* i

8.4 that should have a leaf a
should add a fragment to
to *drawTo*, provided that
One way of drawing a clo
leaf is to draw a sequenc
whose centers lie on a li
branch in question.

Use methods *iX* and *iY* to co
and *fy* for the inverse conver
can use

```
int iX(float x)
{   return (int)(xDevC
}
```

```
float fx(int x)
{   return xLogCenter
}
```

As usual, we use *d* defined a

```
Dimension d = getSize
```

Let us denote the current bo
xRight. For example, we car
device coordinates, that is, t
mouseReleased, we obtain
boundaries of the cropping re
obtain the corresponding log

8.5

```
xLeftNew = fx(xs);
xRightNew = fx(xe);
```

Then these new values are a

```
pixelSize = Math.max(

xLogCenter = (xLeft +
```

Let us now discuss the plaus
rigorously). Normally, *mouse*
smaller than the width of the
new logical *x*-range (*xLeft*, *x*
pixelSize. As a result of the
method *iX* will be larger than
larger scale. As for panning,
user is on the left half of the
logical *x*-range will be smalle
computed by the method *iX*.
image displayed in the select
displayed in the center of the
to the right.

8.6 Modify the *MandelbrotZoom*
Combine the two programs s

Appendix A: Linear Interpolation of 1/z

We will now discuss why, with central projection, we can use linear interpolation of $1/z$, called zi in Chapter 7, and not simply z. For example, with two points $P_1(x'_1, y'_1, zi'_1)$ and $P_2(x'_2, y'_2, zi_2)$, where x'_1, y'_1, x'_2 and y'_2 are logical screen coordinates, while $zi_1 = 1/z_1$ and $zi_2 = 1/z_2$, we can compute similar coordinates of the midpoint $M(x_M, y_M, zi_M)$ by using

$$x'_M = 0.5(x'_1 + x'_2)$$

$$y'_M = 0.5(y'_1 + y'_2)$$

$$zi_M = 0.5(zi_1 + zi_2)$$

In general we have

$$z_M \neq 0.5(z_1 + z_2)$$

Figure A.1 shows the eye-coordinate axes *x* and *z* and the screen $z = -d$.For simplicity, we ignore the *y*-axis. Recall that the position E of the eye is the origin of this coordinate system and that the negative *z*-axis points

towards the center of the object. Point P lies on line *l*, which has the following equation:

$$\frac{x}{a} + \frac{z}{-b} = 1 \quad \text{(A.1)}$$



Figure A.1: Central projection of point P on

screen

The ray of light PE intersects the screen in P′(x', $-d$). Then all points (x, z)of this ray of light satisfy the equation

$$\frac{x}{x'} = \frac{z}{-d}$$

or

$$x = -\frac{x'z}{d}$$

To compute the point of intersection of this ray of light

and line *l*, we substitute this result in (A.1), finding

$$-\frac{x'z}{ad}-\frac{z}{b}=1$$

Dividing the left- and right-hand sides of this equation by *z* and swapping them, we obtain 1

$$\frac{1}{z}=-\frac{1}{ad}x'-\frac{1}{b} \qquad \text{(A.2)}$$

which shows that $1/z$ is a linear function of x'.

This is useful because it enables us to perform *linear*

interpolation. This term is used to indicate that, with a linear function

$$f(x) = mx + c$$

and three values x_A, x_B and x_I satisfying

$$x_I = x_A + \lambda(x_B - x_A)$$

we can express $f(x_I)$ in $f(x_A)$ and $f(x_B)$ in the same way as x_I is expressed in x_A and x_B, that is,

$$f(x_I) = f(x_A) + \lambda\{f(x_B) - f(x_A)\}$$

Although this sounds very plausible, here is a proof for the sake of completeness:

$$
\begin{aligned}
f(x_{\mathrm{I}}) &= mx_{\mathrm{I}} + c \\
&= m\{x_{\mathrm{A}} + \lambda(x_{\mathrm{B}} - x_{\mathrm{A}})\} + c \\
&= mx_{\mathrm{A}} + c + \lambda(mx_{\mathrm{B}} - mx_{\mathrm{A}}) \\
&= f(x_{\mathrm{A}}) + \lambda\{(mx_{\mathrm{B}} + c) - (mx_{\mathrm{A}} + c)\} \\
&= f(x_{\mathrm{A}}) + \lambda\{f(x_{\mathrm{B}}) - f(x_{\mathrm{A}})\}
\end{aligned}
$$

As we have seen in Equation (A.2) that $1/z$ is a linear function of x', it follows that we can find the z-coordinate of a point I on a line AB in 3D space by using 1

$$
\frac{1}{z_{\mathrm{I}}} = \frac{1}{z_{\mathrm{A}}} + \lambda\left(\frac{1}{z_{\mathrm{B}}} - \frac{1}{z_{\mathrm{A}}}\right) \qquad \text{(A.3)}
$$

where λ indicates the position of the projection I′ relative to A′ and B′ :

$$x_{I'} = x_{A'} + \lambda(x_{B'} - x_{A'})$$

$$y_{I'} = y_{A'} + \lambda(y_{B'} - y_{A'})$$

We have used Equation (A.3) in Chapters 6 and 7 to compute the *z*-coordinate of an unknown 3D point that is the original of a given 2D image point.

A different notation

In the preceding discussion we have written equations of the

form

$$x_{I'} = x_{A'} + \lambda(x_{B'} - x_{A'})$$

in which the variable $x_{A'}$ occurs twice. We can instead use a different equation, in which each of the variables $x_{A'}$ and $x_{B'}$ occurs only once, at the price of using two occurrences of the parameter λ:

$$x_{I'} = (1 - \lambda)x_{A'} + \lambda x_{B'}$$

An example

Using λ = 0.5 in the above formulas, we obtain

$$x_{I'} = 0.5(x_{A'} + x_{B'})$$

$$y_{I'} = 0.5(y_{A'} + y_{B'})$$

$$\frac{1}{z_I} = 0.5\left(\frac{1}{z_A} + \frac{1}{z_B}\right)$$

Figure A.2 illustrates this. The object shown in (a) is a wire-frame model of a cube, containing an extra square between the front and back faces and passing through point I. The viewpoint indicated in (c) as *Eye* is used to obtain the perspective view (b). Here the projection I is the midpoint of A′ B′, so that the

first and second of the above three equations clearly apply. In 3D space, I is not the midpoint of AB, but BI = 2AI, as (a) and (c) show. Since the negative z_e-axis points from the eye to the center of the object, the distances shown in (c) imply that

$$z_A = -3$$

$$z_I = -4$$

$$z_B = -6$$



Figure A.2: Linear interpolation applied to inverse values

These values satisfy the third of the above three equations.

Appendix B: A Note on Event Handling

A brief discussion of event handling in Java will be helpful to understand some related, rather cryptic program fragments in this book.

An event listener

For some component, say, a button *bt*, we can write

```
bt.addActionListener(x);
```

where *x* is an object of a class that implements the interface

ActionListener. Since this implies that there is a method *actionPerformed* in this class, the above statement is in fact a means to provide the button *bt* with information about how to respond to the user clicking this button. For example, the above statement might be preceded by

```
ButtonAction x = new Buttc
```

with *ButtonAction* defined as

```
class ButtonAction impleme
{ public void actionPerfor
  { System.out.println("Bu
  }
}
```

The object *x* in the above example is referred to as an *event listener*.

Using *this* as an event listener

Instead of writing a special class, such as *ButtonAction*, for the event in question, we may as well use a class that also contains methods that are unrelated to it, provided that this class implements the interface *ActionListener*. In particular, we can use the very class in which we create the button and call the method *addActionListener*, writing

```
class MyFrame extends Fram
{ MyFrame()
  { ...
    bt.addActionListener(t
    ...
  }
  public void actionPerfor
  ...
}
```

In contrast to our previous example, this method *actionPerformed* has access to all fields and methods of the class (*MyFrame*) in which the call to *addAction-Listener* occurs.

Inner classes

Instead of the previous, somewhat contrived solution, we can use a special class *ButtonAction* and yet have access to the fields and methods of another class. We simply define *ButtonAction* in that class. For example, in the following fragment the method *actionPerformed* has access to the fields and methods of *MyFrame*:

```
class MyFrame extends Fram
{ MyFrame()
  { ...
    bt.addActionListener(n
    ...
```

```
    }
    class ButtonClass implem
    { public void actionPerf
    }
    ...
}
```

Anonymous classes

It is possible to define a class at the place where we need it, without giving it a name. For example, to create an object of such an anonymous subclass of, say, *Superclass*, we canwrite

```
Superclass y = new Supercl
```

Recall that a variable of type

Superclass can also refer to objects of subclasses of *Superclass*. In the above statement, the part {…} can be identical to that which we would otherwise use in the more familiar form

```
class Subclass extends Sup
Superclass y = new Subclas
```

Instead of a normal class *Superclass*, we can also use an interface here. This explains the following usage of an anonymous class for event handling:

```
class MyFrame extends Fram
{ MyFrame()
```

```
    {  ...
       bt.addActionListener(n
       ...
    }
    ...
}
```

Since the anonymous class, defined on the program line in the middle of this fragment, implements *ActionListener*, the part {…} must contain the method *actionPerformed*. This very compact form is used, for example, in program *Cylinder.java* of Section 6.6.

Adapter classes

As you will know, an interface promises that a set of methods will be defined. For the *ActionListener* interface, this set consists of only one method, *action-Performed*. However, many more methods have to be defined for other event interfaces, such as *WindowListener* and *MouseListener*. For every frame, a call to *addWindowListener* is required to enable the user to close this frame. Unfortunately, the interface *WindowListener* requires as many as seven methods to be defined, even if

we are interested in only one, *windowClosing*.The fragment below lists these seven methods, six of which are defined as do-nothing functions:

```
class MyFrame extends Fram
{ MyFrame()
   { ...
     addWindowListener(new
     { public void windowCl
       public void windowOp
       public void windowIc
       public void windowDe
       public void windowCl
       public void windowAc
       public void windowDe
   });
```

```
    ...
  }
  ...
}
```

To enable us to avoid such tedious program code, the designers of JDK1.1 have introduced a class *WindowAdapter*, which implements the interface *WindowListener* by providing seven do-nothing methods, so we can override only those we like. Therefore, instead of the above fragment, we will actually write

```
class MyFrame extends Fram
{ MyFrame()
```

```
    { ...
      addWindowListener(new
        {public void windowC
      ...
    }
    ...
}
```

The two lines in the middle of this fragment occur in most programs in this book. Mouse events are similar: here we can use the class *MouseAdapter*, which implements the interface *MouseListener*. It is used, for example, in the following fragment, copied from program *Anisotr.java* of Section 1.4:

```
CvAnisotr()
{ addMouseListener(new Mou
   { public void mousePress
     { xP = fx(evt.getX());
        repaint();
      }
   });
}
```

Note that the method *addMouseListener* is used here for a canvas, not for aframe.

Appendix C: File Obj3D.java

The following file is not a complete program. It is the code for a single class, *Obj3D*, which is discussed in Section 5.5 and used in the programs *Wire-frame.java* of Chapter 5, *HLines.java* of Chapter 6, *Painter.java* of Section 7.3, and *ZBuf.java* of Section 7.4.

```
// Obj3D.java: A 3D object
// Uses: Point2D (Section
//       Polygon3D, Input
import java.awt.*;
import java.util.*;
```

```
class Obj3D
{  private float rho, d, t
      xMin, xMax, yMin, yM
      v22, v23, v32, v33,
   private Point2D imgCent
   private double sunZ = 1
      inprodMin = 1e30, in
   private Vector w = new
   private Point3D[] e;
   private Point2D[] vScr;
   private Vector polyList
   private String fName =

   boolean read(String fNa
   {  Input inp = new Inpu
      if (inp.fails())retu
      this.fName = fName;
      xMin = yMin = zMin =
```

```
    xMax = yMax = zMax =
    return readObject(in
}

Vector getPolyList(){re
String getFName(){retur
Point3D[] getE(){return
Point2D[] getVScr(){ret
Point2D getImgCenter(){
float getRho(){return r
float getD(){return d;}

private boolean failing
{  Toolkit.getDefaultTo
    return false;
}

private boolean readObj
{  for (;;)
```

```
{  int i = inp.readI
   if (inp.fails()){
   if (i > 0)
   {  System.out.pri
         "Negative v
      return failing
   }
   w.ensureCapacity(
   float x = inp.rea
         z = inp.rea
   addVertex(i, x, y
}
shiftToOrigin(); //
char ch;
int count = 0;
do   // Skip the lin
{  ch = inp.readChar
}  while (!inp.eof()
if (count < 6 || cou
```

```
    {   System.out.printl
    }
//  Build polygon lis
for (;;)
{   Vector vnrs = new
    for (;;)
    {   int i = inp.re
        if (inp.fails(
        int absi = Mat
        if (i == 0 ||
            w.elementAt
        {   System.out.
            " must be d
            return fail
        }
        vnrs.addElemen
    }
    ch = inp.readChar
    if (ch != '.' &&
```

```
            // Ignore input l
            if (vnrs.size() >
               polyList.addEl
      }
      inp.close();
      return true;
   }

   private void addVertex(
   {  if (x < xMin) xMin =
      if (y < yMin) yMin =
      if (z < zMin) zMin =
      if (i >= w.size()) w
      w.setElementAt(new P
   }

   private void shiftToOri
   {  float xwC = 0.5F * (
            ywC = 0.5F * (
```

```
            zwC = 0.5F * (
        int n = w.size();
        for (int i=1; i<n; i
            if (w.elementA
            {  ((Point3D)w
               ((Point3D)w
               ((Point3D)w
            }
        float dx = xMax -
        rhoMin = 0.6F * (
        rhoMax = 1000 * r
        rho = 3 * rhoMin;
    }

    private void initPer
    {  float costh = (fl
               sinth = (fl
               cosph = (fl
               sinph = (fl
```

```
      v11 = -sinth; v12
      v21 = costh;  v22
                    v32

   }

   float eyeAndScreen(D
      // Called in pain
   {  initPersp();
      int n = w.size();
      e = new Point3D[n
      vScr = new Point2
      float xScrMin=1e3
            yScrMin=1e3
      for (int i=1; i<n
      {  Point3D P = (P
         if (P == null)
      {  e[i] = null; v
      }
```

```
        else
        {   float x = v11
            float y = v12
            float z = v13
            Point3D Pe = e
            float xScr = -
            vScr[i] = new
            if (xScr < xSc
            if (xScr > xSc
            if (yScr < ySc
            if (yScr > ySc
        }
    }
    float rangeX = xScrM
    d = 0.95F * Math.min
    imgCenter = new Poin

    for (int i=1; i<n; i
    {   if (vScr[i] != nu
```

```
    }
    return d * Math.max(
    // Maximum screen-cc
}

void planeCoeff()
{  int nFaces = polyLis

   for (int j=0; j<nFac
   {  Polygon3D pol = (
      int[] nrs = pol.g
      if (nrs.length <
      int iA = Math.abs
          iB = Math.abs
          iC = Math.abs
      Point3D A = e[iA]
      double
         u1 = B.x - A.x
         v1 = C.x - A.x
```

```
            a = u2 * v3 -
            b = u3 * v1 -
            c = u1 * v2 -
            len = Math.sqr
            a /= len; b /=
            h = a * A.x +
          pol.setAbch(a, b,
          Point2D A1 = vScr
          u1 = B1.x - A1.x;
          v1 = C1.x - A1.x;
          if (u1 * v2 - u2
          double inprod = a
          if (inprod < inpr
          if (inprod > inpr
        }
        inprodRange = inprc
      }

      boolean vp(Canvas cv,
```

```
        {   theta += dTheta;
            phi += dPhi;
            float rhoNew = fRh
            if (rhoNew >= rhoM
                rho = rhoNew;
            else
                return false;
            cv.repaint();
            return true;
        }
        int colorCode(double a
        {   double inprod = a *
            return (int)Math.rc
                ((inprod - inprc
        }
}
```

Appendix D: Class CvHLines.java

The following class is used in program *HLines.java*, listed in Section 6.8:

```
// CvHLines.java: Used in
import java.awt.*;
import java.util.*;

class CvHLines extends Can
{  private int maxX, maxY,
   private Obj3D obj;
   private Point2D imgCent
   private Tria[] tr;
   private HPGL hpgl;
   private int[] refPol;
   private int[][] connect
```

```
private int[] nConnect;
private int chunkSize =
private double hLimit;
private Vector polyList
private float maxScreen

Obj3D getObj(){return c
void setObj(Obj3D obj){
void setHPGL(HPGL hpgl)

public void paint(Graph
{  if (obj == null) ret
   Vector polyList = ob
   if (polyList == null
   int nFaces = polyLis
   if (nFaces == 0) ret
   float xe, ye, ze;
   Dimension dim = getS
   maxX = dim.width - 1
```

```
centerX = maxX/2; ce
// ze-axis towards e
// object points are
// coordinates x and
// the z-direction,
// of z. With negati
// a small value of

// obj is a java obj
// with w, e and vSc
// as index values):
// - Vector w (with
// - Array e (with P
// - Array vScr (wit
// - Vector polyList

// Every Polygon3D v
// - Array 'nrs' for
// - Values a, b, c,
```

```
// - Array t (with n

// Every Tria value
// numbers A, B and
maxScreenRange = obj
imgCenter = obj.getI
obj.planeCoeff(); //

hLimit = -1e-6 * obj
buildLineSet();

// Construct an arra
// each polygon and
// of triangles.
nTria = 0;
for (int j=0; j<nFac
{  Polygon3D pol = (
   if (pol.getNrs().
   {  pol.triangulat
```

```
            nTria += pol.g
        }
    }
    tr = new Tria[nTria]
    refPol = new int[nTr
    int iTria = 0;

    for (int j=0; j<nFac
    {  Polygon3D pol = (
       Tria[] t = pol.ge
       if (pol.getNrs().
       {  for (int i=0;
          {  Tria tri =
             tr[iTria] =
             refPol[iTri
          }
       }
    }
    Point3D[] e = obj.ge
```

```
        Point2D[] vScr = obj
        for (int i=0; i<nVer
        {  for (int j=0; j<n
           {  int jj = conne
              lineSegment(g,
                    i, jj, 0)
           }
        }
        hpgl = null;
    }
    private void buildLineS
    {  // Build the array
        // 'connect' of int
        // connect[i] is the
        // vertex numbers j,
        // an edge of the 3D
        polyList = obj.getPo
        nVertices = obj.getV
        connect = new int[nV
```

```
nConnect = new int[n
for (int i=0; i<nVer
nConnect[i] = 0;
int nFaces = polyLis

for (int j=0; j<nFac
{  Polygon3D pol = (
   int[] nrs = pol.g
   int n = nrs.lengt
   if (n > 2 && pol.
   int ii = Math.abs
   for (int k=0; k<n
   { int jj = nrs[k]
     if (jj < 0)
      jj = -jj; // a
     else
     {  int i1 = Mat
           nCon = n
        // Look if j
```

```
                int l;
                for (l=0; l<
                if (l == nCc
                {   if (nCon
                    {   int[]
                        for (l
                        connec
                    }
                    connect[i
                }
            }
            ii = jj;
        }
    }
}
int iX(float x){return
int iY(float y){return

private String toStrin
```

```
// From screen device
{  int i = Math.round(
   String s = "";
   int n = 1000;
   for (int j=3; j>=0;
   {  s += i/n;
      i %= n;
      n /= 10;
   }
   return s;
}
private String hpx(flc
private String hpy(flc

private void drawLine(
   float x2, float y2)
{  if (x1 != x2 || y1
   {  g.drawLine(iX(x1
      if (hpgl != null
```

```
            {  hpgl.write("P
               hpgl.write("P
            }
         }
      }

      private void lineSegme
         Point2D pScr, Point
      {  double u1 = qScr.x
         double minPQx = Mat
         double maxPQx = Mat
         double minPQy = Mat
         double maxPQy = Mat
         double zP = p.z, zQ
         double minPQz = Mat
         Point3D[] e = obj.g
         Point2D[] vScr = ob
         for (int i=iStart;
         {  Tria t = tr[i];
```

```
int iA = t.iA, i
Point2D aScr = v

// 1. Minimax te
if (maxPQx <= aS
 || minPQx >= aS
 || maxPQy <= aS
 || minPQy >= aS
    continue; //

 // 2. Test if P
 if ((iP == iA |
     (iQ == iA |
    continue;  /

 // 3. Test if P
 double zA = e[i
 if (minPQz >= z
    continue; //
```

```
// 4. Do P and
//    by line A
//    Similar f
double eps = 0.
if (Tools2D.are
    Tools2D.are
    Tools2D.are
    Tools2D.are
    Tools2D.are
    Tools2D.are
   continue;

// 5. Test (2D)
//    of the in
double pqa = Tc
double pqb = Tc
double pqc = Tc
```

```
if (pqa < +eps
    pqa > -eps
   continue; //

// 6. Test if n
//    infinite
int iPol = refP
Polygon3D pol =
double a = pol.
   h = pol.getH
   hP = a * p.x
   hQ = a * q.x
if (hP > h - ep
   continue; //

// 7. Test if b
boolean pInside
   Tools2D.insi
boolean qInside
```

```
   Tools2D.insi
if (pInside &&
   return; // T

// 8. If P near
//    the same
double h1 = h +
if (hP > h1 &&
   continue; //

// 9. Compute t
// with ABC in
// If, in 3D, s
// ABC, this tr
// Otherwise, t
// this triangl
double lambdaMi
for (int ii=0;
{  double v1 =
```

```
                w1 =
                denom
        if (denom !=
        {   double mu
            // mu = 0
            if (mu >
            {   double
                // lam
                // (I
                if (la
                {   if
                    lam
                    {
                    }
                if (la
                if (la
            }
```

```
        }
      }
      Point2D temp
      bScr = cScr;

    }
    float d = obj.
    if (!pInside &
    {  double iScr
              iScr
       // Back frc
       double zI =
              xI =
       if (a * xI
          continue

       Point2D iSc
       if (Tools2D
          lineSegm
```

```
                iSc

            }
            if (!qInside &
            {  double jScr
                   jScr
               double zJ =
                  1/(lambd
                     xJ =
               if (a * xJ
                  continue
               Point2D jSc
               if (Tools2D
                  lineSegm
                     qScr,
            }
            return;
                // if no c
        }
```

```
                drawLine(g, pScr
                    // No triangl
        }
}
```

Appendix E: Some Applications

This appendix demonstrates how to generate data files for other interesting 3D objects by special programs, in a similar fashion to the cylinder example in Section 6.6. The generated files are accepted by the programs *HLines.java* (see Chapter 6), *Painter.java* and *ZBuf.java* (see Chapter 7).

E.1 PLATONIC SOLIDS

We will first discuss the generation of 3D files for five well-known objects. Let us begin with two definitions.

If all edges of a polygon have the same length and any two edges meeting at a vertex include the same angle, the polygon is said to be *regular*. I fall bounding faces of a polyhedron are regular polygons, which are congruent (that is, which have exactly the same shape), that polyhedron is referred to as a *regular polyhedron* or *platonic solid*.

There are only five essentially different platonic solids; their names and their numbers of faces, edges and vertices are listed below:

➪ Open table as spreadsheet

Platonic solid	Faces	Edges
Tetrahedron	4	6
Cube (= hexahedron)	6	12
Octahedron	8	12
Dodecahedron	12	30

Note that what we call a *tetrahedron*, a *hexahedron*, and so on, should actually be referred to as *regular tetrahedron*, *regular hexahedron*, etc., but since in this section we are only dealing with regular polyhedra, we omit the word *regular* here.

The above numbers of faces, edges and vertices satisfy Euler's theorem, which also applies to non-regular polyhedra:

$$Faces + Vertices = Edges + 2 \qquad (E.1)$$

E.1.1 Tetrahedron

An elegant way of constructing a tetrahedron is by using the diagonals of the six faces of a cube as the edges of the tetrahedron, as Figure E.1(a) shows.



Figure E.1: A tetrahedron: (a) inside a cube; (b) cube

omitted; (c) after rotation

Using a cube with edges of length 2 and with its center as the origin of the coordinate system, we can easily write down the contents of the data file, say, *tetra.dat*, for the tetrahedron proper (without the surrounding cube):

```
1    1   -1   -1
2   -1    1   -1
3    1    1    1
4   -1   -1    1
Faces:
1 2 3.
2 4 3.
```

```
1  4  2.
1  3  4.
```

Supplying this file to program *HLines.java* results in a poor representation of a tetrahedron, identical to what we obtain if we omit the dashed line (and the vertex numbers) in Figure E.1(b). Most people would fail to recognize the result as a 3D object, unless Figure E.1(a) was also given. The surrounding cube in the latter figure can be obtained by adding vertices 5, 6, 7 and 8 to the first part of the above input file and twelve lines of vertex-pair numbers, for the

cube edges, to the second part.

A much better representation is Figure E.1(c), in which the tetrahedron has been rotated about the edge 1–2, in such a way that the face 1-2-3 becomes horizontal. The angle of this rotation is equal to

$$\alpha = \arctan \sqrt{2}$$

As Figure E.1(a) shows, α is the angle included by the edges P-5 and P-3 in the right-angled triangle P-5-3, where P is the point of intersection of the lines 1–2 and 5–6. Since the cube

edge 3–5 has length 2 and the line segment P-5, being half the diagonal 6-5 of the bottom plane, has the length $\sqrt{2}$, we have tan α = $2/\sqrt{2} = \sqrt{2}$, which explains the above value of α.

Fortunately, we have already developed a general and useful class, *Rota3D*, for 3D rotations. We used it in Section 3.9 in the program *Rota3DTest.java* to rotate a cube about a given axis AB through an angle of 180°. This time, vertices 1 and 2 will act as points A and B, while rotation will take place through the angle α we have just

discussed. We will use the file *tetra.dat*, listed above, as input, to derive the file *tetra*1.*dat*, describing the rotated tetrahedron, from it. Note that the classes *Point3D* and *Rota3D*, both defined in Section 3.9, and the class *Input* of Section 5.5 must be available (in the form of *.class* files) in the current directory.

```
// Rota3DTetra.java: Rotat
//    has horizontal top an
//    a way that it obtains
//    Uses: Point3D, Rota3D
import java.io.*;
      public class Rota3DTe
```

```
{  public static voic
      throws IOExcept
   {  // Specify AB a
      // and alpha as
      Point3D A = new
               B = new
      double alpha =
      Rota3D.initRota
      Point3D P = new
      Input inp = new
      if (inp.fails()
      {  System.out.p
         System.exit(
      }
      FileWriter fw =
      for (;;)
      {  int i = inp.
         if (inp.fail
         P.x = inp.re
```

```
                P.y = inp.re
                P.z = inp.re
                Point3D P1 =
                fw.write(i +
                   P1.y + "
            }
            inp.clear();
            // Copy the res
            for (;;)
            {   char ch = in
                if (inp.fail
                fw.write(ch)
            }
            fw.close();
        }
}
```

This program changes only the coordinates of the four vertices.

With the above input file, *tetra.dat*, the resulting output file, *tetra*1.*dat*, is listed below:

```
1   1.0 -1.0 -1.0
2   -1.0 1.0 -1.0
3   1.7320508 1.7320508 -1.
4   0.57735026 0.57735026 1
Faces:
1 2 3.
2 4 3.
1 4 2.
1 3 4.
```

Since we now have $z = -1.0$ for vertices 1, 2 and 3, we see that triangle 1-2-3 is now horizontal. This is illustrated by Figure E.1(c), which, except for the text

and the dashed edge, is the result of applying the program *HLines.java* to the above file *tetra*1*.dat*.

E.1.2 Cube or hexahedron

The cube, also known as a hexahedron, is perhaps the most common 3D object because of its simplicity. With the rather unusual vertex numbering of Figure E.1(a), this cube (with edges of length 2 and with the origin as its center) is described by the following file:

```
1   1 -1 -1
2 -1   1 -1
3   1   1  1
4 -1 -1   1
5   1   1 -1
6 -1 -1 -1
7   1 -1   1
8 -1   1   1
Faces:
1   5   3   7.
5   2   8   3.
2   6   4   8.
6   1   7   4.
7   3   8   4.
1   6   2   5.
```

E.1.3 Octahedron

An octahedron has eight faces, which are equilateral triangles. One way of constructing this platonic solid is by starting with a cube and using the principle of *duality* or *reciprocity*. The numbers of faces and vertices shown in the table:

Open table as spreadsheet

Platonic solid	Faces	Edges
Cube (= hexahedron)	6	12
Octahedron	8	12

suggest that each face of a cube might be related to a vertex of an octahedron and vice versa. This is indeed the case: a cube and an octahedron are said to be *dual* or *reciprocal*, which implies that the centers of the faces of one can be used as the vertices of the other. Starting with a cube, we can simply use the centers of its six faces as the vertices of an octahedron. The following data file for an octahedron is based on such a cube with edges of length 2 and with O as its center:

```
1   1   0   0
2   0   1   0
```

```
3  -1   0   0
4   0  -1   0
5   0   0  -1
6   0   0   1
Faces:
1  2  6.
2  3  6.
3  4  6.
4  1  6.
2  1  5.
3  2  5.
4  3  5.
1  4  5.
```

If we use this file as input for program *HLines.java*, we obtain the octahedron shown in Figure E.2 on the right. On the left we see the way the vertices are

numbered and the surrounding cube.



Figure E.2:
Octahedron

E.1.4 Icosahedron and dodecahedron

Let us again take a look at the following numbers of faces and vertices:

Open table as spreadsheet

Platonic solid	Faces	Edges
Dodecahedron	12	30
Icosahedron	20	30

Since the number of faces of one of the two polyhedra is equal to the number of vertices of the other, a dodecahedron and an icosahedron are reciprocal polyhedra. Figure E.3 illustrates

this. For example, vertex 1 of the dodecahedron has been constructed as the center of the face 1-2-3 of the icosahedron, vertex 2 of the dodecahedron as that of face 1-3-4 of the icosahedron, and so on. Since showing this dodecahedron in Figure E.3 in its original position would have been confusing, the dodecahedron has been shifted to the right after its construction.



Figure E.3: Icosahedron and dodecahedron as reciprocal polyhedra

It follows that constructing an icosahedron is the only remaining problem: once the coordinates of its vertices are known, we can

derive the dodecahedron from it.

Both polyhedra are based on regular pentagons, as you can see in Figure E.3. In the icosahedron shown here, there are two horizontal pentagons: 2-3-4-5-6 and 7-8-9-10-11. They have both been constructed with their vertices on (horizontal) circles with radius 1. Curiously enough, these two horizontal pentagons lie a distance 1 apart, while the 'north pole' 1 and the 'south pole' 12 lie a distance $\sqrt{5}$ apart. A proof of these facts is omitted here, because it would be rather lengthy and only very

loosely related to computer graphics. Interested readers are referred to books about geometry, such as Coxeter (1961).

With O as the center of the icosahedron, we can now define the coordinates of all twelve vertices of an icosahedron as follows:

➪ Open table as spreadsheet

i	x_i	y_i	z_i
1 2, 3,	0 cos	0 sin	

4,	{(*i* −	{(*i* −	
5,	2) ×	2) ×	$\frac{1}{2}\sqrt{5}$
6	72°}	72°}	0.5
7,	cos	sin	−0.5
8,	{36°	{36°	$\frac{1}{2}\sqrt{5}$
9,	+ (*i*	+ (*i*	
10,	− 7)	− 7)	
11	×	×	
12	72°}	72°}	
	0	0	

We can easily program the above formulas to obtain the numerical values of the vertex coordinate in question, as we will see shortly. These values are listed in the following 3D data file,

in which the faces of the icosahedron are displayed on five text lines, instead of on 20 lines as generated by the program. Also, the layout of the first part of the file has been improved for the sake of readability:

```
 1    0.0          0.0
 2    1.0          0.0
 3    0.309017     0.95105654
 4   -0.809017     0.58778524
 5   -0.809017    -0.58778524
 6    0.309017    -0.95105654
 7    0.809017     0.58778524
 8   -0.309017     0.95105654
 9   -1.0          0.0
10   -0.309017    -0.95105654
11    0.809017    -0.58778524
```

```
12    0.0          0.0
Faces:
 1   2   3.   1   3   4.   1   4
 1   6   2.   2   7   3.   3   7
 4   8   9.   4   9   5.   5   9
 6  10  11.   6  11   2.   2  11
12   9   8.  12  10   9.  12  11
```

E.1.5 Dodecahedron

As mentioned above, we use the center of the first face, 1-2-3, of the icosahedron as vertex 1 of the dodecahedron. For example, we have

$$x_1(\text{of the dodecahedron}) = \frac{x_1 + x_2 + x_3 \text{ (all three of the icosahedron)}}{3}$$

The faces in the above icosahedron file are to be read line by line, so that the center of face 1-3-4 provides vertex 2 of the dodecahedron, that of face 1-4-5 provides vertex 3, and so on. The second part of the dodecahedron file is more difficult. You can check it by comparing both polyhedra of Figure E.3. For example, the vertices of the dodecahedron's face 1-6-7-8-2, in that order, are the centers of face 1 (1-2-3), face 6 (2-7-3), face 7 (3-8-7), face 8 (3-8-4) and face 2 (1-3-4) of the icosahedron. In the data

file for the dodecahedron below, you can find this face 1-6-7-8-2 as the second one after the word *Faces*:

```
 1    0.436339     0.3170188
 2   -0.16666667   0.5129472
 3   -0.53934467   0.0
 4   -0.16666667  -0.5129472
 5    0.436339    -0.3170188
 6    0.7060113    0.5129472
 7    0.26967233   0.8299660
 8   -0.26967233   0.8299660
 9   -0.7060113    0.5129472
10   -0.872678     0.0
11   -0.7060113   -0.5129472
12   -0.26967233  -0.8299660
13    0.26967233  -0.8299660
14    0.7060113   -0.5129472
```

```
15    0.872678     0.0
16    0.16666667   0.5129472
17   -0.436339     0.3170188
18   -0.436339    -0.3170188
19    0.16666667 -0.5129472
20    0.53934467   0.0
Faces:
 1   2   3   4   5.   1   6   7
 3 10 11 12   4.   4 12 13 1
20 19 18 17 16. 20 15 14 1
18 11 10   9 17. 17   9   8
```

Since this book is about programming aspects of graphics, a Java program to generate both above files (in a slightly different format) is listed below:

```
// IcoDode.java: Generatin
//    both an icosahedron
//    Uses: Point3D (Secti

import java.io.*;

public class IcoDode
{  public static void main
   {  new Both();
   }
}

class Both
{  Point3D[] icoV;
   Tria[] icoF;

   Both()throws IOExceptic
   {  outIcosahedron();
      outDodecahedron();
```

```
}

void outIcosahedron()th
{  double zTop = 0.5 *
   // Vertices (icoV[1]
   icoV = new Point3D[1
   icoV[1] = new Point3
   double angle36 = Mat
   for (int i=2; i<=6;
   {  double alpha = (i
      icoV[i] = new Poi
         Math.sin(alpha
   }
   for (int i=7; i<=11;
   {  double alpha = an
      icoV[i] = new Poi
      Math.sin(alpha),
   }
   icoV[12] = new Point
```

```
// Faces (icoF[1], .
icoF = new Tria[21];
icoF[ 1] = new Tria
icoF[ 2] = new Tria
icoF[ 3] = new Tria
icoF[ 4] = new Tria
icoF[ 5] = new Tria
icoF[ 6] = new Tria
icoF[ 7] = new Tria
icoF[ 8] = new Tria
icoF[ 9] = new Tria
icoF[10] = new Tria
icoF[11] = new Tria
icoF[12] = new Tria
icoF[13] = new Tria
icoF[14] = new Tria
icoF[15] = new Tria

icoF[16] = new Tria
```

```
        icoF[17] = new Tria
        icoF[18] = new Tria
        icoF[19] = new Tria
        icoF[20] = new Tria
        FileWriter fwI = new
        for (int i=1; i<=12;
        {  Point3D P = icoV[
           fwI.write(i +""+P
        }
        fwI.write("Faces:\r\
        for (int j=1; j<=20;
        {  Tria t = icoF[j];
           fwI.write(t.iA +"
        }
        fwI.close();
}

    void outDodecahedron()t
    {  FileWriter fwD = new
```

```
for (int j=1; j<=20;
fwD.write("Faces:\r\
// Horizontal, at th
writeFace(fwD, 1, 2,
// Slightly facing u
writeFace(fwD, 1, 6,
writeFace(fwD, 2, 8,
writeFace(fwD, 3, 10
writeFace(fwD, 4, 12
writeFace(fwD, 5, 14
// Horizontal, at th
writeFace(fwD, 20, 1
// Slightly facing d
writeFace(fwD, 20, 1
writeFace(fwD, 19, 1
writeFace(fwD, 18, 1
writeFace(fwD, 17, 9
writeFace(fwD, 16, 7
fwD.close();
```

```
    }

    void writeVertexInCent
    {   Tria t = icoF[j];
        Point3D A = icoV[t.
        float x = (float)((
                y = (float)((
                z = (float)((
        fwD.write(j +" " +
    }

    void writeFace(FileWri
        throws IOException
    {   fwD.write(a +""+b+"
    }
}
```

An icosahedron, as generated by this program, will be useful to

generate (better) approximations of spheres, as we will see in the next section.

E.2 SPHERE REPRESENTATIONS

There are several ways of approximating a sphere by a polyhedron. A very popular one is the globe model with north and south poles at the top and the bottom, horizontal circles called *lines of latitude*, and circles called *lines of longitude* in vertical planes through the poles, as shown in Figure E.4. A program to generate such a globe should preferably be based on a single integer *n*, indicating both the number of horizontal

slices and half the number of lines of longitude. In other words, angles of 180°/*n* play an essential role, both in horizontal and vertical planes. In Figures E.4(a) and (b) we have *n* = 6 and *n* = 30, respectively. Programming this is left as an exercise (see Exercise 6.6).



Figure E.4: Approximations of a sphere: (a) $n = 6$;(b) $n = 30$

The above way of approximating a sphere has two drawbacks:

1. The faces are unequal in size and have different shapes: except for the triangles at the poles, each face is a trapezium, whose size depends on its distance from its nearest pole.

2. These spheres have an

‘anisotropic’ appearance: which may be undesirable. For example, a view from above looks much different from a view from the front. We may prefer all faces to look alike, so that the image should not significantly change if we turn the sphere a little.

We will therefore discuss different models of a sphere, in such a way that we cannot easily tell the poles and the other vertices apart.

E.2.1 Spheres based on an icosahedron

As Figure E.3 illustrates, an icosahedron and a dodecahedron are very poor approximations of a sphere. However, we can use the former as a basis to generate a much better one. The idea is to divide each triangular face of an icosahedron into four triangles, as shown in Figure E.5, and to use the sphere to which all vertices of the icosahedron belong. For the icosahedron we have constructed, the center of this sphere is O and its radius is

½√5.



Figure E.5: Dividing a triangle into four smaller
ones

With O as the center of the icosahedron and D, E and F as the midpoints of three triangle edges BC, CA and AB, we have to extend the lines OD, OE and OF, such that the new vertices D, E and F (like A, B and C) lie on the sphere just mentioned. Actually, we may as well change the lengths of all six lines OA, OB, …, OF, such that the new points A, B, …, F lie on a sphere with center O and radius 1. Doing this for all 20 faces of an icosahedron, we obtain a polyhedron that has $20 \times 4 = 80$ triangles. Since each of the 30

original edges gives a new vertex (its midpoint), and there were already 12 vertices, this new polyhedron has 12 + 30 = 42 vertices. It follows from Equation E.1 that it has 80 + 42 − 2 = 120 edges. Note that the four triangles of Figure E.5 are equilateral (that is, they have three edges of the same length), but this is the case only as long as the six points A, B, …, F lie in the same plane. Consequently, the 80 faces of our new polyhedron are *not* equilateral triangles.

Instead of writing a program just

to generate this polyhedron, we will make the program much more general. It will accept the names of an input file and an output file. The input file can be any file (in our 3D format) for a convex polyhedron that has only triangular faces and whose center is the origin O of the coordinate system (provided the vertex numbers 1, 2, 3, … are used and appear in that order in the first part of the file). In the output file we obtain a polyhedron that has four times as many (triangular) faces as the given one, and whose vertices lie

on a sphere with center O and radius 1. This will enable us to use the program several times, starting with the file *icosa.dat*, generated by program *IcoDode.java*, and each following time to use the previous output file as input. Using names of the form *sph**x**.dat*, where ***x*** is the number of faces, we can proceed as follows:

$$icosa.dat \Rightarrow sph80.dat \Rightarrow sph320.dat \Rightarrow sph1280.dat \Rightarrow \ldots$$

Figure E.6 shows the results of applying program *HLines.java* to these four files, of which the last three have been generated by

the program we are discussing.



Figure E.6: Icosahedron and three other polyhedra derived from it by program *SphTria.java*: (a) 20 faces (see Section E.1); (b) 80 faces; (c) 320 faces; (d) 1280 faces

Program *SphTria.java* takes the names of its input and output files as program arguments. After

generating the file *icosa.dat* by using program *IcoDode.java* of Section E.1, we obtain the files for the other three sphere approximations above as follows:

```
java SphTria icosa.dat sph
java SphTria sph80.dat sph
java SphTria sph320.dat sp
```

Like some other programs in this book, *SphTria.java*, listed below, uses the classes *Point3D*, *Tria* and *Input*, discussed in Sections 3.9 and 5.5:

```
// SphTria.java: Generatin
//     approximation consis
//     are four times as ma
```

```
//     input files are icos
//     the output files prc
//     To run this program,
//        java SphTria icos
//     Uses: Tria, Input (S

import java.io.*;
import java.util.*;
public class SphTria
{  public static void main
   {  if (args.length < 2)
      {  System.out.printl
         + "java SphTria I
      }
      else
         new SphTriaObj(ar
   }
}
```

```
class SphTriaObj
{  Vector v = new Vector()
   Vector t = new Vector()
   int nV, codeRadix;
   Hashtable ht = new Hash
   String inputFile, outpu

   SphTriaObj(String input
   {  this.inputFile = inp
      this.outputFile = ou
      readFile();
      computeMidpoints();
      toUnitCircle();
      writeFile();
   }

   void readFile()throws I
   {  Input inp = new Inpu
      if (inp.fails()) err
```

```
v.addElement(new Int
for (;;)
{  int nr = inp.read
   if (inp.fails())
   nV = nr;
   float x = inp.rea
         z = inp.rea
   v.addElement(new
}
inp.clear();
codeRadix = nV + 1;
inp.clear();
while (inp.readChar(
// Rest of line 'Fac
for (;;)
{  int a = inp.readI
   if (inp.fails())
   t.addElement(new
   inp.readChar(); /
```

```
    }
    inp.clear();
  }

  void error()
  {  System.out.println(
     System.exit(1);
  }
  void computeMidpoints(
  {  for (int j=0; j<t.s
     {  Tria tr = (Tria)
        int a = tr.iA, b
        addMidpoint(a, b
     }
  }

  void addMidpoint(int p
  {  if (p<q)
     {  ht.put(new Integ
```

```
            Point3D P = (Poi
                    Q = (Poi
            v.addElement(new
            (P.x + Q.x)/2, (
        }
    }

    int getMidpoint(int p,
    {   int key = p < q ? (
        Integer iObj = (Int
        return iObj.intValu
    }
    void toUnitCircle()
    {   for (int i=1; i<=nV
        {   Point3D P = (Poi
            float r = (float
                P.x * P.x + P
             P.x /= r; P.y /
        }
```

```
    }

    void writeFile()throws
    {   FileWriter fw = new
        for (int i=1; i<v.s
        {   Point3D P = (Poi
            fw.write(i + " "
                P.y + " " + P
        }
        fw.write("Faces\r\n
        for (int j=0; j<t.s
        {   Tria tr = (Tria)
            int a = tr.iA, b
            int mab = getMid
                mbc = getMid
                mca = getMid
            fw.write(a + " "
            fw.write(b + " "
            fw.write(c + " "
```

```
                fw.write(mab + "
            }
            fw.close();
        }
    }
```

Each edge of a triangle of the given polyhedron is also an edge of a neighboring triangle. Since for each triangle its vertices are specified in counter-clockwise order, the ordered vertex number pair *p*, *q* representing an edge of one of these two triangles will appear as *q*, *p* for the other triangle. To avoid adding the midpoint of this edge twice, we accept the pair *p*, *q* only if *p* is

less than *q*, as the test at the beginning of the method *addMidpoint* shows. Note that we process all given triangles twice, first, in *computeMidpoints*, to add the midpoint of every edge (exactly once) to the list of vertices *v*, and later, in *writeFaces*, to construct the new, smaller triangles. In the first of these two actions, we associate a new midpoint, say, vertex number *m*, with a certain edge *p*, *q*. This must be stored in such a way that later, in *writeFaces*, when we encounter this edge *p*, *q* again, we can use this pair to

find this same vertex number *m*. We can do this efficiently and conveniently by using a *hash table*, writing

```
Hashtable ht = new Hashtab
```

The pair *p*, *q*, or rather, a large integer *codeRadix* * *p* + *q*, where *codeRadix* is a large constant and *p* < *q*, is used as a key. By storing the pair (*key*, *m*)in the hash table *ht*, we can later retrieve the midpoint vertex number *m* using the same key. This explains both the statement

```
ht.put(new Integer(codeRad
```

in *addMidpoint* (called in *computeMidpoints*)and

```
Integer iObj = (Integer)ht
```

in *getMidpoint* (called in *writeFile*).

The sphere that program *SphTria.java* produces obviously depends upon its input file. The file *tetra.dat* of Section E.1, like *iscosa.dat*, describes a polyhedron consisting of equilateral triangles and has O as its center. Note that the latter is not the case with the file *tetra*1*.dat*, obtained by the

program *Rota3DTetra.java* because this program rotates the tetrahedron about the edge 1–2. Another polyhedron satisfying the conditions just mentioned is the octahedron, also discussed in Section E.1. This gives a better, though rather peculiar, result. If we start with the file *octa.dat*, describing the octahedron shown in Figure E.7(a), we obtain

$$octa.dat \Rightarrow sph32.dat \Rightarrow sph128.dat \Rightarrow sph512.dat$$



Figure E.7: Octahedron and three other polyhedra derived from it by program *SphTria.java*: (a) 8 faces (see Section E.1); (b) 32 faces; (c) 128 faces; (d) 512 faces

E.3 A TORUS

We will now discuss a program to construct a *torus*, as shown in Figure E.8. The input data of this program will consist of three program arguments:

- *n*, the number of small vertical circles; on each of these, *n* points are used as vertices to approximate the torus;
- *R*, the radius of a large horizontal circle containing the centers of the *n* smaller circles;

- the name of the output file.



Figure E.8: Torus (n = 30 and R = 2.5)

All small circles will have the same radius, r = 1. You can see

the large horizontal circle (with radius R) and one of the small vertical ones in Figure E.9. Since the smaller circles must not intersect each other, we require that

$R \geq r(=1)$



Figure E.9: Basic circles of a torus

A parametric representation of the large circle is

$$x = R\cos\alpha \quad y = R\sin\alpha \quad z = 0$$

If we take $\alpha = 0$ in these equations, we obtain the center of the small vertical circle shown in Figure E.9, which has the following parametric representation (where $r = 1$):

$$x = R + r\cos\beta \quad y = 0 \quad z = r\sin\beta$$

This small circle belongs to $i = 0$. By rotating it about the z-axis through angles $\alpha = i\,\delta$, where $i = 1, \ldots, n - 1$ and $\delta = 2\pi/n$, we obtain the remaining $n - 1$ small circles. As for the vertex numbers of the torus, we select n points

on the first small circle (corresponding to $i = 0$) and assign the integers 1, 2, …, n to them: the point obtained by using parameter $\beta = j\,\delta$ is assigned vertex number $j + 1$ ($j = 0, 1, \ldots, n - 1$). The next n vertices, numbered $n + 1, n + 2, \ldots, 2n$, lie on the neighboring circle, corresponding to $i = 1$, and so on. In general, we use the n^2 vertex numbers $i \cdot n + j + 1 (i = 0, 1, \ldots, n - 1; j = 0, 1, \ldots, n - 1)$.

We will now rotate the small vertical circle drawn in Figure E.9 about the z-axis through the

angle $\alpha = i\delta$. As follows from Section 3.2, this rotation can be written

$$[x' \quad y'] = [x \quad y] \begin{bmatrix} \cos\alpha & \sin\alpha \\ -\sin\alpha & \cos\alpha \end{bmatrix}$$

In our case the basic small circle lies in the *xz*-plane, so that $y = 0$, which reduces this matrix product to

$$x' = x \cos \alpha$$

$$y' = x \sin \alpha$$

(which we could also have derived directly from Figure E.9,

without using the above matrix multiplication).

As you can see in the following program, we use most of the above formulas in the inner loop, in which the variable *x* denotes the *x*-coordinate of a point of the small circle in the *xz*-plane (see Figure E.9), while *x*1 denotes the *x*-coordinate of that point after rotation through α about the *z*-axis:

```
// Torus.java: Generating
//     a large horizontal c
//     the centers of small
//     of n and R as well a
//     program arguments.
```

```
import java.io.*;
public class Torus
{  public static void main
   {  if (args.length != 3
      {  System.out.printl
            + "and a filena
         System.exit(1);
      }
      int n = 0;
      double R = 0;
      try
      {  n = Integer.value
         R = Double.valueO
         if (n<=2 || R<1)
            throw new Numb
      }
      catch (NumberFormatE
      {  System.out.printl
```

```
            System.out.printl
            System.exit(1);
        }
        new TorusObj(n, R, a
    }
}

class TorusObj
{  TorusObj(int n, double
   {  FileWriter fw = new
      double delta=2* Math
      for (int i=0; i<n; i
      {  double alpha=i* d
            cosa = Math.cc
         for (int j=0; j<n
         {  double beta =
            float x1 = (f
                  y1 = (f
                  z1 = (f
```

```
                    fw.write((i *
                        x1 + " " +
                }
            }
            fw.write("Faces:\r\n")
            for (int i=0; i<n; i++
              { for (int j=0; j<n;
                {  int i1 = (i + 1
                        a = i  * n
                        b = i1 * n
                        c = i1 * n
                        d = i  * n
                    fw.write(a + "
                }
            }
            fw.close();
        }
}
```

E.4 BEAMS IN A SPIRAL

Our next example is a spiral built from horizontal beams with length $2a$ ($a \geq 0.5$), width 1 and height 1. The bottom of the lowest beam lies in the xy-plane; this beam is parallel to the y-axis and its maximum x-coordinate is equal to a (see Figure E.10). Each next beam can be obtained by lifting the previous one a distance 1, and by rotating it about the z-axis though a given angle α.Thereare n beams. The integer n, the two real numbers a

and α (the latter in degrees) and the output file name, in that order, are supplied as program arguments.



Figure E.10: Vertex numbers of first beam

The beams in Figures E.11(a), (b) and (c) have lengths ($2a$ =) 2, 8 and 1, respectively, which implies that the beams are actually cubes in Figure E.11(c).



(a) $n = 4$, $a = 1$, $\alpha = 90°$ (b) $n = 18$, $a = 4$, $\alpha = 20°$ (c) $n = 18$, $a = 0.5$, $\alpha = 10°$

Figure E.11: Spirals of beams

The data files for program *HLines.java* to produce the three spiral images of Figure E.11 were generated by running program *Beams.java* three times as follows:

```
java Beams 4 1 90 FigE11a.
java Beams 18 4 20 FigE11b
java Beams 18 0.5 10 FigE1
```

Although we could have used the class *Rota3D*, discussed in Section 3.9, the rotation about the *z*-axis is as simple as a 2D rotation about O (see Section 3.2), so that we may as well program it directly, as is done in

the nested for-loop in program *Beams.java*, listed below:

```
// Beams.java: Generating
//     values of n, a and a
//     file name are to be
//     Uses: Point3D (Secti
import java.io.*;

public class Beams
{  public static void main
   {  if (args.length != 4
      {  System.out.printl
         "Supply n (> 0),
         "and a filename a
         System.exit(1);
      }
      int n = 0;
      double a = 0, alphaD
```

```
        try
        {  n = Integer.value
           a = Double.valueC
           alphaDeg = Double
           if (n <= 0 || a <
        }
        catch (NumberFormatE
        {  System.out.printl
           System.out.printl
           System.out.printl
           System.exit(1);
        }
        new BeamsObj(n, a, a
    }
}

class BeamsObj
{  FileWriter fw;
```

```
BeamsObj(int n, double
   throws IOException
{  fw = new FileWriter(
   Point3D[] P = new Pc
   double b = a - 1;
   P[1] = new Point3D(a
   P[2] = new Point3D(a
   P[3] = new Point3D(b
   P[4] = new Point3D(b
   P[5] = new Point3D(a
   P[6] = new Point3D(a
   P[7] = new Point3D(b
   P[8] = new Point3D(b
   for (int k=0; k<n; k
   {  // Beam k:
      double phi = k *
         cosPhi = Math.
      int m = 8 * k;
      for (int i=1; i<=
```

```
            {  double x = P[i
            float x1 = (float
                  y1 = (float
                  z1 = (float
            fw.write((m + i)
               "\r\n");
      }
   }
   fw.write("Faces:\r\n")
   for (int k=0; k<n; k++
   {  // Beam k again:
      int m = 8 * k;
      face(m, 1, 2, 6, 5)
      face(m, 4, 8, 7, 3)
      face(m, 5, 6, 7, 8)
      face(m, 1, 4, 3, 2)
      face(m, 2, 3, 7, 6)
      face(m, 1, 5, 8, 4)
   }
```

```
      fw.close();
   }
   void face(int m, int a,
   {   a += m; b += m; c +=
      fw.write(a + " " + b
   }
}
```

E.5 FUNCTIONS OF TWO VARIABLES

Although the programs *Painter.java*, *ZBuf.java* and *HLines.java* were primarily intended to represent solid objects, they can also be used for other purposes, such as displaying surfaces that correspond to functions of the form

$$z = f(x, y)$$

For example, Figure E.12 shows such a surface for the function

$$z = f(x, y) = \frac{10 \cos \sqrt{x^2 + y^2}}{2 + \sqrt{x^2 + y^2}} \qquad \text{(E.2)}$$



Figure E.12: Surface of a function $z = f(x, y)$ as specified by (E.2) and (E.3)

As usual, the *x*-axis points towards us, the *y*-axis points to the right and the *z*-axis points upwards. Note that each of the three coordinate axes is partly visible and partly hidden. The lines on the surface connect points (*x*, *y*, *z*), where

$$-6 \le x \le 6 \text{ and } -6 \le y \le 6, \text{ with step sizes } \Delta x = \Delta y = 0.25 \qquad \text{(E.3)}$$

Instead of dealing only with this particular function, we will discuss a very general program, based on an *expression evaluator*. Using a graphical user interface (as we also did in Section 6.6), we will enable the user to enter both an expression

for the function in question and the intervals and step sizes for *x* and *y*. Such expressions are similar to what we write in our programs, although the set of available operators and standard functions is very limited:

1. An *expression* consist of one or more terms, separated by + and −.

2. A *term* consists of one or more factors, separated by * and /.

3. A *factor* can be

1. a real number (such as 12.3, 4 or -25; number representations such as 1*e*7 are not allowed),

2. a variable *x* or a variable *y* (and no other variables),

3. an expression, as defined in point 1, written between parentheses, such as the

one occurring in 3 * (*x* + *y*),

4. a function call of one of the following three forms (and no others):

   sin(*expres*

   cos(*expres*

   pow(*expres*
   expression

The last three standard functions are the same as those in the

Math class of Java. For example, we write *pow*(*x*, 0.5) for $x^{0.5}$. There is no special *sqrt* function. As usual, blank spaces are allowed in expressions.

For example, the function given by Equation E.2 can be written as the following expression:

```
10 * cos(pow(x*x + y*y, 0.
```

As for the intervals and step sizes for *x* and *y*, we write, for example,

```
-6 (0.25) 6
```

indicating that the variable in question ranges from −6 to 6, with step size 0.25. The dialog box to be used to enter expressions, intervals and step sizes is shown in Figure E.13.


Function of two variables
z = f(x, y) =
10 * cos(pow(x * x + y * y, 0.5)) / (2 + pow(x * x + y * y, 0.5))
xMin (deltaX) xMax
-6 (0.25) 6
yMin (deltaY) yMax
-6 (0.25) 6
Output file name:
cospow.dat
Write file
Exit

Figure E.13: Dialog box for program Func.java

There is also a text field in which the user has to enter the name of

the output file. After filling in all text fields, the user can click the button *Write file* to generate the desired file. Since this does not terminate the program, there is also an *Exit* button. Although the program *Func.java* produces only a file, such as *cospow.dat* in this example, we can quickly see the 3D surface in question by executing the two programs *Func.java* and *HLines.java* at the same time. After pressing the button *Write file*, in the former program, we use *File |Open* in the latter to see the result. If we want to change any data, such

as shown in Figure E.13, we go back to *Func.java*, which is still running; after doing this, we click the *Write file* button and switch to *HLines.java* again, and so on.

If the expression entered for $z = f(x, y)$ cannot be interpreted because it is syntactically incorrect, the computer gives an audible signal. Such a beep also occurs if an interval or a step size is incorrect; this happens, for example, if *xMin* is greater than *xMax* – *deltaX*. It follows from this that error handling is not the strongest point of the program

we will discuss, and neither is its speed. However, although the given expression is not converted into more efficient intermediate code (such as postfix), it is much faster than the hidden- line program that follows; improvements with regard to error handling and efficiency were deliberately omitted because many readers will find the program already complex enough in its current form. After having a look at the program listed below, we will discuss some of its internal aspects.

```
// Func.java: A function c
```

```
import java.awt.*;
import java.awt.event.*;
import java.io.*;

public class Func extends
{  public static void main
   Func(){new FuncDialog(t
}

class FuncDialog extends D
{  TextField tfFun = new T
   tfX = new TextField (10
   tfFileName = new TextFi
   Button buttonWriteFile
          buttonExit = new

   FuncDialog(Frame fr)
   {  super(fr, "Function
```

```
addWindowListener(ne
{  public void windc
   {  dispose();
      System.exit(0)
   }
});

Panel p1 = new Panel
p1.add(new Label("z
p1.add(tfFun);
p2.add(new Label("xM
p2.add(tfX);
p2.add(new Label(" y
p2.add(tfY);
p3.add(new Label("Ou
p3.add(tfFileName);
p3.add(buttonWriteFi
p3.add(buttonExit);
setLayout(new Border
```

```
add("North", p1);
add("Center", p2);
add("South", p3);

buttonWriteFile.addA
{  public void actic
   {  float xa=0, dx
          ya=0, dy
      String sX = tf

      xa = (new xyEx
      sX = sX.substr
      dx = (new xyEx
      sX = sX.substr
      xb = (new xyEx

      String sY = tf
      ya = (new xyEx
      sY = sY.substr
```

```
                dy = (new xyEx
                sY = sY.substr
                yb = (new xyEx

                if (xa + dx >
                    ya + dy >
                {   Toolkit.ge
                    return;
                }
                String s = tfF
                   fileName =

                xyExpression x
                try
                {  xyE.generat
                }
                catch (IOExcep
        }
    });
```

```
    buttonExit.addActionLis
    {  public void actionPe
       {  dispose();System.
       }
    });

    Dimension dim = getTool
    setSize(6 * dim.width/1
    setLocation(dim.width/5
    show();
  }
}
class xyExpression
{  String buf;
   float x, y, lastNum;
   char lastChar;
   int pos;
   boolean OK;
```

```
xyExpression(String s){

void generate(float xa,
   float ya, float dy,
   throws IOException
{  FileWriter fw = new
   int nx = Math.round(
       ny = Math.round(
   float za = 1e30F, zb
outer:
   for (int j=0; j<=ny;
   {  float y = ya + j
      for (int i=0; i<=
      {  float x = xa +
         nr = j * (nx +
         float z = eval
         if (!OK)
         {  Toolkit.get
            break outer
```

```
                }
                if (z < za) za
                if (z > zb) zb
                fw.write(nr +
            }
        }
// x, y and z axes:
float dz = (zb - za)/
xa1 = Math.min(xa - 2
ya1 = Math.min(ya - 2
za1 = Math.min(za - 2
fw.write(++nr + " " +
fw.write(++nr + " " +
fw.write(++nr + " 0 "
fw.write(++nr + " 0 "
fw.write(++nr + " 0 0
fw.write(++nr + " 0 0
fw.write("Faces:\r\n"
```

```
    for (int i=0; i<nx; i
    {  for (int j=0; j<ny
       {  int k = j * (nx
             m = k + nx
          fw.write(k + "
          fw.write(k1 + "
          fw.write(k + "
          fw.write(m + "
       }
    }
    int k = (nx + 1) * (n
    fw.write(++k + " " +
    fw.write(++k + " " +
    fw.write(++k + " " +
    fw.close();
    System.out.println("R
}

boolean readChar()
```

```
{   char ch;
    do
    {   if (pos == buf.le
        ch = buf.charAt(p
    }   while (ch == ' ')
    lastChar = ch;
    return true;
}

boolean nextIs(char ch)
{   char ch0 = lastChar;
    if (readChar())
    {   if (ch == lastCha
        pos--;
    }
    lastChar = ch0;
    return false;
}
```

```
float eval(float x, flo
{  this.x = x; this.y =
   pos = 0;
   OK = true;
   return expression();
}

float expression()
{  float x = term();
   for (;;)
   {  if (nextIs('+'))
      if (nextIs('-'))
   }
   return x;
}

float term()
{  float x = factor();
   for (;;)
```

```
      {  if (nextIs('*'))
         if (nextIs('/'))
      }
      return x;
   }

   float factor()
   {  float v = 0;
      if (!readChar()) ret
      if (lastChar == 'x')
      if (lastChar == 'y')
      if (lastChar == '(')
      {  v = expression();
         if (!nextIs(')'))
         return v;
      }
      char ch = lastChar;
      if (ch == 'c'      //
         || ch == 's'    //
```

```
      || ch == 'p') //
    { while ((OK = reac
      if (!OK) return 0
      float arg = expre
      if (ch == 'p')
      {  if (!nextIs(',
         double exponen
         v = (float)Mat
      }
      else
         v = (float)(ch
      if (!nextIs(')'))
      return v;
    }
    pos--;
    if (number()) retur
    OK = false;
    return 0;
}
```

```
boolean number()
{  float x=0;
   int nDec = -1;
   boolean neg = false
   do
   {  if (!readChar())
      if (lastChar ==
      {  neg = true;
         if (!readChar
         break;
      }
   }  while (Character
   if (lastChar == '.'
   {  if (!readChar())
      nDec = 0;
   }
   if (!Character.isDi
   for (;;)
```

```
            {   if (lastChar ==
                if (Character.is
                {   x = 10 * x +
                    if (nDec >= 0
                }   else
                {   pos--;
                    break;
                }
                if (!readChar())
             }
            while (nDec > 0){x
            lastNum = (neg ? -
            return true;
        }
}
```

The given expression is evaluated when the first part of the output file is generated. In the class

xyExpression we find the method *generate*, in which, five lines after the label *outer*, the following call to *eval* occurs:

```
float z = eval(x, y);
```

This method *eval* calls the method *expression*, who set ask is to scan an expression, stored in the array *buf*, and to return its value. According to our above definition of *expression*, defining an expression as a sequence of terms separated by + and − operators, the method *expression* calls the method *term*, which scans a term and

returns its value, and so on. This way of *parsing*, that is, analyzing expressions that satisfy a given *grammar*, is referred to as *recursive descent*. This adjective *recursive* will be clear if we note that our above syntactic definition of *expression* and the corresponding method are recursive. An *expression* cancontaina *factor* that again contains an *expression*. Accordingly, in the program, *expression* calls *term*, which calls *factor*, which may again call *expression*. We immediately evaluate the syntactic entities we

are dealing with, or, as we normally say, we *interpret* the source code. Instead, we might have generated intermediate code. More information about recursive descent parsing can be found in Ammeraal (1996).

In the program, parsing is done by using two simple methods, *readChar* and *nextIs*, as well as the variable *lastChar*, all belonging to the class *xyExpression*:

```
boolean readChar()
```

This method scans the next

character, if possible, places this in the variable *lastChar* and returns *true*. If this is not possible because the end of the expression is encountered, it returns *false*. This methods skips any blank spaces.

`boolean nextIs(char ch)`

This method tests if the next character to be scanned is equal to the argument *ch*. If so, it scans this character and returns *true*; if not, it leaves the scan position unaltered and returns *false*.

After this discussion of parsing (which is unusual in a book on computer graphics) let us now turn to the graphics aspects of this program. It goes without saying that the vertices of a polygon, as specified in our 3D data files after the word *Faces*, should lie in the same plane. This is obviously the case for rectangles (or squares) such as 7-8-12-11 in Figure E.14(a) if we regard these as lying in the plane $z = 0$.



Figure E.14: Two triangles with an invisible common edge forming a rectangle

However, the corresponding four points on the surface may or may not lie in the same plane. We therefore prefer triangles to rectangles in this case.

Remember, the three points of a triangle always lie in the same plane. Instead of the rectangle 7-8-12-11, we can specify the two triangles 7-8-12 and 7-12-11. However, we must pay attention to these two aspects:

1. Diagonals, such as 7–12, must not be drawn; we solve this problem by using minus signs, as discussed in Section 6.4.

2. Each triangle has two sides; since we do not know in advance which

will be visible, we have to specify both. Recall that we have discussed this subject of 'individual faces' in Section 6.5.

According to this second point, the vertices of each triangle in Figure E.14(b) will occur twice in the data file: clockwise and counter-clockwise. Using minus signs, as discussed in the first point, we use four lines in the data file for the 'rectangle' k, k + 1, m + 1, m of Figure E.14(b), as shown below:

k	$-(m + 1)$	$k + 1.$	(lower-right, clockwise)
$k + 1$	$m + 1 - k.$		(lower-right, counter-clockwise)
k	$-(m + 1)$	$m.$	(upper-left, counter-clockwise)
m	$m + 1$	$-k.$	(upper-left, clockwise)

You can find the code that writes

these four triangles to a file in the method *generate*.

Appendix F: Hints and Solutions to Exercises

Numbers of pixels:

1.1

```
g.drawLine (10, 20,
g.drawRect (10, 10,
g.fillRect (10, 10,
```

Program to draw many squ

```
// ManySq.java: This
//    consisting of k
//    Each edge is di
//    (1 - q)   : q. T
                  argume

import java.awt.*;
import java.awt.even
```

```
public class ManySq
{  public static voi
   {  if (args.lengt
      {  System.out.
         System.exit
      }
      int n = Intege
          k = Intege
      float q = Floa
      new ManySq(n,
   }
  ManySq(int n, in
  {  super("ManySq
     addWindowList
      {public void
                Wind
     add("Center",
     setSize (600,
```

```
            show();
        }
    }

    class CvManySq ext
    {   int centerX, ce
        float p0, q0;

1.2     CvManySq(int nn


        int iX(float x)
        int iY(float y)

        public void pai
        {   Dimension d
            int maxX = d
                minMaxXY
            centerX = ma
```

```
float r = 0.
for (int x=0
for (int y=0
{  float xCn
          yCn
      xA, yA
      xA1, y
   if (x % 2
   xA = xD =
   yA = yB =
   for (int
   {  g.draw
      g.draw
      g.draw
      g.draw
      xA1 =
      xB1 =
      xC1 =
```

```
                    xD1 =
                    xA = x
                    yA = y
                }
            }
        }
    }
```

1.3

To draw all edges as exactl
exactly on the edges of thei
pair of very small squares (
twice as large as those of t

The radius *r* of the circumsc
on this radius *r*, the followin
may be helpful:

```
int iX(float x){retu
```

```
int iY(float y){retu

void drawLine(Graphi
{  g.drawLine(iX(xA)
}
...

float halfr = r/2, h
  w = r * (float)Mat
                marg
int nhor = (int)Math
   nvert = (int)Mat
marginleft = -rWidth
               horpit
marginbottom = -rHei
for (int i=0; i<nhor
{  float x = marginl
    y0 = marginbotto
               hexago
```

1.4

```
        int m = nvert -
    // There will be nve
                    ...
    // while there will
                    ...
    // Special case: if
                      by
    // horpitch/2 becaus
                      the
    // right.
       if (nvert == 1 &&
          x += horpitch/
       for (int j=0; j<m
       {  float y = y0+j
          drawLine(g, x
          drawLine(g, x
          drawLine(g, x
          ...
```

We begin by computing the

$$L = \sqrt{u_1^2 + u_2^2}$$

where

$$u_1 = x_B - x_A$$

$$u_2 = y_B - y_A$$

1.5

Since there should be a das
are about equal to *dashLen*

$$L = (2n - 1) \times dashLength$$

to compute *n*, the number c
denoting the dashes by *i* =
endpoints ($x_A + 2ih_1$, $y_A + 2$

2.1 After rotating the vector **v**
vector $(-v_2, v_1)$. Setting **v**
points D and C by adding

2.2 To determine the position
on one of the three sides
Section 2.10. If this is not
method *insideTriangle* of
orientation of A, B and C,
orientation is clockwise, w
of *insideTriangle*, so that
required. If P lies neither

Section 2.11 shows how t
perform this computation
BC and CA (or rather the

2.3

then use the method *proje*
triangle side in question (o
line segment PP′. If the pr
connect this point to the si
has been used. For examp
we can draw P′B.

Using the vector **AB** = **u** =
represent the line through

$$\mathbf{A} + \lambda \mathbf{u}$$

Similarly, with **CD** = **v** = (*v*
C and D is represented by

$$\mathbf{C} + \lambda \mathbf{v}$$

We find the intersection po

$$\mathbf{A} + \lambda\mathbf{u} = \mathbf{C} + \lambda\mathbf{v}$$

for λ (rewriting this vector
y- coordinates of A and C
computed in this way to fir

2.4 $$\mathbf{S} = \mathbf{A} + \lambda\mathbf{u}$$

When deriving the desired
expression $u_2v_1 - u_1v_2$ (w
and CD do not have a unic
coincide. Since the points
small) rounding-off errors,

$$determinant = 0$$

with this one:

$$|determinant| \leq epsilon$$

where *epsilon* is some ver
of length and in view of the

$$epsilon = 10^{-3}(u_1^2 + u_2^2 + v_1^2 + v_2^2)$$

To construct the bisector o
v = **BC**/|**BC**|. We can view
C, respectively. Since both

$$\mathbf{w} = \mathbf{u} + \mathbf{v}$$

2.5

can then be regarded as a
so that, with parameter α,

$$\mathrm{B} + \alpha \mathbf{w}$$

denotes the bisector of an
side AC can then be found

Using **AB**=**u**=(u_1, u_2)=(x_B
following vector form for th

$$\mathbf{A} + 0.5\mathbf{u} + \lambda\mathbf{v} \qquad \text{(F.1)}$$

To find the circumcenter D

$$\mathbf{B} + 0.5\mathbf{w} + \mu\mathbf{t} \qquad \text{(F.2)}$$

for the perpendicular bisec
lines by solving the vector

2.6

$$\mathbf{A} + 0.5\mathbf{u} + \lambda\mathbf{v} = \mathbf{B} + 0.5\mathbf{w} + \mu\mathbf{t}$$

for λ (or μ). Then the circu

value λ in Equation (F.1). A
and *iY* to convert real logic
the circle through A, B and

```
int xLeft = iX(xD -
    yTop = iY(yD +
g.drawOval(xLeft, y
```

Compute the center C and
2.6). Although there is a m
purpose because it require
if *r* is large, this may cause
of the arc. We therefore s
this by using *Point2D* obje
of P, Q and R into account
Section 2.13), we can writ

```
double alpha = Math
```

```
        beta  = Math
if (Tools2D.area2(P
   arcCcw(g, C, r,
else
   arcCcw(g, C, r,
```

The method *arcCcw*, used
the arc with start and end
C and radius *r*:

2.7

```
void arcCcw(Graphic
   double alpha, do
{  double pi2=2* Ma
   // Reduce delta
   delta = (delta +
   int X0=0, Y0=0,
      n = (int)Math
   double theta = d
   for (int i=0; i<
```

```
        {   double phi =
                x = C.x +
                y = C.y +
            int X = iX((f
            if (i > 0) g.
            X0 = X; Y0 =
        }
    }
```

2.8

We can use the first of the
D' of D on AB. Since the c
ABC, we compute the unit
v|, which start at B and pc
factor λ, so that **BM** = λ *v*
using μ =|**BD′**|, we can cc
on BC and the center M a
the arc is *r* =|**MD′**|. We ca

the arc by choosing betwe
orientation of the points A,

2.9 Refer to Exercise 2.8 for b
two lines. This will provide
radius of each circle as the
have discussed the distanc

2.10 Use vector **AB** = (u_1, u_2) t
+ 0.5 $\{(u_1, u_2) + (-u_2, u_1)$

3.1
$$M = \begin{bmatrix} s_x & 0 & 0 \\ 0 & s_y & 0 \\ x_C(1-s_x) & y_C(1-s_y) & 1 \end{bmatrix}$$

3.2 Similar to Exercise 3.1.

For shearing a set of points
shearing equations at the e

$$x' - x_C = (x - x_C) + a(y - y_C)$$

$$y' - y_C = (y - y_C)$$

which reduces to $x' = x + a$

3.3

The sharing operation will t
horizontal axis, so that we c
Therefore, for some large v
C(x_C, y_C) and radius r by c
circle:

$$x_i = x_C + r \cos i\theta$$

$$y_i = y_C + r \sin i\theta$$

where θ = 2 π/ *n* and *i* = 0,
connecting these points by
we first subject each x_i to th

3.4

Just compute the product *A*
example, the upper-left eler
product of the first row of *A*
$a_{11}(a_{22}/D) + a_{12}(-a_{21}/D) =$

If there are many points for
within a single triangle (or o
the following class is more
since most of the work is d
called only once for that tria

```
class TriaTest
{  private Point2D C
   private double a1

   TriaTest(Point2D
   {  this.C = C;
      a1 = A.x - C.x
      b1 = B.x - C.x
      det= a1 * b2 -
      if (det != 0)
      {  c1 = b2/det
         d1 = -b1/de
      }
   }

   double area2(){re

   boolean insideTri
   {  double p1 = P.
```

3.5

```
                lambda, mu;
            return (lambda
                (mu = p1 *
                lambda + m
        }
    }
```

4.1

Adapt the Java program for
endpoints towards the midd
beforehand or check on-the
middle. There may be one
an odd or even number of p
after exiting the loop. Check
consisting of one or two pix
any two endpoints P and Q

You should add a second fo
example, the calls to *putPix*

4.2 their second. If $|y_Q - y_P| \leq |$
second.

The following program prod
to specify the two endpoint
circle.

```
// Bresenham.java: B
//                 d
import java.awt.*;
import java.awt.even
import java.util.*;

public class Bresenh
{  public static voi

   Bresenham()
   {  super("Bresenh
```

```
            addWindowListe
             {public void
                    {Syst
             setSize (340,
             add("Center",
             show();
        }
    }
    class CvBresenham ex
    {  float rWidth = 10
       int centerX, cent

        void initgr()
       {  Dimension d;
          d = getSize();
          maxX = d.width
          maxY = d.heigh
          pixelSize = Ma
          centerX = maxX
```

```
}
    int iX(float x
    int iY(float y

    void putPixel(
    {  int x1 = x
       g.drawOval(
    }

    void drawLine(
    {  int x = xP,
          c, M, xI
       if (HX < 0)
       if (HY < 0)
       if (HY <= H
       {  c = 2 *
          for (;;)
          {  putPi
             if (x
```

4.3

```
                x +=
                D +=
                if (D
            }
        }
        else
        {   c = 2 *
            for (;;)
            {   putPi
                if (y
                y +=
                D +=
                if (D
            }
        }
    }

    void drawCircle(Grap
    {   int x = 0, y = r,
```

```
while (x < y)
{  putPixel(g, xC
   putPixel(g, xC
   putPixel(g, xC
   putPixel(g, xC
   x++; E += u; u
   if (v < 2 * E)
   if (x > y) bre
   putPixel(g, xC
   putPixel(g, xC
   putPixel(g, xC
   putPixel(g, xC
  }
}

void showGrid(Gra
{  for (int x=dGr
      for (int y=
         g.drawLi
```

```
    }

    public void paint
    {  initgr();
       showGrid(g);
       drawLine(g, 1,
       drawCircle(g,
    }
}
```

Since an unknown number o
concept of *Vector*, as we ha
objects representing the ver
class *CurveSegment* andto
shows:

```
class CurveSegment
{  Point2D[] P;
```

```
        CurveSegment(Poin
        ...
    }
```

4.4 Writing

```
Vector curves = new
```

and using the array

```
Point2D[] P = new Po
```

containing the most recent f
we can add a new curve se

```
curves.addElement(ne
```

The object *curves* can store
elements.

In program *Bspline.java* of
terminate the process of ex

```
char ch = evt.getKey
```

in the method *keyTyped* so
different characters entered

4.5 Use a *Vector* element for ea
statement

```
V.copyInto(P);
```

in the *paint* method of progr
P. Using a different *Vector* c
The deletion of the last curv

```
curves.setSize(curve
```

Represent the grid on the s
ten equidistant vertical lines
lines, transform the device c
9, and use these gridpoint c
been defined. On the right c

$$algorithm[0], algorithm[1], \ldots, algorithm[7]$$

below each other, where th

```
String[] algorithm =
    "int x=xP,y=yP,d=
    "    m=2*(yQ-yP);
    "for (;;)",
    "{ putPixel(g, x,
    " if (x == xQ) br
    " x++; d += m;",
    " if (d > dx){y++
    "}"};
```

As soon as the user has de
highlighted, indicating that tl
this by using a variable, say
should be displayed in red (
black). All lines *algorithm*[*j*]
statement to test the value

4.6 fragment of the following fo

```
addMouseListener(new
{  public void mouse
   {  // When the mo
      // it is on th
      // action, if
      int xClick = 0
      // Get the coo
      xClick = evt.g
      yClick = evt.g
      // Check to se
      if (xClick, yC
```

```
                stepPressed
            else
            if (xClick, yC
            {   ...
            }
            repaint();
        }
});
```

In the switch statement just
program line (stored in the
the variable *i* mentioned ab
correct program line in red

As Figure 5.11 shows, nine
method of program *CubePe*
fragment:

```
// Visible edges:
line(g, 0, 1); line(
line(g, 1, 2); line(
line(g, 5, 6);

// Invisible edges:
g.setColor(Color.blu
line(g, 0, 3); line(
```

If you did Exercise 1.5 and
available, you may be able

```
dash(g, 0, 3); dash(
```

while adding the following m

5.1

```
void dash(Graphics g
{  Point2D P = obj.v
   Lines.dashedLine(
```

}

Figure F.1 shows the result



Figure F.1: Dashed lines

5.2

There are two *fillPolygon* m
other taking two arrays *x* a
device coordinates, using th
before each of the three ca

5.3

To replace Figure 5.11, beg
plane, and by assigning the
second cube. With this sket
you can easily update the p
objSize, which is used to co

The following program dem
a simple case: a line segme
the canvas. Every 20 ms, th
origin O (in the center of the

that of a running clock with

```
// Anim.java: Animat
import java.awt.*;
import java.awt.even
public class Anim ex
{  public static voi

   Anim()
   {  super("Animati
      addWindowListe
       {public void
                {Syst
      add("Center",
      Dimension dim
      setSize(dim.wi
      setLocation(di
      show();
   }
}
```

```
class CvAnim extends
   implements Runnab
{  float rWidth = 10
   int centerX, cent
   Dimension d;
   Image image;
   Graphics gImage;

   float alpha = 0;
   Thread thr = new

   public void run()
   {  try
      { for (;;)
        {  alpha +=
           repaint()
           Thread.sl
        }
      }
```

5.4

```
    catch (Interru
}

CvAnim(){thr.star

void initgr()
{   d = getSize();
    int maxX = d.w
    pixelSize = Ma
    centerX = maxX
    xC = rWidth/2;
}

int iX(float x){r
int iY(float y){r
public void updat
public void paint
{   initgr();
    if (w != d.wid
```

```
            {    w = d.widt
                 image = cr
                 gImage = i
            }
            float r = 0.8F
                x = r * (fl
                y = r * (fl
            gImage.clearRe
            // Every 20 ms
            // Each time,
            // different p
                gImage.draw
                g.drawImage
        }
    }
```

The following program prod
Remember, this program w

available in the current direc

```
// CubRot2.java: Two
//    Uses: Point2D (
//          Point3D,
import java.awt.*;
import java.awt.even

public class CubRot2
{  public static voi

   CubRot2()
   {  super("Rotatin
      addWindowListe
       {public void
                {Syst
      add("Center",
      Dimension dim
      setSize(3 * di
      setLocation(di
```

```
            show();
        }
    }

    class CvCubRot2 exte
        implements Runnab
    {   int centerX, cent
        Obj2 obj = new Ob
        Image image;
        Graphics gImage;

        double alpha = 0;
        Thread thr = new

        public void run()
    {   try
        {   for (;;)
            {   alpha += 0.
                repaint();
```

```
                Thread.slee
            }
        }
        catch (Interrupte
    }

    CvCubRot2(){thr.star
    public void update(G

    int iX(float x){retu
    int iY(float y){retu

    void line(int i, int
    {   Point2D P = obj.v
        gImage.drawLine(i
    }
    public void paint(Gr
    {   Dimension dim = g
        int maxX = dim.wi
```

```
centerX = maxX/2;
int minMaxXY = Ma
obj.d = obj.rho *
obj.rotateCube(al
obj.eyeAndScreen(
if (w != dim.widt
{   w = dim.width;
    image = create
    gImage = image
}
gImage.clearRect
// Horizontal edg
line (0, 1); line
// Horizontal edg
line (4, 5); line
// Vertical edges
line (0, 4); line
// Same for secon
line (8, 9); line
```

5.5

```
        // Horizontal edg
           line (12, 13);
           // Vertical ed
           line (8, 12);
           g.drawImage(im
        }
     }

     class Obj2 // Contai
     {    float rho, theta
          Point3D[] s, w;
          Point2D[] vScr;
          float v11, v12,
            v32, v33, v43,
            xe, ye, ze, ob

          Obj2()
          {   s = new Point
              w = new Point
```

```
vScr = new Po
// Bottom sur
s[0] = new Po
s[1] = new Po
s[2] = new Po
s[3] = new Po
// Top surfac
s[4] = new Po
s[5] = new Po
s[6] = new Po
s[7] = new Po
// Bottom sur
s[8] = new Po
s[9] = new Po
s[10] = new P
s[11] = new P
// Top surfac
s[12] = new P
s[13] = new P
```

```
            s[14] = new P
            s[15] = new P
            rho = 15; //
        }

    void rotateCube(doub
        {   Rota3D.initRo
            for (int i=0;
                w[i] = Rot
            Rota3D.initRo
            for (int i=8;
                w[i] = Rot
        }

        void initPersp()
        {  float costh =
                   sinth =
                   cosph =
                   sinph =
```

```
        v11 = -sinth;
        v12 = -cosph *
        v13 = sinph *
        v21 = costh;
        v22 = -cosph *
        v23 = sinph *
        v32 = sinph;
        v33 = cosph;
        v43 = -rho;
    }

    void eyeAndScreen
    {   initPersp();
        for (int i=0;
        {   Point3D P =
            float x = v
            float y = v
            float z = v
            Point3D Pe
```

```
                vScr[i] = n
                   Point2D(
            }
        }
    }
```

The desired input file is list

6.1

```
1    1-1   0
2    1 1   0
3   -1 1   0
4   -1-1   0
5   0 0    -2
6   0 0    2
Faces:
1 2 3 4.
4 3 2 1.
5 6.
```

6.2

Use the vertices 1, 2 and 3
lies inside the triangle. Let
endpoints as in the above
use the invisible lines 1–4,
6.14. In other words, defir
polygon, specified as a se
1, 2, 4, 2, 3, 4, and so on,

See Section 6.4 for holes
the same structure as the
faces. Based on Figure F.2

1 2 3 -7 6 5 8 7 -3 4.

6.3



Figure F.2: One of the
6.27

```
1  2  3  -7  6  5  8  7  -3
```

A simple solution to this pr
edges (visible as well as ir
are drawn as solid lines w

words, every visible edge
effect of a solid line. Altho
dashed lines, we obtain be
required for screen output
and ends with a dash of th
modify the program file *HL*

1. Disable back-fac
   buildLineSet.

```
if (n>2&& po
```

2. Insert the followi

6.4

```
void dashedL
        float
{  float u1
        L = (f
   int n = M
   float h1
   for (int
```

```
        {   float
            drawLi
        }
    }
```

3. Just before the c
   the program file,

   ```
   dashedLine(g
   ```

A program to generate an
4and *n* = 150) to produce
Exercise 6.6 below for the

```
// BookView.java: G
import java.io.*;

public class BookVi
```

```
{  public static vo
      throws IOExce
   {  if (args.leng
      {  System.out
         "Supply nr
         "as progra
         System.exi
       }
       int n;
       float w, h;
       FileWriter f
       n = Integer.
       w = Float.va
       h = Float.va
       fw = new Fil
       int spineTop
       float theta
       float xTop =
       fw.write(spi
```

6.5

```
fw.write(spi
for (int i=0
{  float phi
      y = w
      z = w
   outerTop
   fw.write(
      y + "
   fw.write(
      y + "
}
fw.write("Fa
for (int i=0
{  outerTop
   fw.write(
      + oute
   fw.write(
      + oute
}
```

```
            fw.close();
        }
    }
```

Before writing the program
mathematical expressions
discuss how this can be d
program that generates 3D

The model of a sphere in
north pole. Since it is given
horizontal planes between
latitude, on the sphere. Th
vertex (other than the two
horizontal and a vertical ci
poles. There are $n - 2$ re
faces is equal to $(n - 2) \cdot$

horizontal edges. Altogeth
below, $2(n^2 - n + 1)$ vertic
5.3. Using a sphere radius
their z-coordinate

$$z = \cos\varphi$$

Writing $\delta = \pi/n$, we will or
angles:

6.6

$$\varphi = i \cdot \delta \; (i = 1, 2, \ldots, n-1)$$

On each of these circles w

$$\theta = j \cdot \delta \; (j = 0, 1, \ldots, 2n-1)$$

Thus, each pair (i, j) is ass
associating a vertex numb

with vertex number 2 on ci
vertex number available fo
2, and so on. In general, c
each circle there are $2n$ ve

$$\text{number for vertex } (i,j) = (i-1)\cdot 2n + 2 + j$$

As we have seen in Sectic
computed as $x = \sin\varphi$ co
upon i and j as shown abo

Finally, we have to assign
$1 + (n - 1) \cdot 2n$ vertex nu

$$1 + (n-1)\cdot 2n + 1 = 2(n^2 - n + 1)$$

which is also the total num

6.7 Analyze this problem in the
(at the south pole) and eac
and clockwise, since eithe
Exercise 6.6, we had bette
sphere in this problem, so
circle that we use, giving a

6.8 Use program arguments fo
and *z*. Remember, the wo
specify the vertices of *all* c

Let us start with a torus su
as its center, and let the s
x-axis. We will make the s
their positions are differen
completely determined by

must be wide enough for t
≥ 2.

For each vertex of the first
have seen in Section E.3 t
numbers i and $i + n^2$ for ea
torus, we have to shift the
we turn it through the x-ax

6.9 computations are required
*Rota*3D of Section 3.9 in t
corresponding vertex $i + n$

Although, in the first part c
order of the vertex numbe
lines of the following form

i	x	y	z
$i+n^2$	x'	y'	z'

Similarly, in the second pa
in the second face of eacl
the desired program for tw
statements.

If necessary, you might ref
Section 6.6 for the cylindri
that the situation here is si
Cylinder.java with *rInner* =

6.10 You can use program *Bea*
constructed, or you can us
you also perform a transla
step. As for the railing, rec
segments specified as two
Section 6.5.

In Figure F.3, the two outer
but the corresponding inner
and 19 indicate. The latter f
invisible if we view the objec
shows.



Figure F.3: Object nearb
visible



Figure F.4: The same ob
invisible

7.1 Recall that, with eye coordi
the *y*-axis upwards and the
inner face that is visible in F
Figure F.4. Estimating the n
value *h*, as specified in the

for this face, we find:

1. is almost equal to
   the negative *x*-axi

2. is almost zero, bu
   slightly from abov

3. is almost zero, bu
   the back.

These values, and in particu
distance. By contrast, the ir
vector from the viewpoint E
depends on the viewing dist
drawing a sketch similar to
example. As a result, you w
but positive in Figure F.4. Tl
determine if a face is a bac

not that of *c*. The correct pr
equivalent to back-face culli
points: if this orientation on
object is viewed from outsic
of *h* would be equivalent to
instead of the screen coord
image points. This would w
may result in wrongly decid
if the object is viewed from
Recall that we also briefly c

7.2 We can use back-face culli
are visible. Refer to the solu
implementation of animatior

In the previous exercise we
rotation about a vertical axi

7.3

the cube unchanged. This is
now want to use two rotatio
rotating each cube about or
rotation speeds, the latter s
angles in each step. As in th
to supply only one method r
occurs.

Change the class *CvPaint* (
follows:

1. At the beginning o
   line

   ```
   implements Ru
   ```

2. After {, add the fo

   ```
   Image image;
   Graphics gIma
   ```

```
double sunThe
Thread thr =
```

3. Insert the method
Exercise 5.4, but
spherical coordina
variables *obj.sun*
value for *sunPhi*,
constant. By using
= 1, the light vecto

7.4

4. Insert the program

```
int w, h;
CvPainter(){t
public void u
```

5. Modify the *paint* m
glmage as well as

done in program *A*
Exercise 5.4.

7.5 For the format of the desire
for the program to generate
and Appendix E, if necessa

In the program *FractalGran*
draws a line from the curren
yLast + *dy*), which, after the
(*xLast*, *yLast*).

```
case 'F': // Step fo
   // Start: (xLast,
   if (depth == 0)
   {  double rad = M
      dx = len * Mat
```

```
            drawTo(g, xLas
        }
```

8.1

Besides *xLast* and *yLast*, in
the cornerpoints that we wil
time, instead of drawing a li
one from the current point (
approximate the rounded co
automatically stored as the
again. Then update the vari
and *dy*, respectively, so the
second line, from the curren
dy/4). Note that this last line
fragment, since a quarter o
now replaced with the appr

In the *paint* method of the p

8.2 to *drawKoch* preceded by s
calls, each preceded by ass
starts in the right direction.

8.3 You can generate a random
and derive the thickness of
line of any thickness can be

This hint is based on the pro
Tree2 of Section 8.3. In this

$$strX = "F[+X]F[-X]+X"$$

8.4 Each time the second *F* in t
have a leaf at its end. So in
draw a leaf in the *case F* pa
counter *i* for *strX* is equal to

approximates the shape of
of *drawOval*) whose center
the branch in question.

Use methods *iX* and *iY* to c
and *fy* for the inverse conve
can use

```
int iX(float x)
{   return (int)(xDev
}

float fx(int x)
{   return xLogCenter
}
```

As usual, we use *d* defined

```
Dimension d = getSiz
```

Let us denote the current b
xRight. For example, we ca
device coordinates, that is,
mouseReleased, we obtain
boundaries of the cropping
obtain the corresponding lo

```
xLeftNew = fx(xs);
xRightNew = fx(xe);
```

8.5

Then these new values are

```
pixelSize = Math.max
```

```
xLogCenter = (xLeft
```

Let us now discuss the plau
rigorously). Normally, *mous*
smaller than the width of th

new logical *x*-range (*xLeft*, *
pixelSize. As a result of the
method *iX* will be larger tha
larger scale. As for panning
user is on the left half of the
logical *x*-range will be small
computed by the method *iX*
image displayed in the sele
displayed in the center of th
to the right.

8.6 Modify the *MandelbrotZoom*
Combine the two programs

Bibliography

Ammeraal, L. (1996) *Algorithms and Data Structures in C++*, Chichester: John Wiley.

Ammeraal, L. (1998) *Computer Graphics for Java Programmers*, Chichester: John Wiley.

Arnold, K., and J. Gosling (1996) *The Java Programming Language*, Reading, MA: Addison-Wesley.

Burger, P., and D. Gillies (1989) *Interactive Computer Graphics*, Wokingham: Addison-Wesley.

Coxeter, H. S. M. (1961) *Introduction to Geometry*, New York, NY: John Wiley.

Flanagan, D. (1997) *Java in a Nutshell*, 2nd Edition, Cambridge, MA: O'Reilly.

Foley, J. D., A. van Dam, S. K. Feiner, J. F. Hughes, and R. L. Phillips (1990) *Computer Graphics* –

Principles and Practice, 2nd Edition, Reading, MA: Addison-Wesley.

Foley, J. D., A. van Dam, S. K. Feiner, and J. F. Hughes (1994) *Introduction to Computer Graphics*, Reading, MA: Addison-Wesley.

Glassner, A. S. (1990) *Graphics Gems*, Boston, MA: Academic Press.

Gosling, J., and F. Yellin (1996) *The Java Application Programming*

Interface, Reading, MA: Addison-Wesley.

Hearn, D., and M. P. Baker (1986) *Computer Graphics*, Englewood Cliffs, NJ: Prentice-Hall.

Hill, F. S., Jr (2001) *Computer Graphics Using Open GL*, 2nd Edition, Prentice-Hall.

Horstmann, C. S., and G. Cornell (1997) *Core Java*, Mountain View, CA: Sun Microsystems.

Kreyszig, E. (1962) *Advanced Engineering Mathematics*, NewYork, NY: John Wiley.

Newman, M. N., and R. F. Sproull (1979) *Principles of Interactive Computer Graphics*, New York, NY: McGraw-Hill.

O'Rourke, J. (1993) *Computational Geometry in C*, Cambridge: Cambridge University Press.

Rokne, J. G., B. Wyvill,

and X. Wu (1990) *Fast Line Scan-Conversion*, *ACM Transactions on Graphics*, Vol. 9, No. 4, 376–388.

Salmon, R., and M. Slater (1987) *Computer Graphics – Systems & Concepts*, Wokingham: Addison-Wesley.

Watt, A. (1989) *Fundamentals of Three-Dimensional Computer Graphics*, Wokingham: Addison-Wesley.

Wu, X. and J. G. Rokne (1987) *Double-Step Incremental Generation of Lines and Circles*, *Computer Vision, Graphics, and Image Processing*, Vol. 37, 331–344.

Colour Plates



Plate 1: Fillet or rounded corner, Exercise 2.8



Plate 2: Inscribed circle and three excircles of triangle, Exercise 2.9



Plate 3: Tree of Pythagoras, Exercise 2.10



Plate 4: Demonstration of Bresenham's algorithm, Exercise 4.6



Plate 5: Two colored cubes, captured when rotating independently, Exercise 7.3



Plate 6: Three beams partly hiding each other, see Sections 6.7, 7.3 and 7.4

Plate 7: Beams in a spiral, see Section E4, Appendix E



Plate 8: An open book, see

Exercise 6.5



Plate 9: Solid letter A as an object with a hole, see Section



Plate 10: A cube of cubes, Exercise 6.8



Plate 11: Dodecahedron, see Section E1, Appendix E



Plate 12: Two tori, Exercise 6.9



Plate 13: A function of two variables, see Section E.5, Appendix E. The expression 10. sin(pow(x*x + y*y, 0.5))/(1 + pow(x*x + y*y, 0.2)) was supplied to program Func.java, with ranges and step sizes for

x and y specified as .15(0.25)15



Plate 14: Tree with green leaves, Exercise 8.4

Plate 15: Sample output of

program *MandelbrotZoom.java*, see Section 8.4



Plate 16: Julia set, as discussed at the end of Section 8.4

Index

A

ActionListener 283
actionPerformed 281

adapter 284

addActionListener 282
addMouseListener 285
animation 175, 354
anisotropic mapping mode 15

anonymous class 283

arc 345
*area*2 (for polygon) 43

*area*2 (for triangle) 40

AWT 2

Index

B

back-face culling 220

background color 6

B´

ezier curve 120

beams 323

BorderLayout 202

Bresenham's algorithm for circles 103

Bresenham's algorithm for lines 92

B-spline curve fitting 130

Index

C

camera 140

canvas 3

ccw (for polygon) 42

circle 102

circumcenter 344

circumscribed circle 59

client rectangle 4

Cohen-Sutherland line clipping 107

color 225

complex numbers 265
concave polygon 41
contains (Java method) 47
continuous interval 14
coordinate system 33
coordinate system (changing) 78
counter-clockwise 39, 75, 191
cropping 271
cross product 37
cube 148, 302
curve fitting 120
curved surface 232
CvDefPoly class 24

cylinder 199

Index

D

dashed line 29, 342

data files for 3D objects 190

determinant 35

device coordinates 5, 8

distance between point and line 50

*distance*256

dodecahedron 306

dot product 34

double buffering 175, 354

double-step line-drawing 97

Dragon curve 255

drawArc 345

drawLine 2

drawOval 102

Index

E

Euler's theorem 302

event listener 282

Export HP-GL command 209

expression evaluator 327

eye coordinates 146

eye position 140

Index

F

Faces (in 3D data files) 232

File menu 209, 232

files for 3D objects 190

fillet 60

fillPolygon 221, 354

fillRect 7

foreground color 6

fractal 249

frame 5

function of two variables 244,

Index

G

getSize 5

globe model 215, 312

grammar 258

Index

H

Hewlett-Packard Graphics Language 207

hexahedron 302

hidden-face elimination 219

hidden-line elimination 177

Hilbert curve 255

holes in faces 192

hollow cylinder 199

hollow prism 199

horizon 140

Horner's rule 129

HP-GL 207

Index

I

icosahedron 306
image size 148
inner class 282
inner product 34
input file for 3D objects 190
inscribed circle 60
insidePolygon 47
insideTriangle 44
interpolation for *z* 235
interpolation for z 277

inverse matrix 73

isotropic mapping mode 18

Index

J

JDK 2

Julia 274

Index

K

Koch 250

Index

L

Lindenmayer 254

line clipping 107

line drawing 92

line through two points 36

linear combination of vectors 33

linear transformation 65

lines of latitude 312

lines of longitude 313

listener 281

logical coordinates 8

Logo 251

L-systems 254

Index

M

Mandelbrot 249, 264

matrix 64

matrix product 64

menu 231

mouse 21

mouse button 75

MouseAdapter 284

MouseListener 283

Index

N

nonconvex solid 225

normal vector 220

Index

O

Obj3D class 160

octahedron 302, 305

orientation 38

orthographic projection 146, 220

Index

P

painter's algorithm 226

panel 202

parsing 336

perpendicular bisector 344

perspective transformation 141, 146

pixel 5

plane through three points 36

platonic solid 301

point in polygon 45

point in triangle 44
point on line 47
Point2D 25
Point3D 83
polygon 21, 41
polygon clipping 113
Polygon3D class 162
printer output via HP-GL 208
prism 199
projection of point on line 51

Index

Q

quicksort 231

Index

R

recursive descent parsing 335

reflection 69

reflex vertex 41

regular polyhedron 301

right-handed coordinate system 33

Rokne 97

Rotate3D 84

rotation 66, 74

rotation (3D) 79

rotation about arbitrary axis 80
rotation matrix (3D) 81
rotation matrix 66
rounding-off errors 13
rubber banding 271

Index

S

scaling 69

screen coordinates 147, 220

semi-sphere 216

setColor 221

setXORMode 106

shearing 70

shift vector 72

Sierpinski 255

silhouette 245

smooth curve 128

snowflake 253

sorting triangles 227, 231

sphere 312, 363

spherical coordinates 142

spiral of beams 323

staircase 217

string grammar 253

superpixel 135

sutherland-hodgman polygon clipping 113

Index

T

tetrahedron 302
thickness of line 7
tolerances 181

Tools2D class 54

torus 217, 319, 364

transformation matrix 65

translation 71
tree (fractal) 258

tree of Pythagoras 60
Triangle 53

triangulate 53

turtle graphics 251

Index

U

unit vector 33

Index

V

vector 32

Vector 32

Vector (in Java) 32

Vector (in Java) 33

vector product 37

viewing matrix 143

viewpoint 143

viewing transformation 141

viewpoint menu commands 231

visible lines 178

Index

W

WindowAdapter 284

windowClosing 283

WindowListener 283

wire-frame model 148

world coordinates 141

Wu 97

Wyvill 97

Index

X

XOR paint mode 106

Index

Y

y-axis, direction 8

Index

Z

Z-buffer algorithm 234
zooming 271

List of Figures

Chapter 1: Elementary Concepts

Figure 1.1: Largest possible rectangle and canvas dimensions

Figure 1.2: Pixels as coordinates in an 8 × 4 canvas (with *maxX* = 7 and *maxY* = 3)

Figure 1.3: Small filled regions

Figure 1.4: Logical and device coordinates, based on *ymax* = 16

Figure 1.5: Triangles drawn inside each other

Figure 1.6: Pixels lying 10/9 logical units apart

Figure 1.7: Logical coordinates with anisotropic mapping mode

Figure 1.8: Windows after changing their sizes

Figure 1.9: Polygon defined by a user

Figure 1.10: Polygon still in the center of the window after resizing the window

Figure 1.11: A chessboard of squares

Figure 1.12: Concentric squares

Figure 1.13: Hexagons

Figure 1.14: Dashed lines

Chapter 2: Applied Geometry

Figure 2.1: Two equal vectors

Figure 2.2: Vector addition

Figure 2.3: Right-handed coordinate system

Figure 2.4: Vector product a × b

Figure 2.5: Counter-clockwise and clockwise orientation of A, B, C

Figure 2.6: Using vectors a

and b instead of triangle edges CA and CB

Figure 2.7: Two simple and two non-simple polygons

Figure 2.8: Orientation used to test if P lies within triangle ABC

Figure 2.9: Polygon and half-line starting at P

Figure 2.10: Projection P′ of P on line AB between A and B

Figure 2.11: Distance between point P and line *l*

Figure 2.12: Cutting off a triangle

Figure 2.13: Triangulation of a polygon

Figure 2.14: Fillet

Figure 2.15: Incircle and excircles of triangle ABC

Figure 2.16: Tree of Pythagoras

Chapter 3: Geometrical Transformations

Figure 3.1: Rotation of unit vectors

Figure 3.2: Arrow before and after rotation through 120° about the origin

Figure 3.3: Shearing effects (dashed lines) on a square object (solid lines)

Figure 3.4: A homogeneous coordinate system with the plane $W = 1$

Figure 3.5: Arrow before and after rotation through 30° about a point selected by the user

Figure 3.6: (a) Translation; (b) change of coordinates

Figure 3.7: Rotations about coordinate axes

Figure 3.8: Rotation about a vector starting at O

Figure 3.9: Rotation of a cube about the axis AB

Chapter 4: Some Classic Algorithms

Figure 4.1: Grid points approximating a line segment

Figure 4.2: Slope *m* **and error** *d*

Figure 4.3: Four double-step patterns when $0 \leq$ slope ≤ 1

Figure 4.4: Choice of patterns based on initial error *d* and slope *m*

Figure 4.5: Arc PQ in sector O of a circle with origin O and

radius *r*

Figure 4.6: Pixels that approximate the arc PQ

Figure 4.7: Line segment PQ to be clipped

Figure 4.8: Code values

Figure 4.9: Demonstration of program *ClipLine.java*

Figure 4.10: Nine polygon vertices defined; final edge not yet drawn

Figure 4.11: Polygon completed and clipped

Figure 4.12: The Sutherland–Hodgman algorithm

Figure 4.13: Bézier curve based on four points

Figure 4.14: Constructing points for two smaller curve segments

Figure 4.15: A constructed Bézier curve

Figure 4.16: Velocity at the points P_0 and P_3

Figure 4.17: Single B-spline segment, based on four points

Figure 4.18: B-spline curve consisting of five curve segments

Figure 4.19: Bresenham algorithms for a line and for a circle (see also Figures 4.1 and 4.6)

Chapter 5: Perspective

Figure 5.1: Vanishing points on the horizon

Figure 5.2: (a) Eye nearby; (b) eye far away

Figure 5.3: Spherical coordinates of viewpoint E

Figure 5.4: Eye-coordinate system

Figure 5.5: Situation before rotation about the *z*-axis

Figure 5.6: Relating the sine and cosine of $-\theta - 90°$ to

those of θ

Figure 5.7: Situation before rotation about *x* -axis

Figure 5.8: Screen and eye coordinates

Figure 5.9: Image size and object size

Figure 5.10: Output of program *CubePers.java*

Figure 5.11: Vertex numbers and coordinate axes

Figure 5.12: Object and vertex numbers

Figure 5.13: Default view of object

Figure 5.14: Same object viewed from the back

Figure F.1: Dashed lines representing invisible edges

Figure 5.15: Snapshot of two cubes rotating about vertical axes

Chapter 6: Hidden-Line Elimination

Figure 6.1: Triangles and line segments

Figure 6.2: A non-convex polyhedron

Figure 6.3: Flowchart for *lineSegment* method

Figure 6.4: Test 1: both P and Q on the left of A, B and C

Figure 6.5: Test 2: PQ identical with AB

Figure 6.6: Test 3: P and Q nearer than A, B and C

Figure 6.7: Test 4: P and Q on a side of AB different from that of C

Figure 6.8: Test 5: triangle ABC on one side of PQ

Figure 6.9: Test 6: neither P nor Q behind plane ABC

Figure 6.10: Test 7: PQ behind triangle ABC

Figure 6.11: Test 8: P nearer than plane ABC

Figure 6.12: Test 9: I and J in front of plane ABC

Figure 6.13: Solid letter A

Figure 6.14: A polygon

Figure 6.15: A hollow cube

Figure 6.16: Solid pyramid in wire-frame cube

Figure 6.17: Vertex numbers of pyramid and cube

Figure 6.18: Internal representation of line segments

Figure 6.19: Hollow cylinders with $n = 6$ (left) and $n = 60$ (right)

Figure 6.20: Vertex numbering

Figure 6.21: Calculating vertex coordinates

Figure 6.22: Dialog box for (possibly hollow) cylinder

Figure 6.23: Letter X in italic

Figure 6.24: The Export HP-GL menu item

Figure 6.25: Three beams

Figure 6.26: Line passing through the center of a square

Figure 6.27: Two thin square rings

Figure F.2: One of the four faces for the square rings of Figure 6.27

Figure 6.28: Hidden lines represented by dashed lines

Figure 6.29: Two open books; number of sheets: 4 on the left and 150 on the right

Figure 6.30: A semi-sphere

Figure 6.31: A cube of cubes

Figure 6.32: Two tori

Figure 6.33: A spiral staircase

Chapter 7: Hidden-Face Elimination

Figure 7.1: Result of back-face culling

Figure 7.2: Vector s, pointing to the sun, and normal vector n of a face

Figure 7.3: Beams, each of which partly obscures another

Figure 7.4: Program *Painter.java* applied to file *letterL.dat*

Figure 7.5: Sphere and cone

Figure 7.6: Triangle ABC and scan line LR

Figure 7.7: Illustration of more efficient version

Figure 7.8: Z-buffer algorithm applied to three beams

Figure 7.9: Painter's algorithm failing

Figure 7.10: Function of two variables

Figure 7.11: Point P belonging to triangles of very different colors

Figure 7.12: Geometrical interpretation of x, n and *h*, where *h* is negative

Figure F.3: Object nearby: two inner faces visible

Figure F.4: The same object far away: two inner faces invisible

Figure 7.13: Two rotating cubes, generated by back-face culling

Figure 7.14: Steps

Chapter 8: Fractals

Figure 8.1: Three generations of the Koch curve

Figure 8.2: Koch snowflakes of generations 3, 5 and 7

Figure 8.3: Dragon curves: 1st, 2nd, 3rd, 4th, 5th and 11th generations

Figure 8.4: Dragon curve of 8th generation, rounded corners

Figure 8.5: Hilbert curve (5th generation) and Sierpinski

arrowhead (7th generation)

Figure 8.6: Second generation islands

Figure 8.7: Examples of fractal trees: Tree1 (4th generation), Tree2 (5th generation) and Tree3 (4th generation)

Figure 8.8: Mandelbrot set and magnified detail

Figure 8.9: Cropping and zooming in

Figure 8.10: Result of cropping and zooming in

Figure 8.11: Julia set, obtained by using $c = -0.76 + 0.084i$

Appendix A: Linear Interpolation of 1/z

Figure A.1: Central projection of point P on screen

Figure A.2: Linear interpolation applied to inverse values

Appendix E: Some Applications

Figure E.1: A tetrahedron: (a) inside a cube; (b) cube omitted; (c) after rotation

Figure E.2: Octahedron

Figure E.3: Icosahedron and dodecahedron as reciprocal polyhedra

Figure E.4: Approximations of a sphere: (a) $n = 6$;(b) $n = 30$

Figure E.5: Dividing a triangle into four smaller ones

Figure E.6: Icosahedron and three other polyhedra derived from it by program *SphTria.java*: (a) 20 faces (see Section E.1); (b) 80 faces; (c) 320 faces; (d) 1280 faces

Figure E.7: Octahedron and three other polyhedra derived from it by program *SphTria.java*: (a) 8 faces (see Section E.1); (b) 32 faces; (c) 128 faces; (d) 512 faces

Figure E.8: Torus (n = 30 and R = 2.5)

Figure E.9: Basic circles of a torus

Figure E.10: Vertex numbers of first beam

Figure E.11: Spirals of beams

Figure E.12: Surface of a function $z = f(x, y)$ as specified by (E.2) and (E.3)

Figure E.13: Dialog box for program Func.java

Figure E.14: Two triangles with an invisible common edge forming a rectangle

Appendix F: Hints and Solutions to Exercises

Figure F.1: Dashed lines representing invisible edges

Figure F.2: One of the four faces for the square rings of Figure 6.27

Figure F.3: Object nearby: two inner faces visible

Figure F.4: The same object far away: two inner faces invisible

Colour Plates

Plate 1: Fillet or rounded corner, Exercise 2.8

Plate 2: Inscribed circle and three excircles of triangle, Exercise 2.9

Plate 3: Tree of Pythagoras, Exercise 2.10

Plate 4: Demonstration of Bresenham's algorithm, Exercise 4.6

Plate 5: Two colored cubes, captured when rotating

independently, Exercise 7.3

Plate 6: Three beams partly hiding each other, see Sections 6.7, 7.3 and 7.4

Plate 7: Beams in a spiral, see Section E4, Appendix E

Plate 8: An open book, see Exercise 6.5

Plate 9: Solid letter A as an object with a hole, see Section 6.4

Plate 10: A cube of cubes, Exercise 6.8

Plate 11: Dodecahedron, see Section E1, Appendix E

Plate 12: Two tori, Exercise 6.9

Plate 13: A function of two variables, see Section E.5, Appendix E. The expression 10. sin(pow(x*x + y*y, 0.5))/(1 + pow(x*x + y*y, 0.2)) was supplied to program Func.java, with ranges and step sizes for x and y specified as .15(0.25)15

Plate 14: Tree with green leaves, Exercise 8.4

Plate 15: Sample output of program *MandelbrotZoom.java*, see Section 8.4

Plate 16: Julia set, as discussed at the end of Section 8.4

List of Code Examples

Chapter 1: Elementary Concepts

EXERCISES

Chapter 2: Applied Geometry

EXERCISES

Chapter 3: Geometrical Transformations

EXERCISES

Chapter 4: Some Classic Algorithms

EXERCISES

Chapter 5: Perspective

EXERCISES

Chapter 6: Hidden-Line Elimination

EXERCISES

Chapter 7: Hidden-Face Elimination

EXERCISES

Chapter 8: Fractals

EXERCISES